Engineers Opinion of Probable Cost Magnitude

LAKEVIEW CORPORATE PARK - OPEN SITE IMPROVEMENTS (TID SUMMARY)

10/17/2025

This opinion of cost is based on conceptual layouts. It will be necessary to refine this opinion of cost to reflect actual layouts and final engineering design. PEG assumes no liability for conceptual opinions of cost used for anything other than determining the approximate magnitude of construction costs.

Lot 60 (Parcel No.: 92-4-122-281-0260, 92-4-122-281-0230)			
Site Work to Achieve Development Ready		$	-
Raise North Property Line to Protect Sanitary Sewer Easement		$	56,467
Utility Relocation to allow Developmet (Storm Sewer Trunk Line, Sanitary Sewer Manhole's)		$	66,000
	Engineering, Investigations, Etc.	$	9,900
	Construction Admin	$	3,300
	Subtotal (No Contingency)	**$**	**135,667**
Lot 83 (Parcel No.: 92-4-122-321-0165) **| IN CONJUNCTION WITH LOT 103**			
Site Work to Achieve Development Ready		$	-
Extra Topsoil (Compared to Graded Business Park Lot)		$	111,758
Pond Construction (Over Excavation of Pond foorprint to get material to "build-up" elevation for positive drainage)		$	424,888
County Road Intersection Improvements (Split with 103)		$	250,000
Grade Transition Structural Elements to Protect Natural Resources and Utilities		$	75,000
ATC Easement Considerations (Sag Survey, Avoidance, etc.)		$	40,000
	Engineering, Investigations, Etc.	$	135,247
	Construction Admin	$	45,082
	Subtotal (No Contingency)	**$**	**1,081,975**
Lot 103 (Parcel No.: 92-4-122-321-0165) **| IN CONJUNCTION WITH LOT 83**			
Site Work to Achieve Development Ready		$	-
Extra Topsoil (Compared to Graded Business Park Lot)		$	68,227
Pond Construction (Over Excavation of Pond foorprint to get material to "build-up" elevation for positive drainage)		$	179,214
County Road Intersection Improvements (Split with 83)		$	250,000
Grade Transition Structural Elements to Protect Natural Resources and Utilities		$	60,000
Wetland Impact Permitting and Mitigation Credit Cost		$	130,000
ATC Easement Considerations (Sag Survey, Avoidance, etc.)		$	40,000
	Engineering, Investigations, Etc.	$	109,116
	Construction Admin	$	36,372
	Subtotal (No Contingency)	**$**	**872,930**
PARCEL 9 CSM #2273 (ZPG) (Parcel No.: 92-4-122-272-0502)			
Site Work to Achieve Development Ready		$	-
Extra Topsoil (Compared to Graded Business Park Lot)		$	87,994
Pond Construction (Over Excavation of Pond foorprint to get material to "build-up" elevation for positive drainage)		$	281,570
Floodplain Impact Permitting and Associated Impact (Permitting, Undercuts, Abutments, & Stabilization)		$	74,900
Wetland Impact Mitigation Costs (1.46 Acres Impact + Undercut)		$	337,898
Water Main Extension (1,200LF)		$	216,000
	Engineering, Investigations, Etc.	$	149,754
	Construction Admin	$	49,918
	Subtotal (No Contingency)	**$**	**1,198,033**
PROJECTED COST		$	3,288,606
	(15% Contingency)	**$**	**493,291**
TOTAL PROJECTED BUDGET		**$**	**3,781,897**