

ZILBER INDUSTRIAL 3

108TH STREET, LAKEVIEW CORPORATE PARK
PLEASANT PRAIRIE, WI

GOVERNING AGENCY CONTACTS

PLEASANT PRAIRIE VILLAGE HALL
9915 39TH STREET
PLEASANT PRAIRIE, WI 53158
OFFICE: (262) 694-1400

COMMUNITY DEVELOPMENT DEPARTMENT
ROBERT HANSON
- COMMUNITY DEVELOPMENT DIRECTOR
OFFICE: (262) 925-6713
EMAIL: rhanson@pleasantprairiewi.gov

FEGGY HERRICK
- ASSISTANT COMMUNITY DEVELOPMENT DIRECTOR
OFFICE: (262) 925-6716
EMAIL: fherrick@pleasantprairiewi.gov

MIRANDA STEINMETZ
- PLANNER II
OFFICE: (262) 925-6711
EMAIL: msteinmetz@pleasantprairiewi.gov

ENGINEERING DEPARTMENT
MATT FINEOUR, P.E.
- EXECUTIVE DIRECTOR OF INFRASTRUCTURE MANAGEMENT
OFFICE: (262) 925-6715
EMAIL: mfineour@pleasantprairiewi.gov

KURT DAVIDSEN, P.E.
- VILLAGE ENGINEER
OFFICE: (262) 925-6728
EMAIL: kdavidsen@pleasantprairiewi.gov

SARAH TOMCZYK
- ASSISTANT VILLAGE ENGINEER
OFFICE: (262) 948-8938
EMAIL: stomczyk@pleasantprairiewi.go

PUBLIC WORKS DEPARTMENT
TOM HUPP, P.E.
- DIRECTOR OF PUBLIC WORKS
ROGER PRANGE MUNICIPAL BUILDING
8600 GREEN BAY ROAD 53158
OFFICE: (262) 925-6768
EMAIL: thupp@pleasantprairiewi.gov

BUILDING INSPECTION DEPARTMENT
SANDRO PEREZ
- DIRECTOR OF BUILDING INSPECTIONS
OFFICE: (262) 925-6722
EMAIL: sperez@pleasantprairiewi.gov

FIRE & RESCUE DEPARTMENT
CRAIG ROEPKE
- CHIEF OF FIRE & RESCUE
9065 TERWALL TERRACE 53158
OFFICE: (262) 948-8975
EMAIL: croepke@pleasantprairiewi.gov

AARON LONGRIE
-ASSISTANT FIRE CHIEF
OFFICE: (262) 948-8975
EMAIL: alongrie@pleasantprairiewi.gov

WI DEPARTMENT OF NATURAL RESOURCES
ANDREA STERN
- WATER REGULATION/ZONING ENGINEER-ADV
OFFICE: 262-282-8654
EMAIL: andreastern@wisconsin.gov

PETER WOOD
- WATER RESOURCES ENGINEER
OFFICE: 262-884-2360
EMAIL: peterswood@wisconsin.gov

PUBLIC UTILITY CONTACTS

AMERICAN TRANSMISSION COMPANY
BRIAN MCGEE
OFFICE: 262-506-6895
EMAIL: bmcgee@atcllc.com
EMERGENCY NUMBER: (800) 972-5341

WISCONSIN D.O.T.
ART BAUMANN, TRAFFIC OPERATIONS ENGINEER
OFFICE: (262) 548-6707
EMAIL: art.bauman@dot.wi.gov

KEVIN KOEHNKE, PERMITS COORDINATOR
OFFICE: (262) 548-5891
EMAIL: kevinkoehnke@dot.wi.gov

KENOSHA COUNTY
GREGORY BOLDT
DIRECTOR/HIGHWAY COMMISSIONER
DIVISION OF HIGHWAYS - PUBLIC WORKS DEPARTMENT
OFFICE: 262.857.1810
EMAIL: GregoryBoldt@kenoshacounty.org

AT&T
BRENT LEWIS
OFFICE: 414.429.4214
EMAIL: bl5701@att.com

TDS TELECOM
SOUTHEAST WISCONSIN
OFFICE: 877.483.1142

TIME WARNER CABLE/SPECTRUM
STEVE CRAMER
CONSTRUCTION SUPERVISOR
OFFICE: 414.271.4045
EMAIL: steve.cramer@charter.com
EMERGENCY NUMBER: 800.672.2288

WEC ENERGY GROUP
JOEL BUROW
CEM MANAGER
OFFICE: 414.221.3192
EMAIL: joel.burrow@wecenergygroup.com

WE-ENERGIES
ALLIE KLAUINSKI
SENIOR SERVICE MANAGER
OFFICE: 262.595.3227
EMAIL: allieklauinski@we-energies.com

MICHAEL BAKER
CUSTOMER SERVICE MANAGER
OFFICE: 262-886-1041
EMAIL: michaelbaker@we-energies.com

HUSSAIN BIYJUERWALA
SENIOR ENGINEER
OFFICE: 262-886-1074
EMAIL: hussainbiyjuerwala@we-energies.com

BRANDON ERTS
GAS ENGINEERING
OFFICE: 414-221-3654
EMAIL: brandon.erts@we-energies.com

NATURAL GAS EMERGENCY: 800.261.5325

ELECTRICAL EMERGENCY: 800.662.4797

SHEET INDEX

TI TITLE SHEET

ARCHITECTURAL
A0.1 CODE SUMMARY
A1.1 SITE PLAN
A1.2 SITE DETAILS
A3.1 OVERALL BUILDING PLAN
A3.2 PARTIAL FLOOR PLAN
A3.3 PARTIAL FLOOR PLAN
A3.4 ENLARGED PLANS & NOTES
A3.5 SCHEDULES & NOTES
A4.1 EXTERIOR ELEVATIONS & FRAME TYPES
A5.1 WALL SECTIONS
A5.2 WALL SECTIONS
A5.3 WALL SECTIONS
A5.4 WALL SECTIONS & SECTION DETAILS
A6.1 PLAN DETAILS
A9.1 ROOF PLAN & DETAILS

STRUCTURAL
S0.1 STRUCTURAL NOTES
S0.2 STRUCTURAL NOTES
S0.3 SPECIAL INSPECTIONS
S1.0 FOUNDATION PLAN
S1.1 FOUNDATION PLAN
S2.0 ROOF FRAMING PLAN
S2.1 ROOF FRAMING PLAN
S6.0 FOUNDATION DETAILS
S6.1 FOUNDATION DETAILS
S6.5 FRAMING DETAILS
S6.6 FRAMING DETAILS

Conditionally
APPROVED
DEPT. OF SAFETY AND PROFESSIONAL SERVICES
DIVISION OF INDUSTRY SERVICES

Jennifer Zettler

SEE CORRESPONDENCE

Building
New Construction - SHELL only
DIS-032611817
CB-052600583-PRB
May 29, 2026

PROJECT DATA

APPLICABLE CODES:

BUILDING: 2021 INTERNATIONAL BUILDING CODE -AS MODIFIED BY THE WISCONSIN ENROLLED COMMERCIAL BUILDING CODE IN CHAPTER SPS 362.
ENERGY: 2021 INTERNATIONAL ENERGY CONSERVATION CODE (IECC) - SUBJECT TO THE MODIFICATIONS SPECIFIED IN THIS CHAPTER AND CH. SPS 363 IS INCORPORATED BY REFERENCE INTO CH6. SPS 361 TO 366.
MECHANICAL: 2021 INTERNATIONAL MECHANICAL CODE (IPC) - SUBJECT TO THE MODIFICATIONS SPECIFIED IN THIS CHAPTER AND CH. SPS 364 IS INCORPORATED BY REFERENCE INTO CH6. SPS 361 TO 366
PLUMBING: 2023 WISCONSIN PLUMBING CODE, SPS 361-387
ELECTRIC: 2011 NEC, SUBJECT TO THE MODIFICATIONS SPECIFIED IN CH. SPS 316
FUEL/GAS: THE INTERNATIONAL FUEL GAS CODE (FGC) - 2021, SUBJECT TO THE MODIFICATIONS SPECIFIED IN THIS CHAPTER AND CH. SPS 369 IS INCORPORATED BY REFERENCE INTO CH6. SPS 361 TO 366.

BUILDING CLASSIFICATION:

MIXED USE NON-SEPARATED, UNLIMITED AREA BUILDING

S-1 (MODERATE-HAZARD STORAGE)
F-1 (MODERATE-HAZARD FACTORY)
B (BUSINESS)

CONSTRUCTION CLASSIFICATION:

TYPE IIB - UNPROTECTED WITH AUTOMATIC SPRINKLER SYSTEM

FOOTPRINT AREA: 152,236 SF.
GROSS RENTABLE: 152,334 SF.

GENERAL NOTES


1. DO NOT SCALE DRAWINGS.
2. CONTRACTOR SHALL FIELD VERIFY AND BECOME THOROUGHLY FAMILIAR WITH ALL CONDITIONS AND DIMENSIONS.
3. EACH CONTRACTOR SHALL REVIEW COMPLETE PLANS FOR RELATED WORK.
4. ALL WORK SHALL BE IN COMPLINCE WITH STATE AND LOCAL CODES FOR RESPECTIVE TRADES.

ABBREVIATIONS

ALT	ALTERNATE	HDWR	HARDWARE
A/E	ARCHITECT/ENGINEER	HM	HOLLOW METAL
AFF	ABOVE FINISH FLOOR	HT	HEIGHT
ALUM	ALUMINUM	HW	HOT WATER
BD	BOARD	INT	INTERIOR
B/O	BOTTOM OF	INSUL	INSULATION
CPT	CARPET	JT	JOINT
℄	CENTER LINE	LAV	LAVATORY
CLG	CEILING	MFR	MANUFACTURER
CJ	CONTROL JOINT	MIN	MINIMUM
CMU	CONCRETE MASONRY UNIT	MO	MASONRY OPENING
CONC	CONCRETE	MTL	METAL
CONT	CONTINUOUS	NIC	NOT IN CONTRACT
CO	CLEAN OUT	NTS	NOT TO SCALE
CW	COLD WATER	OC	ON CENTER
CT	CERAMIC TILE	OFCI	OWNER FURNISHED, CONTRACTOR TO INSTALL
DBL	DOUBLE		
DF	DRINKING FOUNTAIN		
DIA	DIAMETER	OPP	OPPOSITE
DIM	DIMENSION	PLYWD	PLYWOOD
DN	DOWN	PL	PLASTIC LAMINATE
DR	DOOR	PL	PLATE
DS	DOWNSPOUT	PT	PORCELAIN TILE
DTL	DETAIL	QT	QUARRY TILE
DWG	DRAWING	REQ'D	REQUIRED
EA	EACH	RO	ROUGH OPENING
EIFS	EXTERIOR INSULATION AND FINISH SYSTEM	SHT	SHEET
		SV	SHEET VINYL
EL	ELEVATION	SIM	SIMILAR
EJ	EXPANSION JOINT	SS	SOLID SURFACE
EQ	EQUAL	SST	STAINLESS STEEL
EQUIP	EQUIPMENT	STD	STANDARD
EXIST	EXISTING	SAT	SUSPENDED ACOUSTIC TILE CEILING
EXT	EXTERIOR		
EWC	ELECTRIC WATER COOLER	TBD	TO BE DETERMINED
FEC	FIRE EXTINGUISHER CABINET	TEMP	TEMPORARY
		T/O	TOP OF
FIN	FINISH	T&G	TONGUE AND GROOVE
FD	FLOOR DRAIN	TYP	TYPICAL
FLR	FLOOR	UNO	UNLESS NOTED OTHERWISE
FRP	FIBERGLASS REINFORCED PLASTIC	VCT	VINYL COMPOSITION TILE
		VB	VINYL BASE
GA	GAUGE	VIF	VERIFY IN FIELD
GALV	GALVANIZED	WD	WOOD
GYP BD	GYPSUM BOARD	WWF	WELDED WIRE FABRIC

LOCATION MAP

PLEASANT PRAIRIE, WI



ZILBER PROPERTY GROUP

CLIENT:
ZILBER PROPERTY GROUP
710 N. PLANKINGTON AVENUE
MILWAUKEE, WI 53203
ATTN: JASON LUEDERS

Partners in Design ARCHITECTS

ARCHITECT:
PARTNERS IN DESIGN ARCHITECTS
2610 LAKE COOK ROAD, SUITE 280
RIVERWOODS, IL 60015
PHONE: 847.940.03300
ATTN: WERNER BRISKE, AIA
OR
JEREMY HALL, AIA

WISCONSIN
WERNER H. BRISKE
ARCHITECT
LIC. EXP. DATE: 07.31.26
DATE: 05.20.26

PINNACLE ENGINEERING GROUP LLC

CIVIL & LANDSCAPING ENGINEER:
PINNACLE ENGINEERING GROUP
15850 WEST BLUEMOUND ROAD, SUITE 210
BROOKFIELD, WI 53005
PHONE: 262.754.8888
FAX: 262.754.8850
ATTN: ADAM ARTZ
OR
ANDY SHOAF

raSmith


STRUCTURAL ENGINEER:
R.A. SMITH NATIONAL, INC.
16745 WEST BLUEMOUND ROAD, SUITE 200
BROOKFIELD, WI 53005
PHONE: 262.317.3334
ATTN: STEVE ROLOFF

Partners in Design ARCHITECTS

ZILBER INDUSTRIAL 3
PROJECT NUMBER: 522.22.031

CONSTRUCTION SET

ISSUE DATE: 03.20.26
REVISION DATE: 05.20.26



1 A0.1 FIRST FLOOR PLAN
1/32" = 1'-0"

TRUE NORTH

PLAN NORTH

APPLICABLE CODES:

BUILDING CODE: INTERNATIONAL BUILDING CODE - 2021 AS MODIFIED BY THE WISCONSIN ENROLLED COMMERCIAL BUILDING CODE IN CHAPTER SPS 362.

CHAPTER 3 - USE AND OCCUPANCY CLASSIFICATION

THIS BUILDING WILL BE CLASSIFIED AS A FULLY SPRINKLERED, NON-SEPARATED 'S-1', 'F-1' & 'B' USE. DEPENDING ON USE WHEN FUTURE OCCUPANCY IS DETERMINED, IT WILL INCORPORATE NON-SEPARATED USES PER SECTION 508.3.1 INCLUDING BUSINESS OFFICES WHICH ARE CLASSIFIED AS BUSINESS 'B' USE GROUP. THE BUILDING WILL BE CURRENTLY CLASSIFIED AS 'F-1' - THE MOST RESTRICTIVE OCCUPANCY.

CHAPTER 5 - GENERAL BUILDING HEIGHTS AND AREAS

THE BUILDING IS CONSTRUCTED WITH UNPROTECTED STEEL COLUMNS, JOISTS, BEAMS, AND ROOF DECK, THEREFORE THE CONSTRUCTION CLASSIFICATION FOR THE BUILDING IS TYPE II-B. THE BUILDING IS FULLY SPRINKLERED.

TABLE 504.3 'ALLOWABLE BUILDING HEIGHT IN FEET ABOVE GRADE PLANE'
OCCUPANCY GROUPS S-1, F-1, B FOR CONSTRUCTION TYPE IIB: 75'-0"

TABLE 506.2 'ALLOWABLE AREA FACTOR IN SQUARE FEET'

OCCUPANCY GROUP S-1: 70,000 SF MAXIMUM FOR SINGLE STORY SPRINKLERED BUILDING.
OCCUPANCY GROUP F-1: 62,000 SF MAXIMUM FOR SINGLE STORY SPRINKLERED BUILDING.
OCCUPANCY GROUP B: 92,000 SF MAXIMUM FOR SINGLE STORY SPRINKLERED BUILDING.

ACTUAL BUILDING:	39'-2" HIGH
	SINGLE STORY
	152,334 SF

SECTION 507.4 'SPRINKLERED, ONE-STORY BUILDINGS'

THE AREA OF A GROUP A-4 BUILDING NO MORE THAN ONE STORY ABOVE GRADE PLANE OF OTHER THAN TYPE V CONSTRUCTION, OR THE AREA OF A GROUP B, F, M OR S BUILDING NOT MORE THAN ONE STORY ABOVE GRADE PLANE OF ANY CONSTRUCTION TYPE, SHALL NOT BE LIMITED WHERE THE BUILDING IS PROVIDED WITH AN AUTOMATIC SPRINKLER SYSTEM THROUGHOUT IN ACCORDANCE WITH SECTION 903.3.1.1 AND IS SURROUNDED AND ADJOINED BY PUBLIC WAYS OR YARDS NOT LESS THAN 60 FEET IN WIDTH.

THIS BUILDING QUALIFIES AS AN UNLIMITED AREA BUILDING.

CHAPTER 6 - TYPES OF CONSTRUCTION

SECTION 602.2 'TYPES I AND II'
TYPES I AND II CONSTRUCTION ARE THOSE TYPES OF CONSTRUCTION IN WHICH THE BUILDING ELEMENTS SPECIFIED IN TABLE 601 ARE OF NONCOMBUSTIBLE MATERIALS, EXCEPT AS PERMITTED IN SECTION 603 AND ELSEWHERE IN THIS CODE.

TABLE 601 'FIRE-RESISTANCE RATING REQUIREMENTS FOR BUILDING ELEMENTS (HOURS)'

BUILDING ELEMENTS		
PRIMARY STRUCTURAL FRAME	INCLUDING COLUMNS, GIRDERS, TRUSSES	0 HOURS / NONCOMBUSTIBLE
BEARING WALLS	EXTERIOR (>30')	0 HOURS / NONCOMBUSTIBLE
	INTERIOR	0 HOURS / NONCOMBUSTIBLE
NONBEARING WALLS AND PARTITIONS	EXTERIOR (>30')	0 HOURS / NONCOMBUSTIBLE
	INTERIOR	0 HOURS / NONCOMBUSTIBLE
FLOOR CONSTRUCTION AND ASSOCIATED SECONDARY STRUCTURAL MEMBERS	INCLUDING SUPPORTING BEAMS AND JOIST	0 HOURS / NONCOMBUSTIBLE
ROOF CONSTRUCTION AND ASSOCIATED SECONDARY STRUCTURAL MEMBERS	INCLUDING SUPPORTING BEAMS AND JOIST	0 HOURS / NONCOMBUSTIBLE

THIS BUILDING IS CLASSIFIED AS TYPE II-B.

CHAPTER 7 - FIRE AND SMOKE PROTECTION FEATURES

TABLE 716.2 "OPENING FIRE PROTECTION ASSEMBLIES, RATINGS AND MARKINGS"
OTHER FIRE BARRIERS REQUIRE A 45 MINUTE DOOR RATING.

A 45 MINUTE RATED DOOR IS PROVIDED AT THE FIRE PROTECTION ROOM.

CHAPTER 8 - INTERIOR FINISHES

SECTION 803.1.1 'INTERIOR WALL AND CEILING FINISH MATERIALS TESTED IN ACCORDANCE WITH NFPA 286'
INTERIOR WALL AND CEILING FINISHES SHALL BE CLASSIFIED IN ACCORDANCE WITH NFPA 286 AND COMPLY WITH SECTION 803.1.1.1. MATERIALS COMPLYING WITH SECTION 803.1.1.1 SHALL BE CONSIDERED TO ALSO COMPLY WITH THE REQUIREMENTS OF CLASS A.

SECTION 803.1.1.1 'ACCEPTANCE CRITERIA FOR NFPA 286'
THE INTERIOR FINISH SHALL COMPLY WITH THE FOLLOWING:
1. DURING THE 40kW EXPOSURE, FLAMES SHALL NOT SPREAD TO THE CEILING.
2. THE FLAME SHALL NOT SPREAD TO THE OUTER EXTREMITY OF THE SAMPLE ON ANY WALL OR CEILING.
3. FLASHOVER, AS DEFINED IN NFPA 286, SHALL NOT OCCUR.
4. THE PEAK HEAT RELEASE RATE THROUGHOUT THE TEST SHALL NOT EXCEED 800 KW.
5. THE TOTAL SMOKE RELEASED THROUGHOUT THE TEST SHALL NOT EXCEEED 1,000 SM.

CLASS A: FLAME SPREAD 0 - 25, SMOKED DEVELOPED 0 - 450
CLASS B: FLAME SPREAD 26 - 75, SMOKED DEVELOPED 0 - 450
CLASS C: FLAME SPREAD 76 - 200, SMOKED DEVELOPED 0 - 450

SECTION 803.13' INTERIOR FINISH REQUIREMENTS BASED ON OCCUPANCY'
INTERIOR WALL AND CEILING FINISH SHALL HAVE A FLAME SPREAD RATING NOT GREATER THAN THAT SPECIFIED IN TABLE 803.13 FOR THE GROUP AND LOCATION DESIGNATED. INTERIOR WALL AND CEILING FINISH MATERIALS TESTED IN ACCORDANCE WITH NFPA 286 AND MEETING THE ACCEPTANCE CRITERIA OF SECTION 803.1.1.1, SHALL BE PERMITTED TO BE USED WHERE A CLASS A CLASSIFICATION IN ACCORDANCE WITH ASTM E 84 OR UL 723 IS REQUIRED.

TABLE 803.13 REQUIRES THE FOLLOWING IN A SPRINKLERED BUILDING.
INTERIOR EXIT STAIRWAYS AND RAMPS AND EXIT PASSAGEWAYS - B
CORRIDORS AND ENCLOSURE FOR EXIT ACCESS STAIRWAYS AND RAMPS - B
ROOMS AND ENCLOSED SPACES - C

SECTION 803.14 'STABILITY'
INTERIOR FINISH MATERIALS REGULATED BY THIS CHAPTER SHALL BE APPLIED OR FASTENED IN SUCH A MANNER THAT THE MATERIALS WILL NOT READILY BECOME DETACHED WHERE SUBJECTED TO ROOM TEMPERATURES OF 200 DEGREES FAHRENHEIT FOR NOT LESS THAN 30 MINUTES.

SECTION 803.15.4 'MATERIALS'
AN INTERIOR WALL OR CEILING FINISH THAT ARE IS MORE THAN 0.25 INCH THICK SHALL BE APPLIED DIRECTLY TO ONTO THE WALL, CEILING OR STRUCTURAL ELEMENT WITHOUT THE USE OF FURRING STRIPS AND SHALL NOT BE SUSPENDED AWAY FROM THE BUILDING ELEMENT TO WHICH THAT FINISH MATERIAL IT IS APPLIED.

SECTION 803.1.2 'INTERIOR WALL AND CEILING FINISH MATERIALS TESTED IN ACCORDANCE WITH ASTM E-84 OR UL 723'
INTERIOR WALL AND CEILING FINISHES SHALL BE CLASSIFIED IN ACCORDANCE WITH ASTM E-84 OR UL 723. SUCH INTERIOR FINISH MATERIALS SHALL BE GROUPED IN THE FOLLOWING CLASSES IN ACCORDANCE WITH THEIR FLAME SPREAD AND SMOKE-DEVELOPED INDICES.

SECTION 804.4.2 - MINIMUM CRITICAL RADIANT FLUX.
EXCEPTION: WHERE A BUILDING IS EQUIPPED THROUGHOUT WITH AN AUTOMATIC SPRINKLER SYSTEM IN ACCORDANCE WITH SECTION 903.1.1 OR 903.3.1.2, CLASS II MATERIALS ARE PERMITTED IN ANY AREA WHERE CLASS I MATERIALS ARE REQUIRED, AND MATERIALS COMPLYING WITH DOC FF-1 "PILL TEST" (CPSC 16 CFR PART 1630) OR WITH ASTM D2859 ARE PERMITTED IN ANY AREA WHERE CLASS II MATERIALS ARE REQUIRED.

CHAPTER 9 - FIRE PROTECTION SYSTEMS

THIS BUILDING IS FULLY SPRINKLERED IN ACCORDANCE WITH SECTION 903.

CHAPTER 10 - MEANS OF EGRESS

SECTION 1004: 'OCCUPANT LOAD'
TABLE 1004.5 'MAXIMUM FLOOR AREA ALLOWANCES PER OCCUPANT'
WAREHOUSE AREA = 500 GROSS
152,334 GROSS SF (1 OCCUPANT / 500 GROSS) = 305 OCCUPANTS

SECTION 1005: 'MEANS OF EGRESS SIZING'
TABLE 1005.3.2 'OTHER EGRESS COMPONENTS'
THE CAPACITY, IN INCHES, OF MEANS OF EGRESS COMPONENTS OTHER THAN STAIRWAYS SHALL BE CALCULATED BY MULTIPLYING THE OCCUPANT LOAD SERVED BY SUCH COMPONENT BY A MEANS OF EGRESS CAPACITY FACTOR OF 0.2 INCH PER OCCUPANT.
EXCEPTION 1: FOR OTHER THAN GROUP H AND I-2 OCCUPANCIES, THE CAPACITY, IN INCHES, OF MEANS OF EGRESS COMPONENTS OTHER THAN STAIRWAYS SHALL BE CALCULATED BY MULTIPLYING THE OCCUPANT LOAD SERVED BY SUCH COMPONENT BY A MEANS OF EGRESS CAPACITY FACTOR OF 0.15 INCH PER OCCUPANT IN BUILDINGS EQUIPPED THROUGHOUT WITH AN AUTOMATIC SPRINKLER SYSTEM INSTALLED IN ACCORDANCE WITH SECTION 903.3.1.1 OR 903.3.1.2 AND AN EMERGENCY VOICE/ALARM COMMUNICATIONS SYSTEM IN ACCORDANCE WITH SECTION 907.5.2.2.

CALCULATION WITH SPRINKLER SYSTEM = 0.2 INCHES PER OCCUPANT
305 OCCUPANTS (0.15" / OCCUPANT) = 45.75" OF EGRESS WIDTH (544" PROVIDED)

EGRESS WIDTHS COMPLY WITH SECTION 1004.

SECTION 1006 'NUMBER OF EXITS AND EXIT ACCESS DOORWAYS'
TABLE 1006.2.1 'SPACES WITH ONE EXIT OR EXIT ACCESS DOORWAY'
IN OCCUPANCIES 'F-1', 'S-1', 'B' THE COMMON PATH OF EGRESS TRAVEL SHALL NOT EXCEED 100 FEET WITH A SPRINKLER SYSTEM

SECTION 1009.7 'EXTERIOR AREA FOR ASSISTED RESCUE'
EXTERIOR AREAS FOR ASSISTED RESCUE SHALL BE ACCESSED BY AN ACCESSIBLE ROUTE FROM THE AREA SERVED. WHERE THE EXIT DISCHARGE DOES NOT INCLUDE AN ACCESSIBLE ROUTE FROM AN EXIT LOCATED ON THE LEVEL OF EXIT DISCHARGE TO A PUBLIC WAY, AN EXTERIOR AREA OF ASSISTED RESCUE SHALL BE PROVIDED ON THE EXTERIOR LANDING IN ACCORDANCE WITH SECTIONS 1009.7.1 THROUGH 1009.7.4.

SECTION 1009.7.2 'SEPARATION'
EXTERIOR WALLS SEPARATING THE EXTERIOR AREA OF ASSISTED RESCUE FROM THE INTERIOR OF THE BUILDING SHALL HAVE A MINIMUM FIRE-RESISTANCE RATING OF 1 HOUR, RATED FOR EXPOSURE TO FIRE FROM THE INSIDE. THE FIRE-RESISTANCE-RATED EXTERIOR WALL CONSTRUCTION SHALL EXTEND HORIZONTALLY 10 FEET BEYOND THE LANDING ON EITHER SIDE OF THE LANDING OR EQUIVALENT FIRE-RESISTANCE-RATED CONSTRUCTION IS PERMITTED TO EXTEND OUT PERPENDICULAR TO THE EXTERIOR WALL 4 FEET MINIMUM ON THE SIDE OF THE LANDING. THE FIRE-RESISTANCE-RATED CONSTRUCTION SHALL EXTEND VERTICALLY FROM THE GROUND TO A POINT 10 FEET ABOVE THE FLOOR LEVEL OF THE AREA FOR ASSISTED RESCUE OR TO THE ROOF LINE, WHICHEVER IS LOWER. OPENINGS WITHIN SUCH FIRE-RESISTANCE-RATED EXTERIOR WALLS SHALL BE PROTECTED IN ACCORDANCE WITH SECTION 716.
EXCEPTION: THE FIRE-RESITANCE RATING AND OPENING PROTECTIVES ARE NOT REQUIRED IN THE EXTERIOR WALL WHERE THE BUILDING IS EQUIPPED THROUGHOUT WITH AN AUTOMATIC SPRINKLER SYSTEM INSTALLED IN ACCORDANCE WITH SECTION 903.1.1 OR 903.1.2.

SECTION 1017 'EXIT ACCESS TRAVEL DISTANCE'
TABLE 1017.2 'EXIT ACCESS TRAVEL DISTANCE'
IN OCCUPANCIES 'F-1', 'S-1', 'B' THE EXIT ACCESS TRAVEL DISTANCE SHALL BE 250 FEET WITH A SPRINKLER SYSTEM.

SECTION 1017.2.2 'GROUPS F-1 AND S-1 INCREASE'
THE MAXIMUM EXIT ACCESS TRAVEL DISTANCE SHALL BE 400 FEET IN GROUP F-1 OR S-1 OCCUPANCIES WHERE ALL OF THE FOLLOWING CONDITIONS ARE MET:
1. THE PORTION OF THE BUILDING CLASSIFIED AS GROUP F-1 OR S-1 IS LIMITED TO ONE STORY IN HEIGHT
2. THE MINIMUM HEIGHT FROM THE FINISHED FLOOR TO THE BOTTOM OF THE CEILING OR ROOF SLAB OR DECK IS 24 FEET.
3. THE BUILDING IS EQUIPPED THROUGHOUT WITH AN AUTOMATIC SPRINKLER SYSTEM IN ACCORDANCE WITH SECTION 903.3.1.1

SECTION 1017.3 'MEASUREMENT'
EXIT ACCESS TRAVEL DISTANCE SHALL BE MEASURED FROM THE MOST REMOTE POINT OF EACH ROOM, AREA OR SPACE ALONG THE NATURAL AND UNOBSTRUCTED PATH OF HORIZONTAL AND VERTICAL EGRESS TRAVEL TO THE ENTRANCE OF AN EXIT. WHERE MORE THAN ONE EXIT IS REQUIRED, EXIT ACCESS TRAVEL DISTANCE SHALL BE MEASURED TO THE NEAREST EXIT.

TRAVEL DISTANCES COMPLY WITH SECTION 1017.

CHAPTER 29 - PLUMBING SYSTEMS

TABLE 2902.1 ' MINIMUM NUMBER OF PLUMBING FACILITIES'
TOTAL PROVIDED:
WATER CLOSETS: 2 PROVIDED
LAVATORIES: 2 PROVIDED
SERVICE SINK: 1 PROVIDED

TABLE 2902.1 WILL ACCOMMODATE AN OCCUPANCY OF 40

A PORTION OF THE SHELL BUILDING WILL ACCOMODATE AN INITIAL OCCUPANCY OF 40 OCCUPANTS INCLUDING BOTH EMPLOYEES AND CUSTOMERS WITH A MAXIMUM TRAVEL DISTANCE OF 500' FROM THE TOILET ROOM. THE REQUIRED PLUMBING FIXTURES WILL BE VERIFIED UNDER A FUTURE TENANT OCCUPANCY

© 2026 Partners in Design Architects, Inc.

REVISIONS:
1 05.20.26 UI DSPS COMMENTS


ZILBER INDUSTRIAL 3
10801 108th St, Lakeview Corporate Park, Pleasant Prairie, WI

CODE SUMMARY

2610 Lake Cook Road
Suite 280
Riverwoods, IL 60015
Ph.: (847) 940-0300
www.pdarchitects.com

Partners in Design ARCHITECTS

PROJECT NO.: 52222031
DRAWN BY: CTS
CHECKED BY: WHB
DATE: 03.20.26
SHEET NO.: A0.1



SITE DEVELOPMENT DATA

SITE AREA:	22.85± ACRES
PROPOSED BUILDING:	152,334 SF
TRUCK DOORS:	16 TOTAL DOCKS
DRIVE-IN DOORS:	2 D.I.D.
TRAILER PARKING:	15 TOTAL TRAILER STALLS
CAR PARKING SPACES:	89 SPACES (4 ADA SPACES)

GENERAL SITE NOTES

1. ALL SITE LIGHTING SHALL BE DIRECTED DOWNWARDS AND SHALL NOT GLARE ONTO ADJACENT PROPERTIES OR PUBLIC ROADWAYS.

2. TRUCKS/TRAILERS PARKED OUTSIDE OF THE FACILITY SHALL NOT BE USED AS A MEANS OF ADDITIONAL STORAGE AND/OR WAREHOUSING SPACE, EXCEPT FOR THOSE TRUCKS/TRAILERS THAT HAVE BEEN LOADED AND ARE AWAITING IMPENDING DELIVERY OR THOSE THAT ARE IN QUEUE AND ARE AWAITING IMPENDING UNLOADING PROCEDURES.

3. AT NO TIME SHALL THERE BE ANY OUTDOOR STORAGE OF PALLETS (WOODEN, PLASTIC, OR METAL), RECYCLING MATERIALS, GARBAGE, LANDSCAPING EQUIPMENT OR LANDSCAPE MATERIALS, ETC.

4. PROJECT PARCEL IS ZONED M-2, GENERAL MANUFACTURING DISTRICT.

5. THE LOCATION OF ALL CONSTRUCTION TRAILERS PARKED ON THE SITE DURING CONSTRUCTION ACTIVITIES SHALL BE APPROVED BY THE VILLAGE OF PLEASANT PRAIRIE. NO CONSTRUCTION TRAILERS SHALL BE PARKED IN VILLAGE, COUNTY, OR STATE RIGHTS-OF-WAY. ALL CONSTRUCTION RELATED SIGNAGE SHALL BE APPROVED AND PERMITTED BY THE VILLAGE.

6. MUNICIPAL UTILITIES SHALL NOT BE BURIED UNDER EARTH BERMS OR TREE LANDSCAPING.

7. ALL PARKING LOT AND PAVEMENT PARKING STRIPING SHALL BE WHITE.

1 / A1.1 SITE PLAN
1" - 50'-0"

© 2026 Partners in Design Architects, Inc.

REVISIONS:
1 05.20.26 WI DSPS COMMENTS


ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI

SITE PLAN


2610 Lake Cook Road
Suite 280
Riverwoods, IL 60015
Ph.: (847) 940-0300
www.pidarchitects.com

PartnersinDesign
ARCHITECTS


PROJECT NO.: 52222.031
DRAWN BY: JJH
CHECKED BY: WHB
DATE: 03.2026
SHEET NO.: A1.1



1 / A1.2 **TYP. H.C. PARKING STALL**
1/8" = 1'-0"




2 / A1.2 **SIGN MOUNTING DETAIL**
1" = 1'-0"



3 / A1.2 **EGRESS STAIR PLAN**
1/4" = 1'-0"







4 / A1.2 **BOLLARD SECTION**
1/2" = 1'-0"

© 2026 Partners in Design Architects, Inc.

REVISIONS:
1 Ø5.20.26 WI DSPS COMMENTS


ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI

SITE DETAILS

2610 Lake Cook Road
Suite 280
Riverwoods, IL 60015
Ph.: (847) 940-0300
www.pdarchitects.com

PartnersinDesign
ARCHITECTS


PROJECT NO.: 52222.031
DRAWN BY: CTS
CHECKED BY: WHB
DATE: Ø32Ø26
SHEET NO.: A1.2



1 A3.1 OVERALL BUILDING PLAN
1" = 30'-0"

TRUE NORTH

PLAN NORTH



KEY PLAN
NOT TO SCALE

TRUE NORTH

PLAN NORTH

© 2026 Partners in Design Architects, Inc.

REVISIONS:
1 05.20.26 UI DSPS COMMENTS


ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI

OVERALL BUILDING PLAN

2610 Lake Cook Road
Suite 280
Riverwoods, IL 60015
Ph.: (847) 940-0300
www.pdarchitects.com

PartnersinDesign
ARCHITECTS

PROJECT NO.: 52222.031
DRAWN BY: JJH
CHECKED BY: WHB
DATE: 032026
SHEET NO.: A3.1




PARTIAL FLOOR PLAN

1 / A3.2 — 1/16" = 1'-0"

TRUE NORTH — PLAN NORTH


WALL TYPES

1. ALL INTERIOR WALLS TO BE TYPE 'B' UNLESS NOTED OTHERWISE.
2. ALL EXTERIOR WALLS TO BE TYPE 'A' UNLESS NOTED OTHERWISE.
3. ALL GYPSUM BOARD TO BE 5/8" TYPE 'X' UNLESS NOTED OTHERWISE.
4. CONFIRM THE REQUIRED STUD THICKNESS PER SELECTED MANUFACTURER'S LOAD TABLES FOR THE WALL HEIGHTS INDICATED ON THE PLANS.
5. PROVIDE GYPSUM BOARD EXPANSION JOINTS AS REQUIRED PER MANUFACTURER'S RECOMMENDATIONS.




A
1. SEE EXTERIOR ELEVATIONS FOR HEIGHT

A1
1. 12" THICK




B
1. UL #385 - 1 HOUR RATED
2. EXTEND WALLS TO DECK


B1
1. UN-RATED
2. EXTEND WALLS TO DECK




C
1. EXTEND WALLS TO 11'-4" AFF.



D
1. EXTEND PRECAST WALL TO DECK
2. EXTEND INTERIOR GYPSUM BOARD WALL TO 11'-4" AFF.



E
1. EXTEND WAREHOUSE WALL TO 11'-4" AFF.
2. EXTEND TOILET ROOM WALL 6" ABOVE CEILING



KEY PLAN

NOT TO SCALE

TRUE NORTH — PLAN NORTH

© 2026 Partners in Design Architects, Inc.

REVISIONS:
1 05.20.26 WI DSPS COMMENTS


ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI

PARTIAL FLOOR PLAN

2610 Lake Cook Road
Suite 280
Riverwoods, IL 60015
Ph.: (847) 940-9300
www.pidarchitects.com


Partners in Design ARCHITECTS

PROJECT NO.: 522.22.031
DRAWN BY: JJH
CHECKED BY: WHB
DATE: 032026
SHEET NO.: A3.2




WALL TYPES


1. ALL INTERIOR WALLS TO BE TYPE 'B' UNLESS NOTED OTHERWISE.
2. ALL EXTERIOR WALLS TO BE TYPE 'A' UNLESS NOTED OTHERWISE.
3. ALL GYPSUM BOARD TO BE 5/8" TYPE 'X' UNLESS NOTED OTHERWISE.
4. CONFIRM THE REQUIRED STUD THICKNESS PER SELECTED MANUFACTURER'S LOAD TABLES FOR THE WALL HEIGHTS INDICATED ON THE PLANS.
5. PROVIDE GYPSUM BOARD EXPANSION JOINTS AS REQUIRED PER MANUFACTURER'S RECOMMENDATIONS.




A
1. SEE EXTERIOR ELEVATIONS FOR HEIGHT
A1
1. 12" THICK




B
1. UL #U305 - 1 HOUR RATED
2. EXTEND WALLS TO DECK
B1
1. UN-RATED
2. EXTEND WALLS TO DECK



C
1. EXTEND WALLS TO 11'-4" A.F.F.




D
1. EXTEND PRECAST WALL TO DECK
2. EXTEND INTERIOR GYPSUM BOARD WALL TO 11'-4" A.F.F.



E
1. EXTEND WAREHOUSE WALL TO 11'-4" A.F.F.
2. EXTEND TOILET ROOM WALL 6" ABOVE CEILING

1 A3.3 PARTIAL FLOOR PLAN
1/16" = 1'-0"

TRUE NORTH
PLAN NORTH



KEY PLAN
NOT TO SCALE

TRUE NORTH
PLAN NORTH

© 2026 Partners in Design Architects, Inc.

REVISIONS:
1 05.20.26 WI DSPS COMMENTS


ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI

PARTIAL FLOOR PLAN

2610 Lake Cook Road
Suite 280
Riverwoods, IL 60015
Ph.: (847) 940-0300
www.pidarchitects.com


Partners in Design ARCHITECTS

PROJECT NO.: 522.22.031
DRAWN BY: JJH
CHECKED BY: WHB
DATE: 03.20.26
SHEET NO.: A3.3




1 A3.4 ENLARGED FLOOR PLAN
1/4"=1'-0"

TRUE NORTH | PLAN NORTH




3 A3.4 TOILET REFLECTED CEILING PLAN
1/4"=1'-0"

TRUE NORTH | PLAN NORTH




2 A3.4 ENLARGED FLOOR PLAN
1/4"=1'-0"

TRUE NORTH | PLAN NORTH



4 A3.4 TOILET ROOM ELEVATION
1/4"=1'-0"


5 A3.4 TOILET ROOM ELEVATION
1/4"=1'-0"



TOILET ACCESSORIES MOUNTING HEIGHTS
N.T.S.

GENERAL NOTES:

1. ACCESS TO ALL DISPENSING AND OPERABLE CONTROLS SHOULD BE 15" TO 48" ABOVE FINISHED FLOOR.
2. REFER TO MANUFACTURERS' GUIDELINES FOR INSTALLATION.
3. T.O.O. INDICATES TOP OF OPENING.
4. EXPOSED UNDER LAVATORY PIPING TO BE WRAPPED TO PROTECT AGAINST CONTACT.
5. PROVIDE SOLID BLOCKING AT ALL GRAB BAR LOCATIONS AND IN WALLS AS REQUIRED.



FIXTURE CLEARANCES
N.T.S.

GENERAL NOTES:

1. ALL FIXTURES TO MEET ADAAG CLEARANCE AND HEIGHT REQUIREMENTS.
2. ALL TOILET FLUSH CONTROLS SHALL BE ON THE WIDE SIDE OF STALL.

TOILET ACCESSORIES LEGEND

TAG	DESCRIPTION	MANUFACTURER	MODEL#	NOTE
1	42" GRAB BAR	BOBRICK	B-6806 (42)	
2	36" GRAB BAR	BOBRICK	B-6806 (36)	
3	18" GRAB BAR	BOBRICK	B-6806 (18)	
4	TOILET PAPER DISPENSER	BOBRICK	B-2888	
5	RECESSED PAPER TOWEL DISPENSER/WASTE (SMALL)	BOBRICK	B-369	
6	WALL MOUNTED SOAP DISPENSER	BOBRICK	B-4112	
7	SURFACE MOUNTED MIRROR (STANDARD SIZE)	BOBRICK	B-165 (24 x 36)	

APPROVED ALTERNATE MANUFACTURERS: ASI, BRADLEY

© 2026 Partners in Design Architects, Inc.

REVISIONS:
1 05.20.26 WI DSPS COMMENTS

ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI

ENLARGED PLANS & NOTES

2610 Lake Cook Road
Suite 280
Rivenwoods, IL 60015
Ph.: (847) 940-6300
www.pidarchitects.com

PartnersinDesign
ARCHITECTS

PROJECT NO.: 522.22.031
DRAWN BY: JJH
CHECKED BY: WHB
DATE: 032026
SHEET NO.: A3.4

ROOM FINISH SCHEDULE

ROOM NAME	NO.	FLOOR	BASE	WALLS				CEILING		PAINT		REMARKS
				NORTH	EAST	SOUTH	WEST	MAT'L	HT.	WALLS	CLG	
WAREHOUSE	100	S. CONC.	--	CONC. / GYP. BD.	CONC.	CONC.	CONC.	MTL. DECK	VARIES	YES	NO	NOTES 1, 2, 3
ELECTRICAL ROOM	200	S. CONC.	--	CONC.	CONC.	CONC.	CONC.	MTL. DECK	VARIES	YES	NO	NOTE 5
SPRINKLER ROOM	201	S. CONC.	--	CONC.	CONC.	CONC.	CONC.	MTL. DECK	VARIES	YES	NO	NOTE 5
TOILET	203	S. CONC.	VINYL	FRP / GYP. BD.	GYP. BD.	GYP. BD.	FRP / GYP. BD.	S.A.T.	9'-0"	YES	NO	NOTE 4
TOILET	204	S. CONC.	VINYL	FRP / GYP. BD.	FRP / GYP. BD.	GYP. BD.	GYP. BD.	S.A.T.	9'-0"	YES	NO	NOTE 4


ROOM FINISH SCHEDULE NOTES:
1. PROVIDE 4" VINYL BASE ON GYSUM BOARD WALLS ONLY.
2. PROVIDE 4'-0" x 4'-0" FIBER REINFORCED PLASTIC WALL PANEL BEHIND SERVICE SINK.
3. INTERIOR SIDE OF HOLLOW METAL DOORS AND FRAMES TO BE HALLMAN LINDSEY JET GRAY, OR APPROVED EQUAL.
4. PROVIDE 6" VINYL BASE WITH CONTINUOUS WATERPROOF ADHESIVE TO WALL AND FLOOR.
5. WALLS TO BE PAINTED WITH PRIMER PAINT ONLY

DOOR SCHEDULE

NO.	SIZE	MATERIAL		TYPE		HDW SET	REMARKS
		DOOR	FRAME	DOOR	FRAME		
100	3'-0" x 7'-0" x 1 3/4"	ALUM	ALUM	A	5/A4.1	SET 1	
101	3'-0" x 7'-0" x 1 3/4"	ALUM	ALUM	A	5/A4.1	SET 1	
102	3'-0" x 7'-0" x 1 3/4"	HM	HM	B	A	SET 2	
103	3'-0" x 7'-0" x 1 3/4"	HM	HM	B	A	SET 2	
104	3'-0" x 7'-0" x 1 3/4"	ALUM	ALUM	A	5/A4.1	SET 1	
105	3'-0" x 7'-0" x 1 3/4"	ALUM	ALUM	A	5/A4.1	SET 1	
106	3'-0" x 7'-0" x 1 3/4"	HM	HM	B	A	SET 2	
107	3'-0" x 7'-0" x 1 3/4"	HM	HM	B	A	SET 2	
108	14'-0" x 16'-0" x 2"	STEEL		C			OVERHEAD SECTIONAL DOOR
109	9'-0" x 10'-0" x 2"	STEEL		C			OVERHEAD SECTIONAL DOOR
110	9'-0" x 10'-0" x 2"	STEEL		C			OVERHEAD SECTIONAL DOOR
111	9'-0" x 10'-0" x 2"	STEEL		C			OVERHEAD SECTIONAL DOOR
112	3'-0" x 7'-0" x 1 3/4"	HM	HM	B	A	SET 2	
113	9'-0" x 10'-0" x 2"	STEEL		C			OVERHEAD SECTIONAL DOOR
114	9'-0" x 10'-0" x 2"	STEEL		C			OVERHEAD SECTIONAL DOOR
115	9'-0" x 10'-0" x 2"	STEEL		C			OVERHEAD SECTIONAL DOOR
116	9'-0" x 10'-0" x 2"	STEEL		C			OVERHEAD SECTIONAL DOOR
117	3'-0" x 7'-0" x 1 3/4"	HM	HM	B	A	SET 2	
118	9'-0" x 10'-0" x 2"	STEEL		C			OVERHEAD SECTIONAL DOOR
119	9'-0" x 10'-0" x 2"	STEEL		C			OVERHEAD SECTIONAL DOOR
120	3'-0" x 7'-0" x 1 3/4"	HM	HM	B	A	SET 2	
121	9'-0" x 10'-0" x 2"	STEEL		C			OVERHEAD SECTIONAL DOOR
122	9'-0" x 10'-0" x 2"	STEEL		C			OVERHEAD SECTIONAL DOOR
123	9'-0" x 10'-0" x 2"	STEEL		C			OVERHEAD SECTIONAL DOOR
124	9'-0" x 10'-0" x 2"	STEEL		C			OVERHEAD SECTIONAL DOOR
125	3'-0" x 7'-0" x 1 3/4"	HM	HM	B	A	SET 2	
126	9'-0" x 10'-0" x 2"	STEEL		C			OVERHEAD SECTIONAL DOOR
127	9'-0" x 10'-0" x 2"	STEEL		C			OVERHEAD SECTIONAL DOOR
128	9'-0" x 10'-0" x 2"	STEEL		C			OVERHEAD SECTIONAL DOOR
129	14'-0" x 16'-0" x 2"	STEEL		C			OVERHEAD SECTIONAL DOOR
130	3'-0" x 7'-0" x 1 3/4"	HM	HM	B	A	SET 2	
131	3'-0" x 7'-0" x 1 3/4"	HM	HM	B	A	SET 2	
132	3'-0" x 7'-0" x 1 3/4"	HM	HM	B	A	SET 2	
133	3'-0" x 7'-0" x 1 3/4"	HM	HM	B	A	SET 2	
200	3'-0" x 7'-0" x 1 3/4"	HM	HM	B	A	SET 5	
200A	3'-0" x 7'-0" x 1 3/4"	HM	HM	B	A	SET 4	45 MINUTE RATED
201	3'-0" x 7'-0" x 1 3/4"	HM	HM	B	A	SET 5	
201A	3'-0" x 7'-0" x 1 3/4"	HM	HM	B	A	SET 3	45 MINUTE RATED
203	3'-0" x 7'-0" x 1 3/4"	HM	HM	B	A	SET 6	
204	3'-0" x 7'-0" x 1 3/4"	HM	HM	B	A	SET 6	

DOOR SCHEDULE NOTES:
1. HARDWARE TO BE COMMERICAL GRADE, SCHLAGE OR APPROVED EQUAL.
2. ALL LOCKSETS TO BE CAPABLE OF RECEIVING BEST CYLINDER CORES.
3. COORDINATE DOOR KEYING WITH OWNER.
4. ALL CLOSERS TO BE HEAVY DUTY.
5. REFER TO OUTLINE SPECIFICATIONS FOR DOOR & FRAME REQUIREMENTS.
6. ALL PAINTED DOORS AND FRAMES TO BE SPRAY PAINTED.

DOOR TYPES




A
MEDIUM STYLE DOOR

B

C
OVERHEAD PANEL DOOR WITH VISION PANEL

FRAME TYPES



A

HARDWARE SETS

SET 1 (EXT STOREFRONT)
3 HINGES
1 OFFSET PULLS
1 CLOSER WITH OVERHEAD STOP
1 LATCH LOCK
1 CYLINDER
1 MANUAL CONCEALED VERTICAL ROD PANIC DEVICE
1 POWER TRANSFER
1 ELECTRIC STRIKE
1 THRESHOLD
1 SWEEP
WEATHERSTRIPPING

SET 2 (EXT ENTRY)
3 HINGES
1 STOREROOM LOCKSET
1 CLOSER WITH OVERHEAD STOP
1 THRESHOLD
1 SWEEP
1 RAIN DRIP CAP
WEATHERSTRIPPING

SET 3 (INT FP)
3 HINGES
1 STORAGE LOCKSET
1 CLOSER WITH OVERHEAD STOP
1 THRESHOLD SET IN SEALANT
SILENCERS
WEATHERSTRIPPING

SET 4 (INT-ELECTRICAL)
3 HINGES
1 PANIC BAR
1 DUMMY PULL KIT
1 CLOSER
1 WALL STOP
SILENCERS

SET 5 (EXT-UTILITY)
3 HINGES
1 PANIC BAR
1 STOREROOM LOCKSET
1 CLOSER WITH OVERHEAD STOP
1 THRESHOLD
1 SWEEP
1 RAIN DRIP CAP
WEATHERSTRIPPING

SET 5 (TOILET)
3 HINGES
1 PRIVACY LOCKSET
1 WALL STOP
1 CLOSER
1 KICKPLATE
SILENCERS
1 ADA SIGN

HARDWARE NOTES

1. VERIFY HARDWARE FUNCTIONS AND KEYING REQUIREMENTS WITH OWNER.
2. ALL DOOR HARDWARE TO COMPLY WITH ADA REQUIREMENTS AND AS DEFINED IN ANSI A-117.1.
3. DOOR HARDWARE SHALL BE CAPABLE OF OPERATION WITH THE USE OF ONE (1) HAND AND SHALL NOT REQUIRE TIGHT PINCHING, TIGHT GRASPING OR TWISTING OF THE WRIST TO OPERATE. THUMBTURN DEADBOLTS ARE PROHIBITED, LEVER OR PADDLE DEADBOLT RELEASES ARE ACCEPTABLE.
4. DOOR THRESHOLD SHALL NOT EXCEED ONE-HALF INCH (½") IN HEIGHT, THRESHOLDS EXCEEDING ONE QUARTER INCH (¼") IN HEIGHT SHALL HAVE A 1:2 BEVEL.
5. DOOR CLOSERS SHALL MEET OPENING FORCE AND SWEEP PERIOD REQUIREMENTS.
6. ALL ENTRY DOORS AND FIREWALL DOORS SHALL BE EQUIPPED WITH FINISH HARDWARE WHICH MEETS OR EXCEEDS THE REQUIREMENTS OF THE LOCAL CODES.
7. ALL REQUIRED ENTRY/ EXIT AND FIREWALL DOORS SHALL BE OPERABLE FROM THE INSIDE WITHOUT THE USE OF A KEY OR SPECIAL KNOWLEDGE.
8. SIGNS, IF REQUIRED, SHALL BE READILY VISIBLE AND DURABLE WITH LETTERS NOT LESS THAN ONE INCH HIGH ON A CONTRASTING BACKGROUND.
9. ACCESSIBLE TOILET ROOM SIGNAGE TO BE MOUNTED ON THE WALL ADJACENT TO THE LATCH SIDE OF THE DOOR WITH A MOUNTING HEIGHT OF 60" FROM THE FINISHED FLOOR TO THE CENTER OF THE SIGN.
10. PROVIDE KNURLED HANDLES ON EXTERIOR SIDE OF DOORS TO HAZARDOUS AREAS WHERE REQUIRED BY CODE.
11. DOORS AND FRAMES SHALL BE REINFORCED FOR SURFACE MOUNTED HARDWARE AS NECESSARY, DRILLING AND TAPPING FOR SURFACE MOUNTED HARDWARE SHALL BE PERFORMED BY INSTALLATION CONTRACTOR. PROVIDE PROPER DOOR REINFORCING TO ELIMINATE THE USE OF THRU-BOLTS.
12. ALL STANDARD TYPE HARDWARE WILL BE LOCATED AT THE MANUFACTURER'S STANDARD LOCATION AS SHOWN ON DOOR AND FRAME ELEVATION.
13. HARDWARE ITEMS SUCH AS PANIC EXIT DEVICES, DEADLOCKS, ETC. WILL ALSO BE LOCATED AT THE MANUFACTURER'S STANDARD LOCATION UNLESS SPECIFICALLY ADDRESSED IN SUBMITTAL AND/OR SUBMITTAL REVIEW.
14. ALL FRAMES SHALL BE PREPARED FOR DRILLED DOOR SILENCERS, THREE FOR SINGLE SWING OPENING AND TWO PER HEAD FOR DOUBLE SWING OPENINGS.
15. ALL FRAMES MUST BE SET PLUMB AND LEVEL TO ENSURE PROPER OPERATION OF DOORS AND HARDWARE.
16. FRAMES TO BE WELDED FULL DEPTH & WIDTH.
17. INSTALL DOOR CLOSERS ON NON-PUBLIC SIDE OF DOORS TO THE GREATEST EXTENT POSSIBLE.
18. DOOR SURFACES WITHIN 10" OF THE FLOOR OR GROUND SHALL BE SMOOTH AND EXTEND THE FULL WIDTH OF THE DOOR. PARTS CREATING HORIZONTAL OR VERTICAL JOINTS SHALL BE WITHIN 1/16" OF THE SAME PLANE. ANY CAVITIES CREATED BY ADDING A KICKPLATE SHALL BE CAPPED.
19. PROVIDE A THRESHOLD AND WEATHERSTRIP PACKAGE FOR ALL EXTERIOR DOORS INCLUDING COMPRESSIBLE GASKETS AROUND FRAME AND DOOR SWEEPS AT BOTTOM. PROVIDE MANUFACTURER'S STANDARD PACKAGE AT STOREFRONT DOORS AND PAIRS.
20. ALL EXTERIOR DOORS TO HAVE A RAIN CHANNEL CAP THE WIDTH OF THE DOOR + JAMBS COMBINED.
21. WHEN HOLLOW METAL IS USED IN CONJUNCTION WITH ALUMINUM OR STRUCTURAL STEEL PRODUCTS, CONSULT WITH THE CONSTRUCTION MANAGER FOR COORDINATION OF HARDWARE LOCATIONS.
22. WHERE DOORS OPEN BACK TO BACK, PROVIDE OVERHEAD STOP OR OTHER MEANS OF PREVENTING DOORS FROM DAMAGE.
23. PROVIDE HEAVYWEIGHT HINGES FOR DOORS OVER 3'-0" WIDE. USE A MINIMUM OF FOUR HINGES FOR DOORS OVER 7'-6" IN HEIGHT.
24. EXTERIOR HOLLOW METAL DOORS AND FRAMES TO BE GALVANIZED.
25. ALL CLOSERS TO BE HEAVY DUTY.
26. ALL PAINTED DOORS AND FRAMES TO BE SPRAY PAINTED.
27. REFER TO OUTLINE SPECIFICATIONS FOR ADDITIONAL HARDWARE AND DOCK EQUIPMENT REQUIREMENTS.

GLAZING NOTES

1. PROVIDE TEMPERED GLAZING AT THE FOLLOWING LOCATIONS (AND ANY OTHER LOCATIONS REQUIRED BY CODE):
   A. INGRESS AND MEANS OF EGRESS DOORS.
   B. FIXED PANELS IN SWINGING DOORS.
   C. INDIVIDUAL FIXED PANELS ADJACENT TO DOORS.
   D. FIXED PANELS WHOSE BOTTOM EDGE IS LESS THAN 18 INCHES FROM THE FLOOR.
   E. GLAZING IN GUARDS AND RAILINGS.
2. ALL GLAZING SHALL COMPLY WITH THE REQUIREMENTS OF THE LOCAL CODES.
3. ALL GLAZING IN OR ADJACENT TO DOORS OR IS WITHIN A 24" ARC OF EITHER VERTICAL EDGE OF THE DOOR IN A CLOSED POSITION SHALL BE TEMPERED.
4. PROVIDE TEMPERED GLAZING IN AN INDIVIDUAL FIXED OR OPERABLE PANEL WHEN ALL OF THE FOLLOWING CRITERIA APPLY. THE EXPOSED AREA OF AN INDIVIDUAL PANE IS GREATER THAN 9 SF., THE EXPOSED BOTTOM EDGE IS LESS THAN 18" ABOVE THE FLOOR, THE EXPOSED TOP EDGE IS GREATER THAN 36" ABOVE THE FLOOR AND ONE OR MORE WALKING SURFACE(S) ARE WITHIN 36" HORIZONTALLY FROM THE PLANE OF THE GLAZING.
5. FIELD VERIFY ALL ROUGH / FINISHED OPENING DIMENSIONS.
6. IF GLAZING IS IN AN INSULATED UNIT, BOTH LITES MUST BE TEMPERED, LAMINATED SAFETY GLASS, OR A COMBINATION OF THE TWO.
7. EXTERIOR STOREFRONT GLAZING AND DOORS TO HAVE 1" INSULATED GLASS, INTERIOR STOREFRONT GLAZING AND DOORS TO HAVE 1/4" SINGLE GLASS UNLESS NOTED OTHERWISE.

© 2026 Partners in Design Architects, Inc.

REVISIONS:
1 05.20.26 WI DSPS COMMENTS

ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI

SCHEDULES & NOTES

2610 Lake Cook Road
Suite 280
Riverwoods, IL 60015
Ph.: (847) 940-0300
www.pidarchitects.com


Partners in Design ARCHITECTS


PROJECT NO.:
522.22.031

DRAWN BY: JJH
CHECKED BY: WHB

DATE:
03.20.26

SHEET NO.:
A3.5





1 A4.1 NORTH ELEVATION 1" = 20'-0"

EXTERIOR FINISHES:


PAINT COLORS:

- COLOR 1 (LIGHT FIELD COLOR) SHERWIN-WILLIAMS COLOR: SW7064 PASSIVE
- COLOR 2 (DARK ACCENT COLOR) SHERWIN-WILLIAMS COLOR: SW7066 GRAY MATTERS
- COLOR 3 (DARK BASE COLOR) SHERWIN-WILLIAMS COLOR: SW7067 CITYSCAPE
- COLOR 4 (ACCENT COLOR) SHERWIN-WILLIAMS COLOR: SW6511 REGATTA
- ROOF FASCIA 1: FIRESTONE COLOR: STONE WHITE
- ROOF FASCIA 2: FIRESTONE COLOR: CITYSCAPE
- INSULATED TINTED GLASS: COLOR GREY


WINDOW FRAMES: CLEAR ANODIZED ALUMINUM

OVERHEAD DOORS: PREFINISHED ALUMINUM, WHITE


EXTERIOR STAIRS: GALVANIZED STAIRS & RAILINGS




2 A4.1 EAST ELEVATION 1" = 20'-0"




3 A4.1 WEST ELEVATION 1" = 20'-0"






4 A4.1 SOUTH ELEVATION 1" = 20'-0"




5 A4.1 TYPE 1 FRAME ELEV. 1/4" = 1'-0"


T = TEMPERED GLAZING



6 A4.1 TYPE 2 FRAME ELEV. 1/4" = 1'-0"



7 A4.1 TYPE 3 FRAME ELEV. 1/4" = 1'-0"



8 A4.1 TYPE 4 FRAME ELEV. 1/4" = 1'-0"

© 2026 Partners in Design Architects, Inc.

REVISIONS:
1 05.20.26 UI DSPS COMMENTS


ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI

EXTERIOR ELEVATIONS & FRAME TYPES


2610 Lake Cook Road Suite 280 Riverwoods, IL 60015 Ph.: (847) 940-0300 www.pidarchitects.com

Partners in Design ARCHITECTS


PROJECT NO.: 522.22.031
DRAWN BY: CTS CHECKED BY: WHB
DATE: 03.20.26
SHEET NO.: A4.1




1 A5.1 WALL SECTION
1/2" = 1'-0"



2 A5.1 WALL SECTION
1/2" = 1'-0"



3 A5.1 WALL SECTION
1/2" = 1'-0"



4 A5.1 WALL SECTION
1/2" = 1'-0"

© 2026 Partners in Design Architects, Inc.

REVISIONS:
1 05.20.26 WI DSPS COMMENTS


ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI

WALL SECTIONS


2610 Lake Cook Road
Suite 280
Riverwoods, IL 60015
Ph.: (847) 940-0300
www.pdarchitects.com

Partners in Design ARCHITECTS


PROJECT NO.: 522.22.031
DRAWN BY: CTS
CHECKED BY: WHB
DATE: 03.2026
SHEET NO.: A5.1




1 A5.2 WALL SECTION
1/2" = 1'-0"



2 A5.2 WALL SECTION
1/2" = 1'-0"



3 A5.2 WALL SECTION
1/2" = 1'-0"



4 A5.2 WALL SECTION
1/2" = 1'-0"

© 2026 Partners in Design Architects, Inc.

REVISIONS:
1 Ø5.20.26 WI DSPS COMMENTS


ZILBER INDUSTRIAL 3
10801 108th St, Lakeview Corporate Park, Pleasant Prairie, WI

WALL SECTIONS


2510 Lake Cook Road
Suite 280
Riverwoods, IL 60015
Ph.: (847) 940-9300
www.pidarchitects.com

PartnersinDesign
ARCHITECTS


PROJECT NO.: 522.22.031
DRAWN BY: CTS
CHECKED BY: WHB
DATE: Ø32026
SHEET NO.: A5.2




1 A5.3 **WALL SECTION** 1/2" = 1'-0"



2 A5.3 **WALL SECTION** 1/2" = 1'-0"



3 A5.3 **WALL SECTION** 1/2" = 1'-0"



4 A5.3 **WALL SECTION** 1/2" = 1'-0"

© 2026 Partners in Design Architects, Inc.

REVISIONS:
1 03.20.26 WI DSPS COMMENTS


ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI

WALL SECTIONS


2610 Lake Cook Road
Suite 280
Riverwoods, IL 60015
Ph.: (847) 940-0300
www.pidarchitects.com

PartnersinDesign ARCHITECTS

PROJECT NO.: 522.22.031
DRAWN BY: CTS
CHECKED BY: WHB
DATE: 03.20.26
SHEET NO.: A5.3



1 A5.4 **WALL SECTION** 1/2" = 1'-0"



2 A5.4 **WALL SECTION** 1/2" = 1'-0"

3 A5.4 **SECTION DETAIL** 1 1/2" = 1'-0"

4 A5.4 **SECTION DETAIL** 1 1/2" = 1'-0"

5 A5.4 **SECTION DETAIL** 1 1/2" = 1'-0"

6 A5.4 **SECTION DETAIL** 1 1/2" = 1'-0"

7 A5.4 **SECTION DETAIL** 1 1/2" = 1'-0"

8 A5.4 **SECTION DETAIL** 1 1/2" = 1'-0"

9 A5.4 **SECTION DETAIL** 1 1/2" = 1'-0"

© 2026 Partners in Design Architects, Inc.

REVISIONS:
1 05.20.26 WI DSPS COMMENTS


ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI

WALL SECTIONS & SECTION DETAILS

2610 Lake Cook Road
Suite 280
Riverwoods, IL 60015
Ph.: (847) 940-0300
www.pdarchitects.com


Partners in Design ARCHITECTS

PROJECT NO.: 522.22.031
DRAWN BY: CTS
CHECKED BY: WHB
DATE: 03.20.26
SHEET NO.: A5.4




* - JOINT DIMENSION BY PRECASTER

1 A6.1 TYP. WALL PANEL JOINT DETAIL
1 1/2" = 1'-0"




* - JOINT DIMENSION BY PRECASTER

2 A6.1 PRECAST BUTT CORNER DETAIL
1 1/2" = 1'-0"




* - JOINT DIMENSION BY PRECASTER

3 A6.1 PRECAST BUTT CORNER DETAIL
1 1/2" = 1'-0"




* - JOINT DIMENSION BY PRECASTER

4 A6.1 INTERIOR PRECAST DETAIL
1 1/2" = 1'-0"




5 A6.1 WINDOW JAMB DETAIL
1 1/2" = 1'-0"




* - JOINT DIMENSION BY PRECASTER


6 A6.1 CORNER DETAIL
1 1/2" = 1'-0"




7 A6.1 DOOR JAMB DETAIL
1 1/2" = 1'-0"



8 A6.1 DOCK DOOR JAMB DETAIL
1 1/2" = 1'-0"



9 A6.1 DRIVE-IN DOOR JAMB DETAIL
1 1/2" = 1'-0"



10 A6.1 GYP. BD. TO PRECAST DETAIL
1 1/2" = 1'-0"

© 2026 Partners in Design Architects, Inc.

REVISIONS:
1 05.20.26 WI DSPS COMMENTS


ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI

PLAN DETAILS

2610 Lake Cook Road
Suite 280
Riverwoods, IL 60015
Ph.: (847) 940-0300
www.pidarchitects.com

PartnersinDesign
ARCHITECTS

PROJECT NO.: 522.22.031
DRAWN BY: CTS
CHECKED BY: WHB
DATE: 03.2026
SHEET NO.: A6.1




1 A9.1 ROOF PLAN
1" = 30'-0"

TRUE NORTH


PLAN NORTH

GENERAL ROOF NOTES

1. ALL ROOFING PRODUCTS AND MATERIALS TO BE INSTALLED PER MANUFACTURER'S PUBLISHED & WARRANTEED DETAILS.




2 A9.1 ROOF INSULATION JOINT DIAGRAM




3 A9.1 ROOF DRAIN DETAIL
1/4" = 1'-0"

TRUE NORTH


PLAN NORTH




4 A9.1 ROOF DRAIN DETAIL
1 1/2" = 1'-0"



5 A9.1 ROOF HATCH DETAIL
1 1/2" = 1'-0"



6 A9.1 ROOF EDGE DETAIL
1 1/2" = 1'-0"



7 A9.1 ROOF EDGE DETAIL
1 1/2" = 1'-0"

© 2026 Partners in Design Architects, Inc.

REVISIONS:
1 05.20.26 UI DSPS COMMENTS

ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI

ROOF PLAN & DETAILS

2610 Lake Cook Road
Suite 280
Riverwoods, IL 60015
Ph.: (847) 940-0300
www.pdarchitects.com

Partners in Design ARCHITECTS

PROJECT NO.: 522220231
DRAWN BY: JJH
CHECKED BY: WHB
DATE: 03.20.26
SHEET NO.: A9.1

► BUILDING CODES
- DESIGN AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE PROVISIONS OF THE 2025 WISCONSIN COMMERCIAL BUILDING CODE (BASED ON IBC 2021) AS CONTAINED IN CHAPTERS SPS 361, SPS 362 and SPS 366 OF THE WISCONSIN ADMINISTRATIVE CODE.

RISK CATEGORY	II

► DESIGN LOADS AND DATA
- SOIL DATA (AGGREGATE BACKFILL)

ACTIVE SOIL PRESSURE	40 PSF PER FOOT OF DEPTH
AT-REST SOIL PRESSURE	65 PSF PER FOOT OF DEPTH
PASSIVE SOIL PRESSURE	360 PSF PER FOOT OF DEPTH
SURCHARGE LOAD	120 PSF

- ROOF LOADS

DEAD (7 PSF FRAMING, 2 PSF ROOFING, 12/15/18 PSF BALLAST✻ 4 PSF MEP)	25 TO 31 PSF (23 TO 29 PSF TO JOISTS)
✻ HEAVIER BALLAST AT 16' PERIMETER	
LIVE (SEE SNOW LOAD ALSO)	20 PSF

- SNOW LOADS

GROUND SNOW (p_g)	30 PSF
SNOW DENSITY (0.13 x p_g + 14 < 30)	17.9 PCF
ROOF EXPOSURE	PARTIALLY EXPOSED
EXPOSURE FACTOR (C_e)	1.0
THERMAL FACTOR - BUILDING (C_t)	1.0
THERMAL FACTOR - CANOPY, MANSARDS (C_t)	1.2
SNOW IMPORTANCE FACTOR (I_s)	1.0
FLAT ROOF SNOW LOAD - BUILDING	21 PSF (25 PSF USED)
FLAT ROOF SNOW LOAD - CANOPY	26 PSF
DRIFT LOAD	AS NOTED ON 1/S0.2 & DRAWINGS, PER ASCE 7-16

- WIND DATA

ULTIMATE DESIGN WIND SPEED - 3 SECOND GUST (V_{ULT})	107 MPH
NOMINAL DESIGN WIND SPEED - 3 SECOND GUST (V_{ASD})	83 MPH
BUILDING ENCLOSURE	ENCLOSED
EXPOSURE	C
WIND DIRECTIONALITY FACTOR (K_d)	0.85
TOPOGRAPHIC FACTOR (K_{zt})	1.0
GUST FACTOR (G - BUILDING IS RIGID)	0.85
INTERNAL PRESSURE COEFFICIENT (ENCLOSED - GC_{pi})	± 0.18
ANALYSIS PROCEDURE	DIRECTIONAL
EDGE ZONE WIDTH (2a)	28.3 FT
MEAN ROOF HEIGHT (h)	35.3 FT
ROOF PLANE SLOPE (Θ)	1.2 DEGREES
COMPONENTS AND CLADDING	SEE TABLE THIS SHEET
MINIMUM NET UPLIFT	
INTERIOR SPACES	10 PSF
EXTERIOR CANOPIES/SOFFITS	30 PSF

- SEISMIC DATA

SEISMIC IMPORTANCE FACTOR	1.00
MAPPED SPECTRAL RESPONSE ACCELERATION FOR SHORT PERIODS (S_S)	0.092
MAPPED SPECTRAL RESPONSE ACCELERATION FOR 1 SECOND PERIOD (S_1)	0.054
SITE CLASS PER GEOTECHNICAL REPORT	D
DESIGN SPECTRAL RESPONSE ACCELERATION FOR SHORT PERIODS (S_{DS})	0.098
DESIGN SPECTRAL RESPONSE ACCELERATION FOR 1 SECOND PERIOD (S_{D1})	0.086
SEISMIC DESIGN CATEGORY	B
BASIC SEISMIC FORCE RESISTING SYSTEM AND PARAMETERS	
BEARING WALL SYSTEM - ORDINARY PRECAST SHEAR WALLS	
R = 3.0 Ω_0 = 2.0 PRECAST C_d = 3.0	
SEISMIC RESPONSE COEFFICIENT (C_s)	0.033
ANALYSIS PROCEDURE	EQUIVALENT LATERAL FORCE (ASCE 12.8)

- RAIN

RAIN INTESNSITY	3.05 IN/HR
STATIC HEAD	6 IN
OVERFLOW DEVICE	24" LONG CHANNEL SCUPPER
HYDRAULIC HEAD	4.90 IN (MAX)
DESIGN RAIN LOAD (@ PROXIMITY DRAIN)	67.1 PSF (MAX)

► MATERIAL STRENGTHS AND STANDARDS
- SOILS

DESIGN SOIL BEARING CAPACITY FOR SPREAD/STRIP FOOTINGS	4,000 PSF
MODULUS OF SUB-GRADE REACTION	150 PCI
COEFFICIENT OF SLIDING FRICTION (CONCRETE –SOIL)	0.40

- REINFORCING STEEL

WELDED WIRE FABRIC, PROVIDED IN FLAT SHEETS ONLY (ASTM A185)	F_y = 65,000 PSI
DEFORMED BARS (ASTM A615, GRADE 60)	F_y = 60,000 PSI

- MASONRY

CONCRETE MASONRY ASSEMBLY (RUNNING BOND)	f'_m = 2,500 PSI
CMU (ASTM C90 - NORMALWEIGHT)	3,250 PSI
MORTAR (ASTM C270)	TYPE S
GROUT (ASTM C476)	f'_c = 3,000 PSI

- STRUCTURAL STEEL (SHAPES)

W, WT SECTIONS, CHANNELS (ASTM A992)	F_y = 50,000 PSI; F_u = 65,000 PSI
HP SECTIONS(ASTM A572, GRADE 50)	F_y = 50,000 PSI; F_u = 65,000 PSI
M, MT, S, ST SECTIONS, ANGLES (ASTM A36)	F_y = 36,000 PSI; F_u = 58,000 PSI
HSS SHAPES – SQUARE/RECTANGULAR (ASTM A500, GRADE C)	F_y = 50,000 PSI; F_u = 62,000 PSI
HSS SHAPES – ROUND (ASTM A500, GRADE C)	F_y = 50,000 PSI; F_u = 62,000 PSI
STEEL PIPE (ASTM A53, GRADE B)	F_y = 35,000 PSI; F_u = 60,000 PSI
PLATES (ASTM A36)	F_y = 36,000 PSI; F_u = 58,000 PSI

- STRUCTURAL STEEL (CONNECTIONS)

ANCHOR RODS (ASTM F1554, GRADE 36)	F_y = 36,000 PSI; F_u = 58,000 PSI
HIGH STRENGTH BOLTS (F3125)	GR. A325 UNLESS NOTED ON DRAWINGS
TENSION CONTROL BOLTS (F3125)	GR. F1852 UNLESS NOTED ON DRAWINGS
WELDING ELECTRODES	E70XX
SHEAR CONNECTORS (ASTM A29, GRADE 1010 THROUGH 1020; AWS TYPE B)	F_y = 51,000 PSI; F_u = 65,000 PSI
CONCRETE ANCHORS (ASTM A29, GRADE 1010 THROUGH 1020; AWS TYPE B)	F_y = 51,000 PSI; F_u = 65,000 PSI
DEFORMED BAR ANCHORS (ASTM A496; AWS TYPE C)	F_y = 70,000 PSI; F_u = 80,000 PSI
THREADED RODS (ASTM A36)	F_y = 36,000 PSI; F_u = 58,000 PSI
GROUT (ASTM C1107)	f'_c = 5,000 PSI

- COLD-FORMED METAL FRAMING

COLD-FORMED MATERIAL - 18 GAUGE AND THINNER (ASTM A653, GRADE 33)	F_y = 33,000 PSI
COLD-FORMED MATERIAL - 16 GAUGE AND THICKER (ASTM A653, GRADE 50)	F_y = 50,000 PSI
ANCHOR RODS (ASTM F1554, GRADE 36)	F_y = 36,000 PSI; F_u = 58,000 PSI
CONNECTOR PLATES (ASTM A36)	F_y = 36,000 PSI; F_u = 58,000 PSI
CONNECTOR BOLTS (ASTM A307, GRADE A)	F_u = 60,000 PSI
WELDING ELECTRODES	E60XX
GALVANIZING THICKNESS	G60

► GENERAL NOTES
- CONSTRUCTION

UNLESS SPECIFICALLY NOTED OTHERWISE, BUILDING STRUCTURE HAS BEEN DESIGNED FOR THE FINAL COMPLETED CONDITION ONLY, AND HAS NOT BEEN ANALYZED, INVESTIGATED OR DESIGNED FOR OVERALL STRUCTURE, OR INDIVIDUAL MEMBER, STABILITY DURING CONSTRUCTION. CONTRACTOR SHALL PROVIDE AND MAINTAIN TEMPORARY BRACING AND SUPPORTS FOR ALL STRUCTURAL ELEMENTS, BOTH INDIVIDUALLY AND COLLECTIVELY, AS REQUIRED AT EVERY STAGE OF CONSTRUCTION UNTIL THE FINAL COMPLETION OF THE STRUCTURE. NO PORTION OF THE BUILDING STRUCTURE, WHILE UNDER CONSTRUCTION IS INTENDED TO BE STABLE IN THE ABSENCE OF THE CONTRACTORS TEMPORARY BRACES AND SUPPORTS, WHICH SHALL ADDITIONALLY PROVIDE SUPPORT FOR ALL CONSTRUCTION LOADING. MATERIALS AND EQUIPMENT SHALL BE STORED, TRANSPORTED AND INSTALLED IN A MANNER THAT WILL NOT EXCEED THE DESIGN FLOOR LOADING.

CONTRACTOR IS SOLELY RESPONSIBLE FOR THE MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES OF CONSTRUCTION INCLUDING, BUT NOT LIMITED TO, TEMPORARY BRACING, SUPPORTS, SHORING, FORMING TO SUPPORT IMPOSED CONSTRUCTION LOADS, AND OTHER SIMILAR ITEMS.

STRUCTURAL DOCUMENTS MAY REFER TO OSHA REQUIREMENTS. SUCH REFERENCES ARE INCIDENTAL, AND ARE NOT INTENDED TO IDENTIFY ALL APPLICABLE OSHA REQUIREMENTS.

© 2026 Partners in Design Architects, Inc.

► GENERAL NOTES (CONTINUED)
- COMPLETENESS

INFORMATION CONTAINED IN THE GENERAL NOTES IS ONLY A PARTIAL SUMMARY OF PROJECT REQUIREMENTS. SEE SPECIFICATIONS, PLANS AND DETAILS FOR ADDITIONAL REQUIREMENTS.

USE ONLY DIMENSIONS INDICATED ON THE DRAWINGS. DO NOT MANUALLY SCALE THE DRAWINGS OR USE ANY DIMENSIONS MEASURED FROM ELECTRONIC DRAWING FILES.

UNLESS NOTED OTHERWISE, CENTERLINE OF FLOOR FRAMING ELEMENTS COINCIDES WITH COLUMN CENTERLINES, AND FRAMING ELEMENTS ARE EQUALLY SPACED BETWEEN ADJACENT COLUMN CENTERLINES.

MAJOR OPENING LOCATIONS AND SIZES ARE INDICATED ON THE STRUCTURAL DRAWINGS - SMALLER OPENINGS AND SLEEVES REQUIRED TO ACCOMMODATE VARIOUS BUILDING SERVICES MAY NOT BE NOTED. CONTRACTOR TO VERIFY THE SIZE AND LOCATION OF ALL ARCHITECTURAL, MECHANICAL, ELECTRICAL AND PLUMBING OPENINGS, INCLUDING CLEARANCE REQUIREMENTS CONTAINED IN THE RESPECTIVE DISCIPLINE DOCUMENTS FOR INSTALLATION AND IN-PLACE OPERATION OF THE RESPECTIVE EQUIPMENT OR ITEMS.

CONSULT ARCHITECTURAL, MECHANICAL, ELECTRICAL AND PLUMBING DRAWINGS AND MANUFACTURERS SPEC SHEETS FOR LOCATIONS AND DIMENSIONS OF PADS, CURBS, EQUIPMENT SUPPORTS, DEPRESSIONS, INSERTS, DRIPS, REGLETS, REVEALS, FINISHES AND OTHER MISCELLANEOUS PROJECT REQUIREMENTS THAT NECESSITATE INCIDENTAL ACCOMMODATION BY THE BUILDING STRUCTURE BUT ARE NOT SHOWN ON THE STRUCTURAL DRAWINGS.

DEFERRED SUBMITTALS: IBC SECTION 107.3.4.1 REQUIRED DEFERRED SUBMITTALS TO BE APPROVED BY THE BUILDING OFFICIAL. DEFERRED SUBMITTALS SHALL BE REVIEWED BY DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE AFFIXING A NOTATION THAT THE DEFERRED ITEMS ARE IN GENERAL CONFORMANCE WITH THE DESIGN OF THE BUILDING, SUBMITTED FOR REVIEW BY THE BUILDING OFFICIAL AND SHALL NOT BE INSTALLED UNTIL APPROVED BY THE BUILDING OFFICIAL. DEFERRED SUBMITTALS ON THIS PROJECT INCLUDE:
- COLD FORMED METAL FRAMING (DFMF)
- PRECAST WALL PANELS
- STAIRS/ LADDERS/ RAILINGS

- GENERAL

THE STRUCTURE HAS BEEN DESIGNED AS UNRESTRAINED FOR THE PURPOSE OF FIRE RATING AND FIREPROOFING ASSEMBLY EVALUATIONS.

STRUCTURAL COMPONENTS HAVE NOT BEEN DESIGNED FOR VIBRATORY EQUIPMENT UNLESS NOTED OTHERWISE. PLACE VIBRATORY EQUIPMENT AND EQUIPMENT SENSITIVE TO VIBRATIONS ON VIBRATION ISOLATORS SPECIFICALLY DESIGNED FOR THE EQUIPMENT.

ALL SYSTEMS, INCLUDING EXTERIOR FACADES AND FRAMING, WHICH ARE DESIGNED AND DETAILED BY COMPONENT SUPPLIERS, ARE ASSUMED TO IMPOSE VERTICAL AND/OR HORIZONTAL LOADS ON THE BASE BUILDING STRUCTURE WITHOUT CAUSING TORSION IN THE SUPPORTING STRUCTURAL MEMBERS. COMPONENT SUPPLIERS ARE RESPONSIBLE FOR DESIGNING, FURNISHING AND INSTALLING SUPPLEMENTARY BRACING MEMBERS AS REQUIRED TO PREVENT THEIR SYSTEMS FROM CAUSING TORSION IN THE SUPPORTING STRUCTURAL MEMBERS. WHERE PROVIDED, SUPPLEMENTARY BRACING SHALL NOT INTERFERE WITH ANY BUILDING SYSTEM NOTED OR DESCRIBED IN THE CONTRACT DOCUMENTS.

UNDER NO CIRCUMSTANCES MAY ANY STRUCTURAL ELEMENT BE PENETRATED, CUT, NOTCHED, BLOCKED-OUT, SLEEVED, CORE DRILLED, OR OTHERWISE FIELD MODIFIED OR REDUCED IN STRENGTH AFTER DELIVERY TO THE CONSTRUCTION SITE OR FINAL INCORPORATION IN THE BUILDING STRUCTURE UNLESS SUCH MODIFICATION IS SPECIFICALLY DETAILED ON THE STRUCTURAL DRAWINGS, OR IS APPROVED IN ADVANCE IN WRITING BY THE ENGINEER OF RECORD.

ANY FUTURE ADDITION IS ASSUMED TO BE COMPLETELY SELF SUPPORTING FOR BOTH GRAVITY AND LATERAL LOADS.

► SYSTEM NOTES
- FOUNDATIONS AND EARTHWORK

REMOVE EXISTING SURFICIAL TOP SOIL AND VEGETATION FROM WITHIN THE BUILDING AREA AND A MINIMUM OF TEN FEET BEYOND. EXCAVATE MATERIAL TO PROPOSED SLAB-ON-GROUND SUBGRADE. PROOFROLL WITH A HEAVY RUBBER TIRED VEHICLE. SOILS WHICH HEAVE, PUMP, OR DO NOT READILY COMPACT SHALL BE EXCAVATED AND REPLACED WITH ENGINEERED FILL.

SUBGRADE PREPARATION FOR FOOTINGS SHALL CONSIST OF EXCAVATION TO REQUIRED ALLOWABLE BEARING CAPACITY SOILS AT OR NEAR DESIGN FOOTING ELEVATIONS. WHERE UNSUITABLE SOIL IS ENCOUNTERED AT NOMINAL BEARING DEPTH, SEE OVER EXCAVATION DETAIL.

ALL COMPACTION REQUIREMENTS REFER TO % OF MAXIMUM DRY DENSITY PER ASTM D-1557 MODIFIED PROCTOR. GRANULAR STRUCTURAL FILL BENEATH FOOTINGS SHALL BE PLACED IN LAYERS NO MORE THAN 8" THICK, AND EACH LAYER SHALL BE COMPACTED TO 95%. COHESIVE FILL APPROVED BY THE GEOTECHNICAL CONSULTANT SHALL BE PLACED IN LAYERS NO THICKER THAN 8", AND EACH LAYER SHALL BE COMPACTED TO 95%. MOISTURE CONDITION FILL MATERIALS AS REQUIRED TO OBTAIN PROPER COMPACTION. COHESIVE SOILS OR GRANULAR SOILS WITH A SIGNIFICANT PERCENT OF COHESIVE FINES SHALL BE CONDITIONED TO WITHIN 3% OF OPTIMUM MOISTURE CONTENT AT COMPACTION.

FOR GENERAL INFORMATION AND SPECIFIC RECOMMENDATIONS AND REQUIREMENTS PERTAINING TO THE PROJECT SITE, REFER TO THE PROJECT GEOTECHNICAL REPORT PREPARED BY ECS MIDWEST, LLC PROJECT NUMBER 42:1291, DATED AUGUST 25, 2016.

ALL ACTIVITIES CONCERNING PREPARATION AND VERIFICATION OF BEARING SOILS FOR SLAB-ON-GROUND AND FOOTINGS SHALL BE SUPERVISED AND APPROVED BY A QUALIFIED GEOTECHNICAL ENGINEER.

COLUMNS, PIERS, AND SPREAD FOOTINGS ARE CENTERED ON GRIDLINES UNLESS NOTED OTHERWISE. CONTINUOUS FOOTINGS ARE CENTERED ON WALLS ABOVE UNLESS NOTED OTHERWISE.

BACKFILL UNIFORMLY ON EACH SIDE OF FOUNDATION WALLS, GRADE BEAMS AND OTHER SIMILAR ELEMENTS. DO NOT BACKFILL AGAINST ANY STRUCTURAL ELEMENT UNTIL THAT ELEMENT HAS ATTAINED FULL DESIGN STRENGTH. DO NOT BACKFILL AGAINST BASEMENT WALLS UNTIL TOP AND BOTTOM OF WALL IS BRACED BY FLOOR FRAMING AND SLAB-ON-GROUND UNLESS NOTED OTHERWISE ON THE DRAWINGS.

TOP OF FOOTING ELEVATION NOTED ON DRAWINGS REPRESENT CONSIDERED ENGINEERING JUDGMENT BY THE ENGINEER OF RECORD ABOUT PROTECTION FROM FROST AND MINIMUM DEPTH TO SOILS CAPABLE OF PROVIDING DESIGN SOIL BEARING CAPACITY. UNCERTAINTIES INHERENT IN DETERMINING THE ELEVATION OF SOILS ADEQUATE TO PROVIDE DESIGN BEARING CAPACITY MAY REQUIRE FOUNDATIONS TO BE LOWERED – IN NO CASE SHALL TOP OF FOOTING BE HIGHER THAN NOTED. A GEOTECHNICAL ENGINEER SHALL VERIFY THAT SOIL AT THE FOOTING BASE IS ADEQUATE TO PROVIDE THE REQUIRED DESIGN SOIL BEARING CAPACITY.

- CAST-IN-PLACE CONCRETE

DESIGN AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE PROVISIONS OF ACI 318–18 USING STRENGTH DESIGN METHODOLOGY, EXCEPT WHERE MORE RESTRICTIVE REQUIREMENTS ARE NOTED.

REINFORCING CLEAR COVER SHALL BE AS NOTED BELOW UNLESS SPECIFICALLY NOTED OTHERWISE ON STRUCTURAL DRAWINGS.

CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH	3"
CONCRETE EXPOSED TO EARTH OR WEATHER	
#3 - #5 BARS	1 1/2"
#6 - #18 BARS	2"
CONCRETE NOT EXPOSED TO EARTH OR WEATHER	
WALLS - #3 THRU #11 BARS	3/4"
WALLS - #14 THRU #18 BARS	1 1/2"
STRUCTURAL SLABS - TOP, BOTTOM	1"
JOIST TIES AND MAIN REINFORCING - TOP, BOTTOM , SIDES	1 1/2"
BEAM TIES - TOP, BOTTOM, SIDES	1 1/2"
BEAM MAIN REINFORCING - TOP, BOTTOM, SIDES	2"
COLUMN TIES	1 1/2"
COLUMN MAIN REINFORCING	2"

PROVIDE (2) #5 BARS AROUND ALL OPENINGS AND (2) #5 DIAGONAL BARS AT ALL OPENING AND RE-ENTRANT CORNERS. BARS SHALL EXTEND A MINIMUM OF 24" PAST OPENING.

ALL BAR SPLICES SHALL BE CONTACT LAP SPLICED USING CLASS B TENSION LAP LENGTHS, WITH ADJACENT LAPS STAGGERED A MINIMUM OF 3'-0" UNLESS DETAILED OTHERWISE. SEE REINFORCEMENT TABLES FOR REQUIRED LAP AND DEVELOPMENT LENGTHS.

FIELD WELDING OF ASTM A615 REINFORCING STEEL IS NOT PERMITTED. FIELD BENDING OF REINFORCING STEEL IS NOT PERMITTED EXCEPT WHERE SPECIFICALLY DETAILED ON STRUCTURAL DRAWINGS.

CORING OF COLUMNS, WALLS, BEAMS, JOISTS AND SLABS IS NOT PERMITTED. PROVIDE STEEL SLEEVES FOR ALL PENETRATIONS AT ALL LOCATIONS APPROVED BY THE ENGINEER OF RECORD PRIOR TO PLACING CONCRETE.

- PRECAST CONCRETE

DESIGN AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE PROVISIONS OF ACI 318–14 AND THE PCI DESIGN HANDBOOK, SEVENTH EDITION, USING STRENGTH DESIGN METHODOLOGY, EXCEPT WHERE MORE RESTRICTIVE REQUIREMENTS ARE NOTED.

PRECAST MEMBERS SHALL BE DESIGNED TO SUPPORT THEIR OWN SELF WEIGHT, THE SUPERIMPOSED LOADS NOTED ON THE STRUCTURAL PLANS AND DETAILS, AND TO ACCOMMODATE THE DETAILS AND ADDITIONAL LOADS THAT MAY BE SHOWN ON ARCHITECTURAL, MECHANICAL, PLUMBING OR ELECTRICAL PLANS.

► SYSTEM NOTES (CONTINUED)
- CONCRETE MASONRY

DESIGN AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE PROVISIONS OF TMS 402-13 AND TMS 602-13 EXCEPT WHERE MORE RESTRICTIVE REQUIREMENTS ARE NOTED.

UNLESS NOTED OTHERWISE PROVIDE CONTINUOUS LADDER TYPE REINFORCEMENT WITH W1.7 (9 GAUGE) SIDE AND CROSS RODS AT 16" OC VERTICALLY IN ALL WALLS AND PIERS, AND AT 8" OC VERTICALLY AT PARAPETS. WHERE VERTICAL BARS ARE REQUIRED, CONSTRUCT CMU WALL TO PROVIDE A CONTINUOUS UNOBSTRUCTED CELL FROM BOTTOM TO TOP OF BAR. CELL CONTAINING A SINGLE BAR SHALL NOT BE LESS THAN 3" X 4" IN PLAN AREA.

PORTIONS OF CMU CONSTRUCTION REQUIRING STRUCTURAL FILL SHALL USE GROUT ONLY. USE OF CONCRETE FILL IN CMU CONSTRUCTION IS NOT PERMITTED. WHERE CLEARANCES AND CONGESTION PERMIT, USE COARSE GROUT WITH PEA GRAVEL AGGREGATE; OTHERWISE USE FINE GROUT.

REFER TO ARCHITECTURAL DRAWINGS FOR LOCATION OF ALL VERTICAL CONTROL JOINTS IN EXTERIOR WYTHES OF EXTERIOR WALLS, AND IN ALL INTERIOR PARTITION WALLS.

PROVIDE STEEL PIPE SLEEVES AT ALL LOCATIONS WHERE PIPING PASSES THROUGH CMU WALL.

WHERE BOND BEAMS INTERSECT AT WALL CORNERS AT DIFFERENT ELEVATIONS, RUN EACH BOND BEAM AROUND THE CORNER FOR A MINIMUM OF TWO FULL BLOCK LENGTHS BEFORE TERMINATING. WHERE BOND BEAMS ADJOIN ON THE SAME WALL AT DIFFERENT ELEVATIONS, RUN BOND BEAMS PAST ONE ANOTHER A MINIMUM OF FOUR FULL BLOCK LENGTHS BEFORE TERMINATING.

- STRUCTURAL STEEL

DESIGN, DETAILING, AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE SPECIFICATION FOR STRUCTURAL STEEL BUILDINGS (AISC 360-16), THE CODE OF STANDARD PRACTICE FOR STEEL BUILDINGS AND BRIDGES (303-16), AND THE STEEL CONSTRUCTION MANUAL FIFTEENTH EDITION.

TYPICAL DETAILS INDICATE GENERAL CRITERIA FOR DESIGN AND DETAILING OF CONNECTIONS. THEY ARE NOT INTENDED TO CONVEY COMPLETE INFORMATION CONCERNING SIZE AND QUANTITY OF CONNECTORS, PLATES, ANGLES, WELDS AND SIMILAR ITEMS THAT ARE DEVELOPED THROUGH THE DESIGN OF AN INDIVIDUAL CONNECTION FOR A SPECIFIC SET OF LOADS AND COMBINATIONS. DETAILS THAT CONVEY SPECIFIC COMPONENT INFORMATION ESTABLISH MINIMUM REQUIREMENTS AND ARE NOT INTENDED TO CONVEY A COMPLETE DESIGN UNLESS NOTED.

UNLESS OTHERWISE NOTED, ALL STEEL TO STEEL FRAMING HAS BEEN SELECTED ASSUMING ATTACHMENTS FOR SHEAR ONLY, USING DOUBLE ANGLE OR DOUBLE BENT PLATE CONNECTIONS SHOP WELDED TO FRAMING MEMBER AND FIELD BOLTED TO SUPPORTING MEMBER WITH HIGH STRENGTH BOLTS IN BEARING. CONNECTIONS SHALL BE SYMMETRICAL ABOUT THE BEAM WEB. FABRICATORS PROPOSING TO USE ALTERNATIVE METHODS OF ATTACHMENT NOT SPECIFICALLY DETAILED ON THE STRUCTURAL DRAWINGS SHALL SUBMIT ALTERNATIVE FOR CONSIDERATION DURING BIDDING, AND SHALL BEAR ALL COSTS ASSOCIATED WITH REVIEW, ENGINEERING REDESIGN, AND APPROVAL OF ALTERNATIVE CONNECTIONS.

SINGLE PLATE SHEAR TAB CONNECTIONS MAY BE USED IN LIEU OF DOUBLE ANGLE OR DOUBLE BENT PLATE CONNECTIONS WHERE SPECIFICALLY NOTED ON DRAWINGS. TO HSS OR PIPE COLUMNS, OR WHERE CONNECTION OF FRAMING MEMBER TO ONE SIDE OF A SUPPORT MEMBER IS MATCHED BY A SIMILAR CONNECTION ON THE OPPOSITE SIDE OF THE SAME SUPPORT MEMBER, AND WHERE BEAM SPANS DO NOT DIFFER BY MORE THAN 50% OF THE LARGER SPAN. SINGLE PLATE SHEAR TABS MAY NOT BE USED FOR CONNECTION OF FRAMING MEMBERS TO WIDE FLANGE COLUMNS OR TO SPANDREL (EDGE) SUPPORT MEMBERS UNLESS SPECIFICALLY DETAILED ON DRAWINGS.

FOR ALL SLOTTED HOLES, ANCHORS SHALL BE CENTERED IN SLOT UNLESS NOTED OTHERWISE.

CONNECTIONS FOR ALL STRUCTURAL STEEL BEAMS AND GIRDERS SHALL BE DESIGNED FOR THE REACTIONS SHOWN. REACTIONS SHOWN ON THE DRAWINGS WITHOUT INDIVIDUAL LOAD DESIGNATIONS HAVE BEEN COMBINED USING STRENGTH COMBINATIONS. IF NO REACTION IS SHOWN:
- NON-COMPOSITE BEAM AND GIRDER SHEAR CONNECTIONS SHALL BE DESIGNED FOR 50% OF THE TOTAL UNIFORM LOAD CAPACITY FOR THE GIVEN MEMBER SIZE, SPAN, AND GRADE OF STEEL.
- UNLESS DESIGN MOMENTS ARE SPECIFICALLY NOTED ON THE DRAWINGS, MOMENT CONNECTIONS SHALL BE DESIGNED TO FULLY DEVELOP THE MOMENT CAPACITY OF THE BEAM OR GIRDER

CONNECTIONS NOT SHOWN OR NOT COMPLETELY DETAILED ON THE DRAWINGS SHALL BE COMPLETED BY ONE OF THE FOLLOWING METHODS:
- STANDARD AISC FRAMED CONNECTIONS MEETING OTHER REQUIREMENTS OF THE DRAWINGS AND SPECIFICATIONS MAY BE SELECTED OR COMPLETED BY AN EXPERIENCED STEEL DETAILER RETAINED BY THE FABRICATOR IN ACCORDANCE WITH AISC 303-16, PARAGRAPH 3.1.1.2 AND USING STRENGTH DESIGN CONCEPTS.
- ALL CONNECTIONS IN THE FOLLOWING LIST AND ALL CONNECTIONS NOT MEETING THE LIMITATIONS OF STANDARD AISC FRAMED CONNECTIONS SHALL BE DESIGNED BY A PROFESSIONAL ENGINEER REGISTERED IN THE STATE IN WHICH THE PROJECT IS CONSTRUCTED AND RETAINED BY THE FABRICATOR IN ACCORDANCE WITH AISC AISC 303-16, PARAGRAPH 3.1.1.3 AND USING STRENGTH DESIGN CONCEPTS:
  1. TENSION CONNECTIONS NOT COMPLETELY DETAILED ON THE DRAWINGS, INCLUDING CONSIDERATION OF PRYING ACTION.
  2. MOMENT CONNECTIONS NOT COMPLETELY DETAILED ON THE DRAWINGS.
  3. BRACED FRAME CONNECTIONS NOT COMPLETELY DETAILED ON THE DRAWINGS

IN NO CASE SHALL A CONNECTING ELEMENT CONTAIN LESS THAN TWO HIGH STRENGTH BOLTS ON EACH CONNECTING SURFACE, OR UTILIZE LESS THAN 3/16" FILLET WELDS, OR BE LESS THAN T/2 IN DEPTH. IN NO CASE SHALL A CONNECTION BE DESIGNED FOR A SHEAR REACTION LESS THAN 18 KIPS (STRENGTH DESIGN)

DESIGN OF STAIRS, HANDRAILS, GUARDRAILS AND LADDERS SHALL BE BY THE STEEL SUPPLIER.

REFER TO ARCHITECTURAL DRAWINGS FOR MISCELLANEOUS STRUCTURAL STEEL NOT NOTED ON STRUCTURAL DRAWINGS.

PROVIDE CLEVISES, PINS, RODS AND TURNBUCKLES WITH CAPACITIES NOT LESS THAN THOSE LISTED IN THE AISC STEEL CONSTRUCTION MANUAL.

PROVIDE HOLES IN BEAMS TO ACCOMMODATE WOOD CONNECTIONS TO STEEL.

WELDER REQUIREMENTS: TECHNIQUE FOR WELDING AND QUALIFICATION OF WELDING PERSONNEL SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS LISTED IN IBC SECTION 2205. 2206, 2207. 2208, 2210, AND 2211 AS APPLICABLE. ALL WELDING IS TO BE COMPLETED BY A LICENSED STRUCTURAL WELDER ISSUED BY GOVERNING AUTHORITY IN WHICH STATE THE PROJECT RESIDES.

- JOISTS

DESIGN, FABRICATION AND ERECTION OF JOISTS AND LONGSPAN JOISTS, AND JOIST GIRDERS SHALL BE IN ACCORDANCE WITH THE 2015 STEEL JOIST INSTITUTE (SJI) STANDARDS

ALL STANDARD K AND LH SERIES JOISTS SHALL BE DESIGNED FOR A SHEAR CAPACITY EQUAL TO THE REACTION, AND VARYING LINEARLY TO 25% OF THE REACTION AT THE MIDSPAN OF THE JOIST. IN ORDER TO ACCOUNT FOR POTENTIAL STRESS REVERSALS THE SHEAR CAPACITY OF THE JOIST SHALL BE MAINTAINED AT THE 25% VALUE FOR A DISTANCE BEYOND THE MIDSPAN EQUAL TO MINIMUM OF ONE PANEL WIDTH, ROUNDED UP TO THE NEXT PANEL POINT.

WHERE JOISTS ARE DESIGNATED BY DEPTH, SERIES AND TOTAL LOAD / LIVE LOAD, FINAL DESIGN SHALL BE PER NOTED LOAD PLUS SELF WEIGHT OF JOIST AND IS THE RESPONSIBILITY OF THE JOIST SUPPLIER.

WHERE STANDARD JOIST DESIGNATION FOR DEPTH AND SERIES PRECEDES THE DESIGNATION "SP", SPECIAL JOIST SHALL HAVE THAT DEPTH AND THE STANDARD SEAT DEPTH FOR THE SPECIFIED SERIES. JOIST SUPPLIER SHALL PROVIDE A DESIGN PER THE PROVIDED LOADING CONDITIONS PLUS THE SELF WEIGHT OF THE JOIST.

WHERE STANDARD JOIST DESIGNATION FOR DEPTH AND SERIES PRECEDES THE DESIGNATION "SP", FINAL DESIGN SHALL BE PER LOADING DIAGRAM PROVIDED PLUS SELF WEIGHT OF JOIST, SHALL USE THE DEPTH AND STANDARD SEAT DEPTH AND SERIES INDICATED AND IS THE RESPONSIBILITY OF THE JOIST SUPPLIER.

WHERE BRIDGING INTERFERES WITH MECHANICAL OR OTHER TRADE INSTALLATION, CONTRACTOR MAY REMOVE BRIDGING AFTER METAL DECK IS COMPLETE IN PLACE, UPON RECEIPT OF WRITTEN APPROVAL FROM THE JOIST ENGINEER. BRIDGING REMOVED SHALL BE REPLACED AS DIRECTED BY THE JOIST ENGINEER, INCLUDING ADDITIONAL SUPPLEMENTAL BRACING AS MAY BE NECESSARY IN THE SOLE JUDGEMENT OF THE JOIST ENGINEER.

NO FIELD DRILLED HOLES OR CUTS ARE PERMITTED IN ANY JOIST CHORD OR WEB MEMBER.

MAXIMUM HANGER LOAD TO BE LOCATED ALONG BAR JOIST TOP CHORD BETWEEN PANEL POINTS IS 350 POUNDS AND 100 POUNDS TO JOIST BOTTOM CHORD BETWEEN PANEL POINTS. JOIST SUPPLIER TO DESIGN CHORDS FOR THESE LOADS AS A BEND-CHECK CONDITION.


ALL CONCENTRATED LOADS EXCEEDING THE VALUES IN THE PRECEDING PARAGRAPH SHALL BE APPLIED AT A JOIST PANEL POINT UNLESS LOADS ARE INDICATED ON LOAD DIAGRAMS AND CHORDS HAVE BEEN SPECIFICALLY DESIGNED FOR CONCENTRATED LOADS, OR UNLESS SUPPLEMENTAL CHORD BRACING IS PROVIDED. SUPPLEMENTAL CHORD BRACING SHALL BE PROVIDED AS DETAILED ON THE DRAWINGS BY THE CONTRACTOR RESPONSIBLE FOR THE CONCENTRATED LOADS NOT APPLIED AT PANEL POINTS.

JOISTS AND SEAT CONNECTIONS SHALL BE DESIGNED TO RESIST AXIAL LOADS INDICATED, OR RESIST A HORIZONTAL FORCE ACTING PARALLEL TO THE JOIST NOT LESS THAN 5% OF THE (DEAD + LI

CONCRETE MIX DESIGN


CLASS	TYPE OF CONSTRUCTION	SPECIFIED COMP STRENGTH AT 28 DAYS (PSI)	MAXIMUM AGGREGATE SIZE (IN)	MINIMUM LBS OF CEMENT PER CY (NOTE 7)	AIR ENTRAINMENT % +/- 1 1/2%	NOTES
1	ALL FOOTINGS	3,000	1.5	470	NONE	4
2	WALLS/PIERS	4,000	0.75	494	NONE	4
3	EXPOSED WALLS	4,000	0.75	540	6.0	5
4	INTERIOR SLAB-ON-GROUND	4,000	1.0 (NOTE 6)	540	NONE	3,4,8
5	EXTERIOR SLAB-ON-GROUND	4,500	0.75	564	6.0	1,2,5
6	BOND BEAMS	3,000	0.375	470	NONE	4
7	MISCELLANEOUS NON-SCHEDULED CONCRETE WORK	3,000	0.75	470	6.0	1,5

NOTES:
1. AIR ENTRAINED CONCRETE, USE FOR EXTERIOR WALLS, EXTERIOR SLABS, WALKS, PLATFORMS, RAMPS, STEPS, PORTIONS OF PARKING RAMP AND OTHER CONCRETE EXPOSED TO FREEZING AND THAWING.
2. MAXIMUM WATER—CEMENTITIOUS RATIO BY WEIGHT SHALL BE 0.45.
3. MAXIMUM WATER—CEMENTITIOUS RATIO BY WEIGHT SHALL BE 0.50.
4. A MAXIMUM OF 50 PERCENT TOTAL REPLACEMENT OF PORTLAND CEMENT WITH GGBFS (GROUND GRANULATED BLAST—FURNACE SLAG) AND FLY ASH AT A 1:1 RATIO; UP TO 350 POUNDS, WITH A MAXIMUM 25 PERCENT FLY ASH. IF FLY ASH IS USED ALONE, LIMIT MAXIMUM REPLACEMENT TO 25 PERCENT.
5. A MAXIMUM OF 30 PERCENT TOTAL REPLACEMENT OF PORTLAND CEMENT WITH GGBFS (GROUND GRANULATED BLAST—FURNACE SLAG) AND FLY ASH AT A 1:1 RATIO WHERE FREEZE—THAW DURABILITY AND EXPOSURE TO DEICERS IS LIKELY; UP TO 350 POUNDS, WITH A MAXIMUM 25 PERCENT FLY ASH. IF FLY ASH IS USED ALONE, LIMIT MAXIMUM REPLACEMENT TO 25 PERCENT.
6. INCREASE AGGREGATE SIZE TO 1 1/2" IF SLAB-ON-GROUND TO BE PLACED BY LASER SCREED.
7. MINIMUM AMOUNT OF CEMENTITIOUS MATERIAL IDENTIFIED IN THE MIX PROPORTIONS SHALL APPLY FOR MIXES FOR WHICH FIELD EXPERIENCE OR TRIAL MIXTURE INFORMATION REQUIRED IS NOT PROVIDED.
8. MIX SHALL BE DESIGNED SUCH THAT SHRINKAGE SHALL BE LESS THAN OR EQUAL TO 0.040 AFTER 28 DAYS. CONCRETE SUPPLIER SHALL PERFORM SHRINKAGE BEAM TESTING TO VERIFY CONCRETE PERFORMANCE IN ACCORDANCE WITH ASTM C157 AND SUBMIT RESULTS FOR REVIEW.



DRIFT MARK	PARAPET HT. PT.1	PARAPET HT. PT.2	DRIFTING SNOW LOAD PT.1 PSF	PT.1 X1	PT.2 PSF	PT.2 X2
A	2'-0"	1'-5"	35.8	4.8'	25	0'
B	2'-0"	2'-0"	35.8	4.8'	35.8	4.8'
C	4'-0"	3'-0"	71.6	20.7'	53.7	12.8'

1 S0.2 DRIFTING SNOW LOADS
SCALE: 12" = 1'-0"



3D VIEW

COMPONENTS AND CLADDING WIND PRESSURES (PSF)


ZONE	WIND AREA (SF)	ROOF SLOPE 0° TO 7° (+)	ROOF SLOPE 0° TO 7° (-)
1	10	8.9	34.7
1	50	7.6	29.4
1	100	7.0	27.1
1'	10	8.9	19.9
1'	50	7.6	19.9
1'	100	7.0	19.9
2	10	8.9	45.7
2	50	7.6	38.9
2	100	7.0	36.0
3	10	8.9	62.3
3	50	7.6	48.7
3	100	7.0	42.8
(-) WIND PRESSURE ON ROOF OVERHANGS			

LOCATION	WIND AREA (SF)	ROOF SLOPE 0° TO 7° ZONES 1&1'	ZONE 2	ZONE 3
OVERHANG	10	31.4	42.4	59.0
OVERHANG	20	30.8	38.5	52.2
OVERHANG	50	30.1	33.3	43.1
OVERHANG	100	29.5	29.4	36.2

ZONE	WIND AREA (SF)	(+)	(-)
4	10	21.8	23.6
4	20	20.8	22.6
4	50	19.5	21.3
4	100	18.5	20.4
5	10	21.8	29.1
5	20	20.8	27.2
5	50	19.5	24.6
5	100	18.5	22.6
ADJUSTMENT FACTOR (A)			

MEAN ROOF HEIGHT (FT)	EXPOSURE B	EXPOSURE C	EXPOSURE D
15	0.82	1.21	1.47
20	0.89	1.29	1.55
30	1.00	1.40	1.66
35	1.05	1.45	1.70
40	1.09	1.49	1.74
45	1.12	1.53	1.78
50	1.16	1.56	1.81
55	1.19	1.59	1.84
60	1.22	1.62	1.87

NOTES:
1. TABULATED LOADS ARE BASED ON ASCE 7-16 SIMPLIFIED PROVISIONS FOR ENCLOSED REGULAR-SHAPED BUILDINGS WITH THE FOLLOWING PARAMETERS: WIND SPEED = 110 MPH, MEAN ROOF HEIGHT = 30'-0", EXPOSURE B, K_{zt} = 1.0.
2. FOR DIFFERENT MEAN ROOF HEIGHTS OR EXPOSURES, TABULATED VALUES SHALL BE MULTIPLIED BY THE ADJUST FACTOR (A) CONTAINED WITHING THE ABOVE TABLE.
3. FOR WIND PRESSURES BELOW 16 PSF AFTER ALL ADJUSTMENT FACTORS HAVE BEEN TAKEN INTO ACCOUNT, A MINIMUM WIND PRESSURE OF 16 PSF SHALL BE USED FOR DESIGN. THOSE PRESSURES INDICATED BY ▭ IN THE ABOVE TABLE ARE THOSE THAT FALL BELOW THE MINIMUM VALUE BASED ON NO ADJUSTMENTS.
4. WIND PRESSURES INDICATED ARE STRENGTH LEVEL VALUES.
5. TABLE LEGEND:
   - (+) = POSITIVE (INWARD) PRESSURE
   - (-) = NEGATIVE (OUTWARD) PRESSURE
   - SF = SQUARE FEET
6. FOR EFFECTIVE MEMBER AREAS NOT SPECIFICALLY LISTED, INTERPOLATE OR USE LARGEST VALUE OF WIND PRESSURE / SUCTION NOTED. DO NOT USE 1/3 STRESS INCREASE FOR MEMBER DESIGN WITH VALUES NOTED IN THIS TABLE.



FLAT ROOF
ROOF SLOPE 7° OR LESS

UNCOATED TENSION DEVELOPMENT & CLASS "B" LAP SPLICE SCHEDULE (f'c = 4,000 psi)

BAR SIZE	TENSION DEVELOPMENT LENGTH CLR COV = .75" BOT BARS	TOP BARS	CLR COV = 1" BOT BARS	TOP BARS	CLR COV = 1.5" BOT BARS	TOP BARS	CLASS "B" TENSION LAP LENGTH CLR COV = .75" BOT BARS	TOP BARS	CLR COV = 1" BOT BARS	TOP BARS	CLR COV = 1.5" BOT BARS	TOP BARS
#3	12	12	12	12	12	12	12	15	12	15	12	15
#4	15	19	12	15	12	15	19	24	15	20	15	20
#5	21	28	17	22	15	19	28	36	22	29	19	24
#6	29	37	24	31	17	22	37	48	31	40	22	29
#7	46	60	38	50	28	37	60	78	50	64	37	48
#8	57	74	48	62	36	47	74	96	62	80	47	60
#9	69	90	58	76	44	57	90	117	76	98	57	74
#10	83	108	70	92	54	70	108	140	92	119	70	91
#11	98	127	83	108	64	84	127	165	108	141	84	109

SCHEDULE NOTES:
1) BASED ON:
   1a. GRADE 60 REINFORCEMENT BARS.
   1b. NORMAL WEIGHT CONCRETE.
   1c. FOR BARS IN WALLS AND SLABS.
2) TOP BARS ARE HORIZONTAL BARS WITH MORE THAN 12" OF CONCRETE BELOW THE BARS.
3) FOR LIGHTWEIGHT CONCRETE, MULTIPLY TABLED VALUES BY 1.33.

THIS SCHEDULE IS PROVIDED FOR THE CONVENIENCE OF THE CONTRACTOR AND IS NOT INTENDED TO COVER ALL SITUATIONS. SHOP DRAWINGS SHALL CLEARLY INDICATE ALL REQUIRED LAP LENGTHS.

UNCOATED TENSION DEVELOPMENT & CLASS "B" LAP SPLICE SCHEDULE (f'c = 3,000 psi)

BAR SIZE	TENSION DEVELOPMENT LENGTH CASE 1 BOT BARS	CASE 1 TOP BARS	CASE 2 BOT BARS	CASE 2 TOP BARS	CLASS "B" TENSION LAP LENGTH CASE 1 BOT BARS	CASE 1 TOP BARS	CASE 2 BOT BARS	CASE 2 TOP BARS
#3	17	22	25	32	22	28	32	42
#4	22	29	33	43	29	37	43	56
#5	28	36	41	54	36	47	54	70
#6	33	43	50	64	43	56	64	84
#7	48	63	72	94	63	81	94	122
#8	55	72	82	107	72	93	107	139
#9	62	81	93	121	81	105	121	157
#10	70	91	105	136	91	118	136	177
#11	78	101	116	151	101	131	151	196

SCHEDULE NOTES:
1) BASED ON:
   1a. GRADE 60 REINFORCEMENT BARS.
   1b. NORMAL WEIGHT CONCRETE.
2) CASE DEFINITIONS (db = BAR DIAMETER)
   CASE 1: BEAMS, COLUMNS: W/ COVER ≥ 1.0db & C-C BAR SPACING ≥ 2.0db
   ALL OTHER UNO: W/ COVER ≥ 1.0db & C-C BAR SPACING ≥ 3.0db
   CASE 2: BEAMS, COLUMNS: W/ COVER < db OR C-C BAR SPACING < 2.0db
   ALL OTHER UNO: W/ COVER < db OR C-C BAR SPACING < 2.0db
3) TOP BARS ARE HORIZONTAL BARS WITH MORE THAN 12" OF CONCRETE BELOW THE BARS.
4) FOR LIGHWEIGHT CONCRETE, MULTIPLY TABLED VALUES BY 1.33.

THIS SCHEDULE IS PROVIDED FOR THE CONVENIENCE OF THE CONTRACTOR AND IS NOT INTENDED TO COVER ALL SITUATIONS. SHOP DRAWINGS SHALL CLEARLY INDICATE ALL REQUIRED LAP LENGTHS.

STANDARD ABBREVIATIONS:

AB	ANCHOR BOLT (ROD)	LLBB	LONG LEG BACK TO BACK
AHU	AIR HANDLING UNIT	LLH	LONG LEG HORIZONTAL
ALT	ALTERNATE	LLV	LONG LEG VERTICAL
APPROX	APPROXIMATELY	LP	LOW POINT
ARCH	ARCHITECTURAL	LSB	CLASS 'B' BAR LAP
BF	BOTTOM OF FOOTING	LSL	LAMINATED STRAND LUMBER
BS	BOTTOM OF STEEL	LTWT	LIGHTWEIGHT
BC	BOTTOM CHORD	LVL	LAMINATED VENEER LUMBER
BLDG	BUILDING	LW	LONG WAY
BRG	BEARING	MAX	MAXIMUM
BTWN	BETWEEN	MECH	MECHANICAL
CB	CATCH BASIN	MFR	MANUFACTURER
CIP	CAST-IN-PLACE	MIN	MINIMUM
CJ	CONTROL JOINT	MISC	MISCELLANEOUS
CL	CENTER LINE	MO	MASONRY OPENING
CLR	CLEAR (DISTANCE)	MS	MIDDLE STRIP
CMU	CONCRETE MASONRY UNIT	NA	NOT APPLICABLE
COL	COLUMN	NIC	NOT IN CONTRACT
CONC	CONCRETE	NOM	NOMINAL
CONT	CONTINUOUS	NTS	NOT TO SCALE
CS	COLUMN STRIP	OC	ON CENTER
DBA	DEFORMED BAR ANCHOR OR DECK BEARING ANGLE	OD	OUTSIDE DIAMETER
		OF	OUTSIDE FACE
DBE	DECK BEARING ELEVATION	OPNG	OPENING
DEMO	DEMOLITION / DEMOLISH	OPP	OPPOSITE
DIA	DIAMETER	OSL	OUTSTANDING LEG
DL	DEAD LOAD	PC	PRECAST / PRESTRESSED
DWG	DRAWING	PCI	POUNDS PER CUBIC INCH
EOD	EDGE OF DECK	PDF	POUNDS PER CUBIC FOOT
EOS	EDGE OF SLAB	PL	PLATE
EF	EACH FACE	PLBG	PLUMBING
EJ	EXPANSION JOINT	PLF	POUNDS PER LINEAR FOOT
EL	ELEVATION	PROJ	PROJECTION
ELEC	ELECTRICAL	PSF	POUNDS PER CUBIC FOOT
ENG	ENGINEER	PSI	POUNDS PER SQUARE INCH
EQ	EQUAL	PT	PRE (POST) -TENSIONED
ES	EDGE STRIP	RD	ROOF DRAIN
EW	EACH WAY	REF	REFERENCE
EWEF	EACH WAY EACH FACE	REINF	REINFORCE(D)
EXP	EXPANSION	REM	REMAINDER
EXT	EXTERIOR	RTU	ROOF TOP UNIT
EXTG or (e)	EXISTING	SC	SLIP CRITICAL
FD	FLOOR DRAIN	SCHED	SCHEDULE
FLG	FLANGE	SHT	SHEET
FLR	FLOOR	SIM	SIMILAR
FND	FOUNDATION	SL	SNOW LOAD
FTG	FOOTING	SLBB	SHORT LEGS BACK TO BACK
FRMG	FRAMING	SOG	SLAB-ON-GRADE
FUT	FUTURE	SPA	SPAC(ES)(ED)(ING)
FV	FIELD VERIFY	SPEC	SPECIFICATION(S)
GA	GAUGE	SQ	SQUARE
GALV	GALVANIZED	SS	STAINLESS STEEL
GC	GENERAL CONTRACTOR	STD	STANDARD
GLULAM	GLUE-LAMINATED BEAM(S)	SW	SHORT WAY
GT	GIRDER TRUSS	TF	TOP OF FOOTING
HK	HOOK	TL	TOP OF LEDGE
HORIZ	HORIZONTAL	TP	TOP OF PIER
HP	HIGH POINT	TS	TOP OF STEEL
HVAC	HEATING, VENTILATING, AND AIR CONDITIONING	TW	TOP OF WALL
		TC	TENSION CONTROL
HWS	HEADED WELDED STUD(S)	TC	TOP CHORD
ID	INSIDE DIAMETER	THK	THICK (NESS) (ENED)
IF	INSIDE FACE	TL	TOTAL LOAD
INT	INTERIOR	TYP	TYPICAL
JBE	JOIST BEARING ELEVATION	UNO	UNLESS NOTED OTHERWISE
K	KIP	VERT	VERTICAL
KO	KNOCKOUT PANEL	VIF	VERIFY IN FIELD
KSI	KIPS PER SQUARE INCH	VWA	VERIFY WITH ARCHITECT
L	ANGLE	WL	WIND LOAD
LB	POUNDS	WP	WORKING POINT
LL	LIVE LOAD	WWF	WELDED WIRE FABRIC

raSmith
CREATIVITY BEYOND ENGINEERING
project number 2220439
1674S W. Bluemound Road
Brookfield, WI 53005-5938
(262) 781-1000
rasmith.com

REVISIONS:

ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI

STRUCTURAL NOTES

Partners in Design ARCHITECTS
2610 Lake Cook Road Suite 280 Riverwoods, IL 60015 Ph.: (847)940-0300

PROJECT NO.: 522.22.031
DRAWN BY: EMS CHECKED BY: SJR
DATE: 03.09.26
SHEET NO.: S0.2

© 2026 Partners in Design Architects, Inc.

STATEMENT OF SPECIAL INSPECTIONS (IBC 2021 SECTION 1704.3)

SPECIAL INSPECTION NOTES:

Special inspections are required for materials, installation, fabrication, erection or placement of components and connections requiring special expertise to insure compliance with approved construction documents and applicable referenced standards. The Owner or a registered design professional in responsible charge retained by the Owner and acting as the Owner's agent shall employ one or more approved agencies to provide inspections during construction on the types of work listed under IBC Section 1705.

Special inspectors must be approved by the building official and be objective, competent and independent from the contractor responsible for the work being inspected. Special inspectors must have the adequate equipment to perform required tests, and experienced personnel educated in conducting, supervising, and evaluating tests and special inspections. Any approved agency must provide written documentation of qualifications to the building official in accordance with IBC Section 1704.2.1.

Material approval, performance tests, labeling, and evaluation shall be in compliance with IBC Section 1703.

Construction requiring special inspections must be accessible and exposed for inspection and testing purposes until completion of inspections and tests (1704.2.2).

Special Inspectors shall keep records of inspections per 1704.2.4. The Special Inspector shall furnish inspection reports to the building official and to the registered design professional in responsible charge. Reports shall indicate that the work inspected was done in conformance to approved construction documents. In addition to the reports for the special inspections and tests, the owner or owner's authorized agent shall submit reports and certificates per IBC 2021 Section 1704.5.

Discrepancies shall be brought to the immediate attention of the contractor for correction. If they are not corrected the discrepancies shall be brought to the attention of the building official and to the registered design professional in responsible charge prior to the completion of that phase of the work.

A final report of inspections documenting required special inspections and tests, and correction of any discrepancies noted in the inspections shall be submitted periodically at a point in time agreed upon by the permit applicant and the building official prior to the start of the work.

Where fabrication of structural load-bearing or lateral load resisting members and assemblies is being performed on the premises of a fabricator's shop, special inspection of the fabricated items shall be performed during fabrication in accordance with section 1704.2.5 except where the fabricator has been approved to perform work without special inspections in accordance with Section 1704.2.5.1. Approved fabricators, approved in accordance with 1704.2.5.1 shall submit a certificate of compliance upon completion of fabrication.

Each contractor responsible for the construction of a main wind- or seismic force resisting system, designated seismic system or a wind- or seismic force-resisting component listed in the statement of special inspections shall submit a written statement of responsibility to the building official and the owner or owner's authorized agent prior to the commencement of work on the system or component per IBC 2021 Section 1704.4.

Structural observations are not required, **[in accordance with section 1704.6, and shall be made by a registered design professional. Observations shall not waive the necessity for the structural inspections.]**

Structural observations for seismic resistance are not required in accordance with section 1704.6.1.

Structural observations for wind resistance are not required in accordance with section 1704.6.1.

The following statement of special inspections must be submitted by the applicant.

STEEL CONSTRUCTION (1705.13.1)

Special Inspections for seismic resistance shall be in accordance with Section 1705.13.1.1 or 1705.13.1.2, as applicable.

1705.13.1.1 & 1705.13.1.2. Seismic force-resisting systems. Special inspections of structural steel in the seismic force-resisting systems and elements in the resisting system of buildings and structures assigned to Seismic Design Category B, C, D, E or F shall be performed in accordance with the quality assurance requirements of AISC 341 as indicated below.

> Observe shall mean to observe items indicated on a random basis.
> Perform shall mean to perform tasks on each element (welded joint/member, bolted joint/member, or steel element in composite construction).
> Document shall mean the inspector shall prepare reports indicating that the work has been performed in accordance with the contract documents.

PERFORM	OBSERVE	DOCUMENT	REQUIRED VERIFICATION AND INSPECTIONS
			1. Inspection Tasks Prior to Welding (AISC 341 Table J6.1)
-	x	-	a. Material Identification (Type / Grade)
-	x	-	b. Welder Identification system
-	x	-	c. Fit-up of Groove Welds (including joint geometry)
			- Joint Peparation
			- Dimension (alignment, root opening, root face, bevel)
			- Cleanliness (condition of steel surfaces)
			- Tacking (tack weld quality and location)
			- Backing type and fit (if applicable)
-	x	-	d. Configuration and finish of access holes
-	x	-	e. Fit-up of fillet welds
			- Dimensions (alignment, gaps at root)
			- Cleanliness (condition of steel surfaces)
			- Tacking (tack weld quality and location)
			2. Inspection Tasks During Welding (AISC 341 Table J6.2)
-	x	-	a. WPS followed
			- Settings on welding equipment
			- Travel speed
			- Selected welding materials
			- Shielding gas type/flow rate
			- Preheat applied
			- Interpass temperature maintained (min/max)
			- Proper position (F, V, H, OH)
			- Intermix of filler metals avoided unless approved
-	x	-	b. Use of qualified welders
-	x	-	c. Control and handling of welding consumables
			- Packaging
			- Exposure control
-	x	-	d. Environmental conditions
			- Wind speed within limits
			- Precipitation and temperature
-	x	-	e. Welding techniques
			- Interpass and final cleaning
			- Each pass within profile limitations
			- Each pass meets quality requirements
-	x	-	f. No welding over cracked tacks
			3. Inspection Tasks After Welding (AISC 341 Table J6.3)
-	x	-	a. Welds cleaned
x	-	-	b. Size, length, and location of welds
x	-	x	c. Welds meet visual acceptance criteria
			- Crack prohibition
			- Weld / base-metal fusion
			- Crater cross section
			- Weld profiles and size
			- Undercut
			- Porosity
x	-	x	d. When welding of doubler plates, continuity plates or stiffeners has been performed in the k-area, visually inspect the web k-area for cracks within 3" of the weld. Perform inspection after 48 hours following completion of the welding.
x	-	x	e. Placement of reinforcing or contouring fillet welds (if required)
x	-	x	f. Backing removed, weld tabs removed and finished, and fillet welds added (if required)
x	-	x	g. Repair activities
			4. Inspection Tasks Prior to Bolting (AISC 341 Table J7.1)
-	x	-	a. Proper fasteners selected for the joint detail
-	x	-	b. Proper bolting procedure selected for joint detail
-	x	-	c. Connecting elements, including the faying surface condition and hole preparation, if specified, meet applicable requirements
-	x	x	d. Pre-installation verification testing by installation personnel observed for fastener assemblies and methods used.
-	x	-	e. Proper storage provided for bolts, nuts, washers and other fastener components
			5. Inspection Tasks During Bolting (AISC 341 Table J7.2)
-	x	-	a. Fastener assemblies placed in all holes and washers (if required) are positioned as required
-	x	-	b. Joint brought to the snug tight condition prior to the pretensioning operation
-	x	-	c. Fastener component not turned by the wrench prevented from rotating
-	x	-	d. Bolts are pretensioned progressing systematically from the most rigid point toward the free edges
			6. Inspection Tasks After Bolting (AISC 341 Table J7.3)
x	-	x	a. Document accepted and rejected connections
			7. Other Inspection Tasks (AISC 341 Table J8.1)
x	-	x	a. RBS requirements, if applicable
			- Contour and finish
			- Dimensional tolerances
x	-	x	b. Protected zone-no holes and unapproved attachments made by fabricator or erector, as applicable.

STEEL CONSTRUCTION (1705.2):

Steel construction shall be inspected and verified in accordance with the requirements of Sections 1705.2. Special inspection for structural steel shall be in accordance with the quality assurance inspection requirements of AISC 360-16 Chapter N.

> Observe shall mean to observe items indicated on a random basis.
> Perform shall mean to perform tasks on each element (welded joint/member, bolted joint/member

PERFORM	OBSERVE	REQUIRED VERIFICATION AND INSPECTIONS
		1. Inspection Tasks Prior to Welding (AISC 360 Table N5.4-1)
-	x	a. Welder qualification records and continuity records.
x	-	b. Welding procedure specifications (WPS) available.
x	-	c. Manufacturer certifications for welding consumables available
-	x	d. Material identification (type/grade)
-	x	e. Welder identification system (The fabricator or erector, as applicable, shall maintain a system by which a welder who has welded a joint or member can be identified. Stamps, if used, shall be the low-stress type)
-	x	f. Fit-up of groove welds (including joint geometry)
		- Joint Preparations
		- Dimensions (alignment, root opening, root face, bevel)
		- Cleanliness (condition of steel surfaces)
		- Tacking (tack weld quality and location)
		- Backing type and fit (if applicable)
-	x	g. Fit-up of CJP groove welds to HSS T-, Y- and K-joints without backing (including geometry)
		- Joint Preparations
		- Dimensions (alignment, root opening, root face, bevel)
		- Cleanliness (condition of steel surfaces)
		- Tacking (tack weld quality and location)
-	x	h. Configuration and finish of access holes
-	x	i. Fit-up of fillet welds
		- Dimensions (alignment, gaps at root)
		- Cleanliness (condition of steel surfaces)
		- Tacking (tack weld quality and location)
		2. Inspection Tasks During Welding (AISC 360 Table N5.4-2)
-	x	a. Control and handling of welding consumables
		- Packaging
		- Exposure Control
-	x	b. No welding over cracked tack welds
-	x	c. Environmental conditions
		- Wind speed within limits
		- Precipitation and temperature
-	x	d. WPS followed
		- Settings on welding equipment
		- Travel speed
		- Selected welding materials
		- Shielding gas type/flow rate
		- Preheat applied
		- Interpass temperature maintained (min/max)
		- Proper position (F, V, H, OH)
-	x	e. Welding techniques
		- Interpass and final cleaning
		- Each pass within profile limitations
		- Each pass meets quality requirements.
x	-	f. Placement and installation of steel headed stud anchors.
		3. Inspection Tasks After Welding (AISC 360 Table N5.4-3)
-	x	a. Welds cleaned
x	-	b. Size, length and location of welds
x	-	c. Welds meet visual acceptance criteria
		- Crack prohibition
		- Weld/base-metal fusion
		- Crater cross section
		- Weld profiles
		- Weld size
		- Undercut
		- Porosity
x	-	d. Arc strikes
x	-	e. k-area (when welding of doubler plates, continuity plates or stiffeners has been performed in the k-area, visually inspect the web k-area for cracks within 3 in of the weld.
x	-	f. Weld access holes in rolled heavy shapes and built-up heavy shapes (After rolled heavy shapes and built-up heavy shapes are welded, visually inspect the weld access hole for cracks)
x	-	g. Backing removed and weld tabs removed (if required)
x	-	h. Repair activities.
x	-	i. Document acceptance or rejection of welded joint or member
-	x	j. No prohibited welds have been added without the approval of the EOR
		4. Inspection Tasks Prior to Bolting (AISC 360 Table N5.6-1)
x	-	a. Manufacturer's certifications available for fastener materials
-	x	b. Fasteners marked in accordance with ASTM requirements
-	x	c. Correct fasteners selected for the joint detail (grade, type, bolt length if threads are to be excluded from the shear plane)
-	x	d. Correct bolting procedure selected for joint detail
-	x	e. Connecting elements, including the appropriate faying surface condition and hole preparation, if specified, meet applicable requirements
-	x	f. Pre-installation verification testing by installation personnel observed and documented for fastener assemblies and methods used.
-	x	g. Protected storage provided for bolts, nuts, washers and other fastener components.
		5. Inspection Tasks during Bolting (AISC 360 Table N5.6-2)
-	x	a. Fastener assemblies, placed in all holes and washers are positioned as required
-	x	b. Joint brought to the snug-tight condition prior to the pretensioning operation
-	x	c. Fastener component not turned by the wrench prevented from rotating
-	x	d. Fasteners are pretensioned in accordance with the RCSC Specification, progressing systematically from the most rigid point toward the free edges.
		6. Inspection Tasks After Bolting (AISC 360 Table N5.6-3)
x	-	a. Document acceptance or rejection of bolted connections

OPEN-WEB STEEL JOISTS AND JOIST GIRDERS (1705.2.3 & TABLE 1705.2.3):

CONTINUAL	PERIODIC	REQUIRED VERIFICATION AND INSPECTIONS
		1. Installation of open-web steel joists and joist girders
	x	a. End connections - welded or bolted Reference Standard: SJI specifications listed in Section 2207.1
	x	b. Bridging - horizontal or diagonal 1. Standard Bridging Reference Standard: SJI specifications listed in Section 2207.1 2. Bridging that differs from the SJI specifications lited in Section 2207.1

COLD-FORMED STEEL DECK (1705.2.2):

Special inspections of cold-formed steel deck shall be in accordance with SDI QA/QC-2017, "Standard for Quality Control and Quality Assurance for the Installation of Steel Deck"

> Observe shall mean to inspect items indicated on a periodic basis.
> Perform shall mean to perform these tasks prior to final acceptance for each item or element.

PERFORM	OBSERVE	REQUIRED VERIFICATION AND INSPECTIONS
		1. Inspection or Execution Tasks Prior to Deck Placement (Table 1.1)
x		a. Verify compliance of materials (deck and all deck accessories) with construction documents, including profiles, material properties, and base metal thickness.
x		b. Document acceptance or rejection of deck and deck accessories.
		2. Inspection or Execution Tasks After Deck Placement (Table 1.2)
x		a. Verify compliance of deck and all deck accessories installation with construction documents.
x		b. Verify deck materials are represented by the mill certifications that comply with the construction documents
x		c. Document acceptance or rejection of installation of deck and deck accessories.
		6. Inspection or Execution Tasks Prior to Mechanical Fastening (Table 1.6)
	x	a. Manufacturer installation instructions available for mechanical fasteners.
	x	b. Proper tools available for fastener installation.
	x	c. Proper storage for mechanical fasteners.
		7. Inspection or Execution Tasks During Mechanical Fastening (Table 1.7)
	x	a. Fasteners are positioned as required.
	x	b. Fasteners are installed in accordance with manufacturer's instructions
		8. Inspection or Execution Tasks After Mechanical Fastening (Table 1.8)
x		a. Check spacing, type, and installation of support fasteners
x		b. Check spacing, type, and installation of sidelap fasteners.
x		c. Check spacing, type, and installation of perimeter fasteners.
x		d. Verify repair activities
x		e. Document acceptance or rejection of mechanical fasteners.

CONCRETE CONSTRUCTION (Table 1705.3):

CONTINUAL	PERIODIC	REQUIRED VERIFICATION AND INSPECTIONS
-	x	1. Inspect reinforcement, including prestressing tendons, and verify placement. Referenced Standards: ACI 318: Ch. 20, 25.2, 25.3, 26.6-1 - 26.6.3
-	-	2. Reinforcing Bar Welding
-	x	a. Verify weldability of reinforcing bars other than ASTM A706 Referenced Standards: AWS D1.4
-	x	b. Inspect Single-Pass Fillet Welds, Maximum 5/16" Referenced Standards: ACI 318: 26.6.4
x	-	c. Inspect All Other Welds
-	x	3. Inspect anchors cast in concrete Referenced Standards: ACI 318: 17.8.2
-	-	4. Inspection of anchors post-installed in hardened concrete
x	-	a. Adhesive anchors installed in horizontally or upwardly inclined orientations to resist sustained tension loads. Referenced Standards: ACI 17.8.2.4
-	x	b. Mechanical anchors and adhesive anchors not defined in 4a Referenced Standards: 17.8.2
-	x	5. Verifying use of required design mix. Referenced Standards: ACI 318: Ch 19, 26.4.3, 26.4.4; IBC-2021: 1904.1, 1904.2
x	-	6. Prior to concrete placement, fabricate specimens for strength tests, perform slump and air content tests, and determine the temperature of the concrete. Referenced Standards: ASTM C 31; ASTM C 172; ACI 318: 26.5, 26.12
x	-	7. Inspect concrete and shotcrete placement for proper application techniques Referenced Standards: ACI 318: 26.5
-	x	8. Verify maintenance of specified curing temperature and techniques Referenced Standards: ACI 318: 26.5.3 - 26.5.5
-	x	10. Inspect erection of precast concrete members Referenced Standard: ACI 318: Ch 26.9
-	x	14. Inspect formwork for shape, location and dimensions of the concrete members being formed Referenced Standard: ACI 318: 26.11.1.2(b)

MASONRY CONSTRUCTION (1705.4):

Masonry construction shall be inspected and verified in accordance with the quality assurance program requirements of TMS 402 and TMS 602, and requirements of Sections 1705.4.1 through 1705.4.2, depending on the classification of the building or structure or nature of the occupancy.

Exception: Special Inspections are not required for masonry construction that meets one of the three exceptions listed in Section 1705.4.

LEVEL 2 QUALITY ASSURANCE

The minimum Special Inspection Program for masonry in Risk Categories I, II, or III designed per Part 3 (Engineered Design), Appendix B (Design of Masonry Infills), or Appendix C (Limit Design Method) and for masonry in Risk Category IV designed per Part 4 (Prescriptive Design).

REQUIRED VERIFICATION REQUIREMENTS
Verify compliance with the approved submittals. Referenced Criteria: TMS 602: Art 1.5
Verification of f'_m and f'_{AAC} prior to construction except where specifically exempted by code Referenced Criteria: TMS 602: Art 1.5
Verification of slump flow and VSI when self-consolidating grout is delivered to the project site. Referenced Criteria: TMS 602: Art 1.5 and 1.6.3

CONTINUAL	PERIODIC	MINIMUM SPECIAL INSPECTION REQUIREMENTS
		1. As masonry construction begins, verify that the following are in compliance:
-	x	a. Proportions of site-prepared mortar Referenced Criteria: TMS 602: Art 2.1, 2.6A & 2.6C
-	x	b. Grade and size of prestressing tendons and anchorages Referenced Criteria: TMS 602: Art 2.4B, 2.4H
-	x	c. Grade, type and size of reinforcement, connectors, anchor bolts, and prestressing tendons and anchorages. Referenced Criteria: TMS 602: Art 3.4, 3.6A
-	x	f. Sample Panel Construction Referenced Criteria: TMS 602: Art 1.6D
		2. Prior to grouting, verify that the following are in compliance:
-	x	a. Grout space Referenced Criteria: TMS 602: Art 3.2D, 3.2F
-	x	b. Placement of prestressing tendons and anchorages Referenced Criteria: TMS 402: Sec 10.8 & 10.9; TMS 602: Art 2.4, 3.6
-	x	c. Placement of reinforcement, connectors and anchor bolts Referenced Criteria: TMS 402: Sec 6.1, 6.3.1, 6.3.6, 6.3.7; TMS 602: Art 3.2E, 3.4
		3. Verify compliance with the following during construction:
-	x	a. Materials and procedures with the approved submittals. Referenced Criteria: TMS 602: Art 1.5
-	x	b. Placement of masonry units and mortar joint construction. Referenced Criteria: TMS 602: Art 3.3B
-	x	c. Size and location of structural members Referenced Criteria: TMS 602 Art 3.3F
-	x	d. Type, size and location of anchors, including other details of anchorage of masonry to structural members, frames or other construction Referenced Criteria: TMS 402: Sec 1.2.1(e), 6.2.1, 6.3.1
-	x	f. Preparation, construction, and protection of masonry during cold weather (temperature below 40F) or hot weather (temperature above 90F) Referenced Criteria: TMS 602: Art 1.8C, 1.8D
x	-	h. Placement of grout and prestressing grout for bonded tendons is in compliance Referenced Criteria: TMS 602: Art 3.5, 3.6C
	X	4. Observe preparation of grout specimens, mortar specimens and/or prisms Referenced Criteria: TMS 602: Art 1.4B.2.a.3, 1.4.B.2.b.3, 1.4.B.2.c.3,1.4.B.3, 1.4.B.4

SOILS (1705.6 & TABLE 1705.6):

> Perform Special Inspections of existing site soil conditions, fill placement and load-bearing requirements as required by Section 1705.6 and Table 1705.6
> Determine compliance using the approved geotechnical report (Section 1803.1), and the construction documents prepared by the Registered Design Professional.
> Determine that the proper materials and procedures are used during fill placement and in accordance with the provisions of the approved geotechnical report.

Exception: Where Section 1803 does not require reporting of materials and procedures for fill placement, the special inspector shall verify that the in-place dry density of the compacted fill is not less than 90% of the maximum dry density at optimum moisture content determined in accordance with ASTM D 1557

CONTINUAL	PERIODIC	REQUIRED VERIFICATION AND INSPECTIONS
-	x	1. Verify materials below shallow footings are adequate to achieve the design bearing capacity.
-	x	2. Verify excavations are extended to proper depth & have reached proper material
-	x	3. Perform classification and testing of compacted fill material
x	-	4. During fill placement, verify use of proper materials and procedures in accordance with the approved geotechnical report. Verify densities and lift thicknesses during placement and compaction of compacted fill.
-	x	5. Prior to placement of compacted fill, inspect subgrade and verify that site has been prepared properly.

© 2026 Partners in Design Architects, Inc.

raSmith
CREATIVITY BEYOND ENGINEERING
project number 2220439
16745 W. Bluemound Road
Brookfield, WI 53005-5938
(262) 781-1000
rasmith.com


REVISIONS:
1 Code Updates 05.26.26

ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI

SPECIAL INSPECTIONS

2610 Lake Cook Road Suite 280 Riverwoods, IL 60015 Ph.: (847)940-0300
PartnersinDesign ARCHITECTS


PROJECT NO.: 522.22.031
DRAWN BY: EMS
CHECKED BY: SJR
DATE: 03.09.26
SHEET NO.: S0.3



1 S1.0 FOUNDATION PLAN - AREA A

SCALE: 1/16" = 1'-0"

FOUNDATION LEGEND



FOUNDATION PLAN NOTES

1. FINISH SLAB ELEVATION = 100'-0". LOCAL DATUM UNLESS NOTED OTHERWISE. TOP OF PERIMETER FOOTING ELEVATION = 96'-6" UNLESS NOTED OTHERWISE. TOP OF INTERIOR FOOTING ELEVATION = 98'-8" UNLESS NOTED OTHERWISE.
2. PROVIDE 7" THICK UNREINFORCED SLAB-ON-GROUND ON 6" THICK STONE BASE MEETING THE GRADATION REQUIREMENTS OF ASTM D2940 ON PORTLAND STABILIZED SUB-BASE. HARD STEEL TROWEL FINISH MEETING FF35/FL25 (OVERALL) AND FF24/FL17 (LOCAL).
3. TYPICAL WHERE SLAB-ON-GROUND ABUTS WALL OR COLUMN, PROVIDE 1/4" x (SOG THICKNESS) PRE-SCORED REMOVABLE TOP STRIP ISOLATION BOARD.
4. OVER-EXCAVATION PER DETAIL 2/S1.1 MAY BE REQUIRED TO REMOVE EXISTING UNDOCUMENTED FILL AND UNSUITABLE BEARING SOIL.
5. COORDINATE EXACT DIMENSION OF WALL STEP WITH PRECAST WALL PANEL LAYOUT. SEE 3/S8.0
6. TYPICAL DETAILS THAT APPLY TO PLAN INCLUDE:
   - 1/S8.0 SPREAD FOOTING OVER LATERAL
   - 2/S8.0 CORNER REINFORCEMENT DETAIL
   - 3/S8.1 STOOP DETAIL
7. IN AREAS SHOWN SOG, PROVIDE 10 MIL POLY VAPOR BARRIER DIERECTLY BELOW SLAB-ON-GROUND. SEE ARCHITECTURAL.

ISOLATED FOOTING SCHEDULE


MARK	ISOLATED FOOTING DIMENSIONS			FOOTING REINFORCEMENT	REMARKS
	LENGTH	WIDTH	THICKNESS		
F60	6'-0"	6'-0"	17"	(8) #5; B, EW	
F66	6'-6"	6'-6"	18"	(6) #6; B, EW	

CONTINUOUS FOOTING SCHEDULE

MARK	CONTINUOUS FOOTING DIMENSIONS		FOOTING REINFORCEMENT	REMARKS
	WIDTH	THICKNESS		
W16	1'-6"	42"	(2) #6; T&B, CONT	AT STOOPS, SEE 3/S8.1
W20	2'-0"	42"	(3) #6 T&B, #3 TIES AT 48"OC	
W20a	2'-0"	42"	(3) #6 T&B, #3 TIES AT 48"OC	NOTE 3

NOTES:

1. B = BOTTOM, T = TOP, LW = LONG WAY, SW = SHORT WAY, EW = EACH WAY.
2. ALL REINFORCEMENT BARS TO BE BOTTOM BARS UNLESS NOTED OTHERWISE.
3. ALTERNATIVELY FOR W20a, PROVIDE 12" THICK FOOTING WITH (2) #5 BOTTOM BARS. IN EITHER CASE DROP BOTTOM OF FOOTING TO MATCH BOTTOM OF EXTERIOR WALL TRENCH FOOTING, HOLDING TOP OF FOOTING = 99'-0".
4. CONTINUOUS TRENCH FOOTING BARS CAN BE COUNTED FOR SPREAD FOOTING BARS AS LONG AS THEY ARE CONTINUOUS THROUGHOUT SPREAD FOOTING.



KEY PLAN
NOT TO SCALE

TRUE NORTH

PLAN NORTH

raSmith
CREATIVITY BEYOND ENGINEERING
project number: 220438
167.45 W. Bluemound Road
Brookfield, WI 53005-5938
(262) 781-1000
rasmith.com

REVISIONS:

ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI

FOUNDATION PLAN

2610 Lake Cook Road
Suite 280
Riverwoods, IL 60015
Ph.: (847)940-0300
Partners in Design ARCHITECTS

PROJECT NO.: 522.22.031


DRAWN BY: EMS

CHECKED BY: SJR


DATE: 03.09.26

SHEET NO.: S1.0

© 2026 Partners in Design Architects, Inc.




1 S1.1 FOUNDATION PLAN - AREA B
SCALE: 1/16" = 1'-0"



NOTE: CONTRACTOR MAY ELIMINATE STRUCTURAL FILL BY:
1. LOWERING DESIGNED FOOTING ELEVATION SO THAT FOOTING RESTS DIRECTLY ON SUITABLE BEARING SUBGRADE.
2. PROVIDING LEAN CONCRETE (f'c = 1,000 PSI) UNDER THE FOOTING TO SUITABLE BEARING SUBGRADE AS SHOWN SHADED ABOVE (NOT APPLICABLE IN GRANULAR SOILS).
3. INCREASING FOOTING THICKNESS TO REACH SUITABLE BEARING SUBGRADE AS SHOWN HATCHED ABOVE.


THIS DETAIL APPLIES ONLY AT THOSE LOCATIONS WHERE GEOTECHNICAL ENGINEER DEEM SOILS AT DESIGN FOOTING ELEVATIONS INADEQUATE FOR FOOTING SUPPORT. WHERE THIS WORK IS REQUIRED, CONTRACTOR WILL BE COMPENSATED ON A PRE-ESTABLISHED UNIT COST AGREED UPON BY ALL PRIOR TO THE WORK BEING COMPLETED.

2 S1.1 OVER-EXCAVATION DETAIL
SCALE: 1/2" = 1'-0"



NOTE: COORDINATE EXACT LOCATION OF PLUMBING RISER BLOCKOUT WITH ARCHITECTURAL DRAWINGS SINCE NOT NECESSARILY IN VICINITY OF ROOF DRAINS

3 S1.1 PLUMBING RISER BLOCKOUT
SCALE: 1" = 1'-0"



KEY PLAN
NOT TO SCALE

raSmith
CREATIVITY BEYOND ENGINEERING
project number 2220439
167.45 W. Bluemound Road
Brookfield, WI 53005-5938
(262) 781-1000
rasmith.com

REVISIONS:


ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI

FOUNDATION PLAN

Partners in Design ARCHITECTS
2610 Lake Cook Road
Suite 280
Riverwoods, IL 60015
Ph.: (847)940-0300

PROJECT NO.: 522.22.031
DRAWN BY: EMS
CHECKED BY: SJR
DATE: 03.09.26
SHEET NO.: S1.1

© 2026 Partners in Design Architects, Inc.




1 S2.0 ROOF FRAMING PLAN - AREA A

SCALE: 1/16" = 1'-0"

© 2026 Partners in Design Architects, Inc.

STRUCTURAL STEEL LEGEND



ROOF FRAMING PLAN NOTES

1. DECK BEARING ELEVATION @ '0' POINTS = 134'-10 1/2". ALL ELEVATIONS SHOWN ON PLAN ARE PLUS OR MINUS, AS INDICATED, FROM THIS DATUM ELEVATION. INCLUDING POINTS SHOWN OUTSIDE OF ROOF PLANE.
2. ROOF DECKING SHALL BE 1 1/2" x22 GA WIDE RIB GALVANIZED (G30) PRIME PAINTED WHITE METAL ROOF DECK FASTENED TO SUPPORTING STRUCTURE USING 36/4 PATTERN TYPICALLY OF FASTENING METHOD SHOWN ON 1/S8.5 AND #10 TEK SIDELAP FASTENERS AT 16" OC. PROVIDE DECK WITH THE FOLLOWING PROPERTIES:
   THICK = 0.0295 in $+M_a/\Omega$ = 422 #-FT/FT $+V_a/\Omega$ = 2654 LBS/FT
   Fy = 50 KSI $-M_a/\Omega$ = 477 #-FT/FT
   IN AREAS SHOWN [ ], USE 36/5 PATTERN W/ SIDELAPS AT 16" OC.
3. ▷ INDICATES LOCATION OF BAR JOIST BOTTOM CHORD EXTENSION. DO NOT WELD EXTENSION TO SUPPORT FRAMING. REFER TO DETAIL 8/S8.5.
4. ▶ INDICATES LOCATION OF BAR JOIST BOTTOM CHORD EXTENSION. WELD EXTENSION TO SUPPORT FRAMING AFTER ALL ROOF DEAD LOAD HAS BEEN APPLIED. SEE DETAIL 8/S8.5 AT JOIST GIRDERS.
5. JOIST SUPPLIER TO PROVIDE CONTINUOUS TOP AND BOTTOM CHORD HORIZONTAL ANGLE AND DIAGONAL X-BRIDGING WHERE SHOWN, NOTED AND AS REQUIRED. GC TO COORDINATE PLACEMENT OF JOIST BRIDGING WITH CLEARANCES REQUIRED BY FIRE PROTECTION LINES AND SPRINKLER HEADS.
6. ALL JOISTS TO BE CAMBERED IN ACCORDANCE WITH SJI STD SPECIFICATION UNLESS SPECIFICALLY NOTED OTHERWISE.
7. ALL BAR JOISTS TO BE DESIGNED FOR A NET WORKING UPLIFT LOAD OF 10 PSF IN ADDITION TO GRAVITY VERTICAL LOADS REQUIRED BY THE BAR JOIST DESIGNATION. A SINGLE LINE OF BOTTOM CHORD BRIDGING MUST BE PROVIDED NEAR THE FIRST BOTTOM CHORD PANEL POINTS.
8. DECK BEARING ANGLE BY PRECAST SUPPLIER, SEE 1/S8.6.
9. BAR JOIST BEARING ANGLE BY PRECAST SUPPLIER, SEE 2/S8.6.
10. ALL STEEL (BAR JOIST, BEAMS, AND COLUMNS) TO BE PRIME PAINTED GRAY.
11. WIND LOAD REACTIONS PROVIDED ON PLANS ARE STRENGTH VALUES (1.0W) UNLESS NOTED OTHERWISE.
12. PROVIDE ANGLE FRAME(S) SUPPORT AT ALL ROOF OPENINGS IN ACCORDANCE WITH DETAIL 3/S8.5 AT SMALLER OPENINGS, SEE 2/S8.5.
13. BELOW ROOFTOP UNIT CURB PROVIDE ANGLE STRUTS PER 4/S8.5 AND CHANNELS SHOWN PER 6/S8.5.
14. PROVIDE L3 1/2x2 1/2x1/4 (LLH) LAID ON TOP OF AND WELDED TO EACH JOIST ALONG EAST AND WEST WALLS PER 12/S8.5.
15. OUTER BAR JOISTS OF DOUBLE JOIST ACT AS CHORD FOR ROOF DIAPHRAGM. SEE 11/S8.5 FOR CONTINUITY PLATE REQUIRED AT EACH JOIST. (DO NOT ADJUST BAR JOIST SEAT HEIGHT)
16. HORIZONTAL SPANNING SPANDREL PANELS SHOWN [ ]. PRECAST SUPPLIER TO PROVIDE HAUNCH CONNECTION AND LATERAL RESTRAINT CONNECTIONS BETWEEN PANELS AS REQUIRED. BOTTOM OF SPANDREL ELEVATION PER PLAN. COORDINATE WITH ARCHITECTURAL DRAWINGS. SPANDREL IS 12" THICK OVERALL WITH BOTTOM AT ELEVATION = 116'-0".
17. SEE 1/S0.2 FOR DRIFTING SNOW LOAD DEFINITION.


ROOF FRAMING KEY NOTES

1. PROVIDE 4'x4' ROOF HATCH OPENING, FRAME OPENING PER 3/S8.5.
2. TOP OF 10 1/2" PRECAST RETURN WALL PANELS BELOW AT ELEVATION 116'-4".

JG DESIGNATION NOTATION

32/44G8N16.8K (W = ± X, E = ± X)

- JOIST GIRDER DEPTH AT NORTH END
- JOIST GIRDER DEPTH AT SOUTH END
- AXIAL WIND & SEISMIC LOAD TO BE DESIGNED FOR (0.6W & 0.7E)



KEY PLAN
NOT TO SCALE

TRUE NORTH
PLAN NORTH


raSmith
CREATIVITY BEYOND ENGINEERING
project number: 222043
167.45 W. Bluemound Road
Brookfield, WI 53005-5938
(262) 781-1000
rasmith.com

REVISIONS:

ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI
ROOF FRAMING PLAN

Partners in Design ARCHITECTS
2610 Lake Cook Road Suite 280 Riverwoods, IL 60015 Ph.: (847)940-0300


PROJECT NO.: 522.22.031
DRAWN BY: EMS CHECKED BY: SJR
DATE: 03.09.26
SHEET NO.: S2.0



1 S2.1 ROOF FRAMING PLAN - AREA B

SCALE: 1/16" = 1'-0"


NOTE: BESIDES DESIGNING JOIST GIRDERS FOR LOAD BASED ON DESIGNATION, DESIGN JOIST GIRDERS FOR THESE SEPARATE LOAD CASES DUE TO PONDING WATER.



2 S2.1 JG SPECIAL LOAD CASE (PONDING WATER)


SCALE: 1/16" = 1'-0"

STEEL COLUMN SCHEDULE		
COLUMN MARK	C1	C2
CAP PLATE	7/S8.5	7/S8.5
COLUMN SIZE	HSS10x10x5/16	HSS12x12x3/8
BASE PLATE	3/4"x18"x1'-6"	3/4"x18"x1'-6"
ANCHOR BOLTS	(4) 3/4" DIA	(4) 3/4" DIA
DETAILS, NOTES	3/S2.1	3/S2.1



3 S2.1 STANDARD ANCHOR ROD DETAIL

SCALE: 1 1/2" = 1'-0"



KEY PLAN

NOT TO SCALE

TRUE NORTH

PLAN NORTH

© 2026 Partners in Design Architects, Inc.

raSmith
CREATIVITY BEYOND ENGINEERING
project number: 2220439
167A5 W. Bluemound Road
Brookfield, WI 53005-5938
(262) 781-1000
rasmith.com

REVISIONS:

ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI
ROOF FRAMING PLAN

Partners in Design ARCHITECTS
2610 Lake Cook Road
Suite 280
Riverwoods, IL 60015
Ph.: (847)940-0300


PROJECT NO.: 522.22.031

DRAWN BY: EMS

CHECKED BY: SJR


DATE: 03.09.26

SHEET NO.: S2.1




1 S8.0 PIPE PASSING UNDER/THROUGH WALL FOOTING

SCALE: 3/4" = 1'-0"



2 S8.0 TYPICAL CONCRETE WALL AND FOOTING CORNER REINFORCEMENT


SCALE: 3/4" = 1'-0"



NOTE:
COORDINATE FOOTING STEP LOCATIONS WITH PRECAST WALL PANEL LAYOUT


3 S8.0 FOOTING STEP DETAIL

SCALE: 1" = 1'-0"




4 S8.0 TYPICAL INTERIOR COLUMN FOOTING

SCALE: 1/2" = 1'-0"



5 S8.0 JOINT LAYOUT AT COLUMN

SCALE: 3/4" = 1'-0"



SLAB DEPTH (IN) ✳✳	PLATE SIZE (IN)	PLATE SPACING✳ CTR-CTR (IN)
5 TO 6	1/4 X 4 1/2 X 4 1/2	18
> 6 TO 8	3/8 X 4 1/2 X 4 1/2	18
> 8 TO 11	3/4 X 4 1/2 X 4 1/2	18

✳: PLACE FIRST AND LAST WITHIN 6" OF A JOINT INTERSECTION
✳✳: IF DIFFERENT SLAB DEPTHS, USE THINNER VALUE FOR PLATE/ DOWEL


SECTION 1: SLAB-ON-GROUND NOTES
- SLAB-ON-GROUND TO BE PLACED USING ALTERNATING STRIPS IF SLAB NOT PLACED USING LASER SCREED.
- SLAB-ON-GROUND CONSTRUCTION SHOULD CONFORM WITH THE RECOMMENDATIONS AND REQUIREMENTS SET FORTH IN THE LATEST RELEASE OF ACI 302 GUIDE FOR CONCRETE FLOOR AND SLAB CONSTRUCTION.
- REFER TO THE GENERAL NOTES, THE SPECIFICATIONS, AND THE DRAWINGS FOR SUB-FLOOR DRAINAGE SYSTEM, SUBGRADE PREPARATION, AND/OR MUD SLAB AND VAPOR RETARDER REQUIREMENTS.
- THE SUBGRADE SHALL BE FREE OF STANDING WATER AT THE TIME OF CONCRETE PLACEMENT.
- REFER TO PLANS FOR SLAB THICKNESS ("T") AND REINFORCEMENT (WWF OR REINFORCEMENT BARS). REFER TO SPECIFICATIONS FOR FIBER REINFORCEMENT TO BE INCORPORATED IN CONCRETE MIX, IF ANY. WHERE PRESENT, REINFORCING BARS SHALL BE CHAIRED BY SOIL SUPPORTED SLAB BOLSTERS.
- PROVIDE (2) #5 x6'-0" AT ALL RE-ENTRANT CORNERS AND OTHER SIMILAR SLAB DISCONTINUITIES.
- UNLESS SHOWN OTHERWISE ON THE DRAWINGS, PROVIDE CONTRACTION AND/OR CONSTRUCTION JOINTS AT EVERY COLUMN LINE AND IN BETWEEN THE COLUMNS SUCH THAT THE JOINT SPACING DOES NOT EXCEED 30x("T") UNO. THE RESULTING PANELS SHOULD BE APPROXIMATELY SQUARE.

SECTION 2: CONSTRUCTION JOINT NOTES
- BREAK THE BOND BETWEEN NEW AND PREVIOUSLY PLACED SLABS BY SPRAYING OR BY PAINTING THE EXPOSED SIDE OF THE JOINT WITH A CURING COMPOUND, ASPHALTIC EMULSION, OR FORM OIL.

SECTION 3: CONTRACTION JOINT NOTES
- FOR SAW-CUT CONTRACTION JOINTS, MAKE THE SAW-CUT AS SOON AS THE SLAB IS ABLE TO SUPPORT THE WEIGHT OF WORKERS AND SAWING EQUIPMENT WITHOUT DAMAGE TO THE FINISHED SURFACE OF THE SLAB, BUT WITHIN 24 HOURS.
- DEPTH OF SAW-CUT SHOULD BE 1 1/2" IF PRODUCED USING THE EARLY ENTRY DRY-CUT PROCESS AND "T"/3 (1 1/2" MIN) IF PRODUCED USING THE CONVENTIONAL WET-CUT PROCESS.
- REFER TO SPECIFICATIONS REGARDING EPOXY RESIN OR ELASTOMERIC SEALANT FOR REQUIREMENTS AT CONTRACTION JOINTS.

6 S8.0 TYPICAL CONSTRUCTION AND CONTROL JOINTS IN SLAB-ON-GROUND


SCALE: 1" = 1'-0"



NOTES:
1) PROVIDE RAILING AT PLATFORM AND STAIRS PER ARCHITECTURAL DRAWINGS AND BUILDING CODE REQUIREMENTS.
2) FRAMING, GRATING, TREADS AND FASTENERS TO BE GALVANIZED.
3) IF C12x20.7 SECTIONS USED, HOLD INSIDE DIMENSIONS.


7 S8.0 STAIR FRAMING PLAN

SCALE: 1/4" = 1'-0"



8 S8.0 LOADING DOCK LEVELER PIT

SCALE: 3/4" = 1'-0"



© 2026 Partners in Design Architects, Inc.

raSmith
CREATIVITY BEYOND ENGINEERING
project number 2220439
1676 N. Blue Mound Road
Brookfield, WI 53005-5938
(262) 781-1000
rasmith.com


REVISIONS:

ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI

FOUNDATION DETAILS


2610 Lake Cook Road
Suite 280
Riverwoods, IL 60015
Ph.: (847)940-0300
Partners in Design ARCHITECTS

PROJECT NO.: 522.22.031
DRAWN BY: EMS
CHECKED BY: SJR
DATE: 03.09.26
SHEET NO.: **S8.0**




1 S8.1 TYPICAL PERIMETER FOOTING

SCALE: 3/4" = 1'-0"



2 S8.1 OVERHEAD DOOR THRESHOLD

SCALE: 3/4" = 1'-0"



3 S8.1 TYPICAL STOOP DETAIL

SCALE: 1" = 1'-0"

© 2026 Partners in Design Architects, Inc.

raSmith
CREATIVITY BEYOND ENGINEERING
project number 2220439
167.45 W. Bluemound Road
Brookfield, WI 53005-5938
(262) 781-1000
rasmith.com

REVISIONS:

ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI

FOUNDATION DETAILS


Partners in Design ARCHITECTS
2610 Lake Cook Road
Suite 280
Riverwoods, IL 60015
Ph.: (847)940-0300

PROJECT NO.: 522.22.031

DRAWN BY: EMS
CHECKED BY: SJR

DATE: 03.09.26

SHEET NO.: S8.1




FAST DECK TO SUPPORTING MEMBERS USING FASTENING METHOD INDICATED ON DRAWINGS AND ACCORDING TO THE FOLLOWING REQUIREMENTS:

a. POWDER-ACTUATED FASTENERS: HILTI X-HSN 24 AND X-ENP 19L15, RAMSET 265D, OR APPROVED EQUAL (SUBMIT MANUFACTURER'S LITERATURE FOR APPROVAL ON EQUAL PRIOR TO USING POWDER-ACTUATED PRODUCT).

1 S8.5 METAL DECK FASTENING DETAIL

SCALE: 1'2" = 1'-0"




NOTE:

A. NO PLATE REINFORCEMENT REQUIRED AT DECK OPENINGS SMALLER THAN 6"Ø OR 4" SQUARE.

B. FOR DECK OPENINGS LARGER THAN 13"Ø OR 9" SQUARE, PROVIDE STEEL FRAME PER TYPICAL FRAMING AT ROOF OPENINGS DETAIL

2 S8.5 TYPICAL ROOF DECK OPENING


SCALE: 1" = 1'-0"



FOR FRAMES SET
BEFORE DECK INSTALLED

NOTE:
GC TO VERIFY SIZE, SHAPE AND LOCATION OF ALL ROOF OPENINGS WITH APPROPRIATE TRADES PROVIDING TYPICAL FRAME AT ALL OPENINGS:


1. LARGER THAN 13" DIAMETER OR 9" SQUARE
   OR
2. SUPPORTING IN EXCESS OF 60 LBS EQUIPMENT LOADS



FOR FRAMES SET
AFTER DECK INSTALLED

3 S8.5 TYPICAL FRAMING AT ROOF OPENINGS

SCALE: 1" = 1'-0"




NOTE:
REINFORCEMENT REQUIRED AT ALL HANGING LOADS BETWEEN BOTTOM CHORD PANEL POINTS THAT EXCEED CRITERIA ON STRUCTUAL NOTES SHEET.

NOTE:
AS LONG AS CONCENTRATED LOAD ALONG JOIST TOP CHORD IS AT OR WITHIN 2" OF JOIST PANEL POINT OR CONCENTRATED LOAD ≤ 100# @ BOTTOM CHORD OR 300# @ TOP CHORD, L2x2 IS NOT REQUIRED.

NOTE:
PRIOR TO INSTALLATION, VERIFY LOADS WITH ENGINEER IF ACTUAL DIFFER FROM THOSE POSTED ON DRAWINGS.

4 S8.5 CONCENTRATED LOAD AT JOIST

SCALE: 1" = 1'-0"





5 S8.5 JOIST GIRDER AT PRECAST PANEL

SCALE: 1" = 1'-0"

6 S8.5 EQUIPMENT RAIL SUPPORT


SCALE: 1" = 1'-0"






7 S8.5 JOIST GIRDERS ON COLUMN

SCALE: 1" = 1'-0"




8 S8.5 TYPICAL JOIST-ON-JOIST GIRDER DETAIL

SCALE: 1" = 1'-0"




9 S8.5 SECTION

SCALE: 1" = 1'-0"




10 S8.5 SECTION

SCALE: 1" = 1'-0"



11 S8.5 BAR JOIST CONTINUITY PLATE

SCALE: 1" = 1'-0"



12 S8.5 ROOF DIAPHRAGM SHEAR COLLECTOR

SCALE: 1 1/2" = 1'-0"

raSmith
CREATIVITY BEYOND ENGINEERING
project number: 222043
1.67.45 W. Bluemound Road
Brookfield, WI 53005-5938
(262) 781-1000
rasmith.com

© 2026 Partners in Design Architects, Inc.


REVISIONS:

ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI
FRAMING DETAILS

2610 Lake Cook Road
Suite 280
Riverwoods, IL 60015
Ph.: (847)940-0300

Partners in Design
ARCHITECTS

PROJECT NO.: 522.22.031
DRAWN BY: EMS
CHECKED BY: SJR
DATE: 03.09.26
SHEET NO.: S8.5




1 S8.6 JOIST BRIDGING AT PRECAST PANEL

SCALE: 1" = 1'-0"


LOADS	LOAD TABLE (PLF)			
DETAIL		1/S8.6		2/S8.6
TOP OF WALL ELEVATION		136'-9 1/2"	138'-9 1/2"	136'-9 1/2"
	VERTICAL (NOTE 1)			
	DEAD (DOWN)	78	78	685
	LIVE (DOWN)	75	201	700
	WIND (UP)	95	95	936
	HORIZONTAL PARALLEL TO WALL (NOTE 1)			
	WIND (+/-)	101	101	644
	SEISMIC (+/-)	132	132	430
	HORIZONTAL PERPENDICULAR TO WALL (NOTE 2)			
	WIND (+/-)	+546 / -511	+730 / -616	+546 / -511
	SEISMIC (+/-)	808	898	808

NOTES:
1. MULTIPLY BY BAR JOIST SPACING TO GET JOIST ROLL OVER FORCE AND POINT REACTION JOIST SUPPORT ANGLE IS TO BE DESIGNED FOR.
2. MULTIPLY BY BAR JOIST SPACING TO GET AXIAL LOAD TO BE TRANSFERRED THROUGH BAR JOIST SEAT ALONG DIRECTION OF JOIST SPAN.
3. WIND AND SEISMIC LOADS ARE STRENGTH LEVEL VALUES (1.0W, 1.0E)
4. LOADS PROVIDED ARE UNIFORM ALONG THE BACKSIDE OF PRECAST WALL PANEL AT ROOF PLANE. PRECASTER TO ADJUST FOR OPENINGS THAT OCCUR BELOW THE ROOF PLANE.



2 S8.6 JOIST AT PRECAST PANEL

SCALE: 1" = 1'-0"



NOTE:
CFMF SHALL BE SELF SUPPORTING AND ABLE TO TRANSFER WIND LOAD @ TOP OF GLAZING TO PRECAST PANEL

3 S8.6 SECTION

SCALE: 3/4" = 1'-0"

© 2026 Partners in Design Architects, Inc.

raSmith
CREATIVITY BEYOND ENGINEERING
project number: 220439
167 S. W. Bluemound Road
Brookfield, WI 53005-5938
(262) 781-1000
rasmith.com

Partners in Design ARCHITECTS
2610 Lake Cook Road
Suite 280
Riverwoods, IL 60015
Ph: (847)940-0300

REVISIONS:

ZILBER INDUSTRIAL 3
108th St, Lakeview Corporate Park, Pleasant Prairie, WI
FRAMING DETAILS

PROJECT NO.: 522.22.031
DRAWN BY: EMS
CHECKED BY: SJR
DATE: 03.09.26
SHEET NO.: S8.6