State of Wisconsin
DEPARTMENT OF NATURAL RESOURCES
1027 W. Saint Paul Avenue
Milwaukee WI 53233

Tony Evers, Governor
Karen Hyun, Ph.D., Secretary
Telephone 608-266-2621
Toll Free 1-888-936-7463
TTY Access via relay - 711

April 1, 2026

Kristi Sherfinski, PLA
LANDCO2
P.O. Box 12043
Milwaukee, WI 53212

Subject: 2026 Assured Wetland Delineator Confirmation

Dear Kristi Sherfinski:

This letter provides Wisconsin Department of Natural Resources (WDNR) confirmation for the wetland delineations you conduct during the 2026 growing season. You and your clients will not need to wait for the WDNR to review your wetland delineations before moving forward with project planning. This will help expedite the review process for WDNR's wetland regulatory program. Your name and contact information will continue to be listed on our website at: http://dnr.wi.gov/topic/wetlands/assurance.html.

In the instance where a municipality may require a letter of confirmation for your work prior to moving forward in the local regulatory process, this letter shall serve as that confirmation. Although your wetland delineations do not require WDNR field review, inclusion of a Wetland Delineation Report is required for projects needing State authorized wetland, waterway and/or storm water permit approvals.

To comply with Chapter 23.321, State Statutes, please supply the department with a polygon shapefile of the wetland boundaries delineated within the project area. Please do not include data such as parcel boundaries, project limits, wetland graphic representation symbols, etc. If internal upland polygons are found within a wetland polygon, then please label as UPLAND. The shapefile should utilize a State Plane Projection and be overlain onto recent aerial photography. If a different projection system is used, please indicate in which system the data are projected. In the correspondence sent with the shapefile, please supply a brief description of each wetland's plant community (eg: wet meadow, floodplain forest, etc.). Please send these data to Calvin Lawrence (608-266-0756 or email at calvin.lawrence@wisconsin.gov).

If you or any client has a question regarding your status in the Wetland Delineation Professional Assurance Program, contact me by email at kara.brooks@wisconsin.gov or phone at 414-308-6780. Thank you for all your hard work and best wishes for the upcoming field season.

Sincerely,

Kara Brooks
Wetland Identification Coordinator
Bureau of Watershed Management

PRINTED ON RECYCLED PAPER











Wetland Delineation

Project #26-149
04-16-2026

Client
Pinnacle Engineering Group
20275 Watertown Road, Ste. 100
Brookfield. WI 53186

Project Location
108th Street & Green Bay Road
Pleasant Prairie, WI 53158

LANDCO2

P.O. Box 12043, Milwaukee, WI 53212
www.LANDCO2.com

INTRODUCTION

The subject site is a 22.85-acre parcel located southwest of the intersection of 108th Street and Green Bay Road in Pleasant Prairie. The parcel is located in the Northwest 1/4 of Section 27 and Northeast 1/4 of Section 28, Township 1 North, Range 22 East, in the Village of Pleasant Prairie, Kenosha County, Wisconsin. A map identifying the project location can be found in **FIGURE 1**. The closest waterbody to the site is an unnamed tributary to The Des Plaines River, which is located in the southern portion of the project site.

The predominant land cover for this property are disturbed old field, active agricultural field, and wetland. The old field and agricultural field are bisected by a wetland area and intermittent creek running northeast to southwest through the property. The purpose of the wetland delineation was to identify the existing wetlands on the property and to create a map of their boundaries. A figure of the surveyed wetland boundary map is found at the end of the report.

Kristi Sherfinski, Emma Johnson, and Matt Provost of LANDCO2 conducted the wetland delineation field work on April 8th, 2026. Field conditions on April 8th, 2026 were sunny and windy with air temperatures in the 40s (°F). Growing season conditions as defined in the Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Midwest Region (2010) and Northcentral and Northeast Region (2012) were documented at the site prior to beginning the delineation. Soil temperatures must be at or above 41°F at depth of 12 inches and at least two plant species must be emerging or breaking bud. On April 8th, 2026, soil temperatures were 47°F at a depth of 12 inches. Green plant species with new growth included reed canary grass (*Phalaris arundinacea*), Kentucky blue grass (*Poa pratensis*), common teasel (*Dipsacus fullonum*), and a Bell's Honeysuckle (*Lonicera x bella*) was breaking bud.

Kristi Sherfinski is certified as an Assured Wetland Delineator with the Wisconsin Department of Natural Resources (WIDNR). She has over 20 years of experience delineating wetlands in the Great Lakes Region. She received her initial basic wetland training at the Wetland Training Institute in Hastings, Michigan in 2002. Kristi worked as a project manager and wetland delineator at JFNew & Associates in Grand Haven, Michigan for six years, conducting wetland delineations in Michigan, Indiana, Illinois, and Wisconsin. Kristi then moved to Wisconsin to work for the Southeastern Wisconsin Regional Planning Commission (SEWRPC). At SEWRPC, Kristi updated the Wisconsin Wetland Inventory (WWI) in 2005 and in 2010 for the seven-county area of southeast Wisconsin. Kristi participated in the Advanced Wetland Delineation training in 2006. In 2009, she attended the Wetland Delineation USACE Regional Supplement training session, the Environmental Corridor Delineation Workshop, and the Farm Service Agency (FSA) Slide Review training session. After working at SEWRPC for seven years, Kristi went back to school for a degree in Landscape Architecture before starting LANDCO2 (formerly Helianthus). Emma Johnson obtained her B.S. in Conservation Biology and Environmental Science at the University of Wisconsin-Madison and assisted with the wetland delineation. Matt Provost, who has a B.S. in Landscape Architecture and an M.S. in Planning, also assisted with the delineation.

METHODS

The process of wetland delineation involves collecting information about the soils, vegetation, and hydrology of a site in order to determine where the wetland boundary is located. The methodology used to conduct the delineation followed the US Army Corps of Engineers Wetlands Delineation Manual (1987), and the appropriate Regional Supplement to the Corps of Engineers Wetland Delineation Manual. In general, in southeastern and western Wisconsin, the Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Midwest Region (Version 2.0, August, 2010) is used. The remaining portions of the state follow the Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Northcentral and Northeast Region (Version 2.0, January, 2012). At this site, the Midwest Regional Supplement was used.

Prior to the site visit, several sources of data are consulted to reveal information that will aid in locating the wetlands on the site. The sources reviewed include weather records using the Antecedent Precipitation Tool (APT) Version 3.0 to determine antecedent hydrologic conditions, the Wisconsin Wetland Inventory (WWI) map, the soil survey maps, a topographic map, and historic aerial photographs of the project area. In areas that are under active cultivation as farmland, a Farm Service Agency (FSA) Slide Review is also conducted.

Data sample points are chosen based on the potential wetland areas identified by reviewing the above-referenced sources, and other sample points are added based on information gathered while in the field. Sample points are chosen on either side of the wetland line for their ability to reveal information about the actual location of the line, and upland reference data samples are chosen in order to show the contrast between wetland and upland field conditions.

Once a data sample point is chosen and located in the field, data is collected on the vegetation, the hydrology, and the soils of the site. Vegetation is identified by strata (tree, shrub/sapling, herbaceous, and vine layers), and an aerial coverage percent is determined for each species by strata. The plot size for the tree, shrub, and vine strata is a 30-foot radius circle, and the plot size for the herbaceous strata is a 5-foot radius circle. The scientific names and wetland status of each plant species follows the National Wetland Plant List (2022). Once all species have been assigned a cover percentage, the dominance by wetland indicator plant species is assessed.

Hydrological indicators, as described in the Regional Supplements, are then listed for the sample point. A soil pit is excavated to required depths and the depth of water, saturation, and the water table is recorded. The soil profile at the sample point is also described, using the Munsell Soil-Color Charts (2009) to assess the color of the soil, and a texture analysis to determine the predominant texture of each soil layer. This data is used to determine if the soil profile meets the hydric soil indicators as defined in the Regional Supplements and the Field Guide for Identifying Hydric Soils V. 9.0 (United States Department of Agriculture, 2024).

If a data sample point has all three indicators for a wetland—hydrology, soils, and vegetation—then the sample point is determined to be within a wetland. In certain circumstances where one or more of the three factors is missing due to problematic conditions or recent disturbances, a

sample may still be determined to be in wetland by following the procedures in Chapter 5 "Difficult Wetland Situations" in the regional supplements. Within the Midwest and Northcentral and Northeast Regional Supplements, Chapter 5 problematic situations are split up into five different types that are most commonly encountered. The situations include, but are not exclusive to: Land use for agriculture (and additionally silviculture in the NCNE), problematic hydrophytic vegetation, problematic hydric soils, wetlands that periodically lack indicators of wetland hydrology, and wetland/non-wetland mosaics. For non-normal circumstances due to agricultural or silviculture practices, the following factors are looked for and evaluated to further confirm the presence of a wetland: Nearby volunteer vegetation, soil survey maps and the hydric status and typical vegetation for those soils, pre-disturbance and post-disturbance aerial photos, the same soil types within undisturbed areas on the property, and existing indicators of wetland hydrology. Additional methods for identifying wetlands under problematic conditions include revisitation to the site in the wet season (if originally done in the dry season), further evaluation of antecedent hydrologic analysis and drought years, and other investigations as needed.

Once the location of the wetland line is determined from the data sampling effort, the edge of the wetland is flagged in the field and then surveyed in order to produce a map of the wetland that occurs on the subject property. Representative photographs of the sample points and of each wetland area were taken during the field visit. Any ditch, stream, pond or other water body that may be considered a Water of the U.S. and thus regulated by the U.S. Army Corps of Engineers (USACE) or the Wisconsin Department of Natural Resources (WDNR) is also identified.

RESULTS AND DISCUSSION

Antecedent Hydrologic Condition Analysis

Weather records were consulted from the Kenosha WWTP weather stations, using the Antecedent Precipitation Tool (APT), to determine if precipitation levels were normal for the three months prior to the site visit (**FIGURE 2**). The antecedent hydrologic condition analysis for the site revealed that climatic conditions near the site were normal at the time of the site visit (**TABLE 1**). However, the 30-day rolling total rainfall showed that precipitation levels were much higher than normal, due to excessively rainy conditions in late March and early April. Drier than normal conditions means that hydrologic indicators may be absent from the wetland sample points and the data must be interpreted accordingly. Wetter than normal conditions must be accounted for when interpreting the data because saturation or the water table may be higher than it is during normal conditions, giving false positives for hydrological indicators.

Table 1 – Antecedent Hydrologic Condition Analysis

30 Days Ending	30th Percentile (inches)	70th Percentile (inches)	Observed Rain Fall (inches)	Condition (Dry, Wet, or Normal)	Condition Value	Month Weight Value	Product of Previous Two Columns

04-08-2026	1.63	3.41	6.67	Wet	3	3	9
03-09-2026	1.58	2.62	1.45	Dry	1	2	2
02-07-2026	1.20	2.28	0.70	Dry	1	1	1
						Sum	12
If sum is:							
6-9	Then prior period has been drier than normal						
10-14	Then prior period has been normal						
15-18	Then prior period has been wetter than normal						
Conclusions:	A sum of 12 shows the prior period to the site visit to be normal.						

Note: Average rainfall data based on the years 1996-2026.

Review of Existing Data Sources

Existing data sources were reviewed to aid in the identification of wetland areas in the field.

The topographic map (**FIGURE 3**) shows a swale with an intermittent creek crossing the property from the northeast to the southwest. A second swale runs from north to south near the west side of the property and merges with the other swale at the southwest corner of the property. A depression is located within a bermed area just east of the second swale. Elevations are at 724 feet above Mean Sea Level at its highest in the southeast corner and 702 feet at its lowest in a depression in the southwest corner.

The soil survey maps show an area of Ashkum silty clay loam (AtA) which coincides with the bottom of the swales and other depressions and low areas. The remainder of the soils are Beecher silt loam (BcA), Blount silt loam (BlA), and Ozaukee silt loam (OzaB, OzaB2, OzaC2) (**FIGURE 4 & FIGURE 5**). The BcA, BlA, OzaB soil types may include a small amount of hydric soil types in depressions. All of the soil types occurring on the property are listed in **TABLE 2**.

Table 2 – Soil Types

Map Symbol	Map Unit Name	Hydric Soil Type
7232A/AtA	Ashkum silty clay loam, 0-2%	Predominantly Hydric
7298B/BcA	Beecher silt loam, 1-3%	Predominantly Non-hydric
7423B/BlA	Blount silt loam, 1-3%	Predominantly Non-hydric
7530B/OzaB	Ozaukee silt loam, 2-6%	Predominantly Non-hydric
7530B2/OzaB2	Ozaukee silt loam, 2-6%, eroded	Predominantly Non-hydric
7530C2/OzaC2	Ozaukee silt loam, 6-12%, eroded	Non-hydric

The Wisconsin Wetland Inventory identifies one wetland within the project area (**FIGURE 6**) that spans two different wetland classes. The majority of the mapped wetland is an E2K, fresh wet meadow, along the swales and low/depressional areas. This fresh wet meadow grades into a T3K, forested wetland, in the southwest corner of the property. The Wisconsin Wetland Inventory also identifies portions of the following soils as purple, potentially hydric soils: AtA, BcA, BlA, MzdB2. An intermittent creek flows through the E2K feature and exits the property in the southwest corner.

Historic aerial photographs revealed that the subject property has been continuously farmed since before 1937 (**FIGURE 7**). Wet signatures were visible within the agricultural fields in these early aerial images. Green Bay Road was built between 1990 and 2000, which created the eastern edge of the parcel and bisected the wetland. Between 2000 and 2005, the building to the west and the roads to the west and north were built, which decreased the size of the northern agricultural field and created the western and northern boundaries of the parcel. A berm was also created on site as a result of these earth moving activities at this time. The configuration of the wetlands remained relatively unchanged from 2005 until present day.

Because agricultural fields are part of the project area, a Farm Service Agency (FSA) Slide Review was conducted to identify the potential for the presence of farmed wetlands (**FIGURE 8**). Three areas were investigated that showed possible wet signatures. FSA Area A was a low area in the southwest corner of the cropped field and showed wetness signatures of soil moisture or crop stress in 9 out of 11 years investigated. FSA Area B was a low area in the northeast corner of the cropped field and showed wetness signatures of soil moisture or crop stress in 8 out of 11 years investigated. FSA Area C was a slight depression perched on top of a hill and only showed wetness signatures in 2 of the 11 years. All three areas were determined not to be wetland and were likely tiled, as a beehive drain feature was observed near the field and wetland conditions were not observed.

A previous wetland delineation was conducted by Dave Meyer in 2016. The wetland boundary map was consistent with current findings (**FIGURE 12**).

Wetlands Identified During the Site Visit

A total of three wetlands were identified on the property during the field visit. Site photos of the different wetlands are included in **FIGURE 9.** Field data sheets are included in **FIGURE 10**. The acreages and types of wetlands that were identified and flagged in the project are shown in **FIGURE 11** and **TABLE 3**. A description of the wetland areas follows.

Wetland A

This wetland is a wetland complex of forested, scrub-shrub, and fresh wet meadow wetland with an intermittent creek running through it. Starting near the eastern property boundary, the roadside swale connects to a fresh wet meadow wetland (#4) dominated by reed canary grass and Eastern cottonwood. Soils met hydric indicators for A11. Depleted Below Dark Surface and F3. Depleted Matrix. Hydrology indicators included Surface Water, Drainage Pattern, Geomorphic

Position, and FAC-Neutral Test. The adjacent upland point to the north (#3) was approximately two feet in elevation higher than wetland point #4 and was taken in an old field dominated by Kentucky bluegrass, Eastern cottonwood, common buckthorn, and multiflora rose, which met the criteria for hydrophytic vegetation. However, hydric soil indicators and wetland hydrology were lacking.

The fresh wet meadow grades into the ditched area immediately to its southwest, which consists of open water surrounded by fresh wet meadow (#8). The fresh wet meadow around the ditch was dominated by reed canary grass. Soils met hydric indicators for A11. Depleted Below Dark Surface and F3. Depleted Matrix. Hydrology indicators included High Water Table, Saturation, Drainage Patterns, Geomorphic Position, and FAC-Neutral Test. The adjacent upland point to the north (#9) was approximately twelve inches above the wetland in an old field dominated by Kentucky bluegrass, apple, Eastern red cedar, and bur oak, which had a Prevalence Index of 3.18, indicating an upland plant community. Hydric soil indicators and wetland hydrology were lacking.

The ditched area continues to drain to the southwest where it entered a forested wetland portion (#10) near the intermittent creek. The forested wetland was dominated by Eastern cottonwood, common buckthorn, green ash, and reed canary grass. Soils met hydric indicators for A11. Depleted Below Dark Surface. Hydrology indicators included High Water Table, Saturation, Water-Stained Leaves, Drainage Patterns, Geomorphic Position, and FAC-Neutral Test. The adjacent upland data point (#11) was approximately 18 inches above the wetland in an old field dominated by bur oak, Eastern red cedar, common buckthorn, autumn olive, and Kentucky bluegrass. Hydric soil indicators and wetland hydrology were lacking.

In the southwest part of the property, there was a forested and fresh wet meadow wetland (#18). This area was dominated by Eastern cottonwood, reed canary grass, and Bell's honeysuckle. Soils met hydric indicators for F6. Redox Dark Surface. Hydrology indicators included Saturation, Water Marks, Water-Stained Leaves, Drainage Patterns, and Geomorphic Position. The adjacent upland point (#19) was approximately 8 feet above the wetland, in an upland forest dominated by bur oak, black walnut, Bell's honeysuckle, common buckthorn, and garlic mustard. The soils consisted of 15 inches of silty clay and silty clay loam over rocky fill. Hydric soil indicators and wetland hydrology were lacking.

In the western swale, the area turns into a scrub-shrub/fresh wet meadow wetland (#12) that was dominated by black willow, sandbar willow, red-osier dogwood, and reed canary grass. Soils met hydric indicators for F6. Redox Dark Surface and F7. Depleted Dark Surface. Hydrology indicators included High Water Table, Saturation, Drainage Patterns, Geomorphic Position, and FAC-Neutral Test. The adjacent upland point (#13) is approximately eighteen inches above the wetland in an old field dominated by bur oak and Kentucky bluegrass, which met the criteria for hydrophytic vegetation. However, hydric soil indicators and wetland hydrology were lacking.

Further north, the wetland (#17) was dominated by Bebb's willow, Bell's honeysuckle, and reed canary grass. Soils met hydric indicators for F6. Redox Dark Surface. Hydrology indicators included Drainage Patterns, Geomorphic Position, and FAC-Neutral Test. The adjacent upland point (#16)

was approximately six feet above the wetland on top of a berm that separates Wetland A from Wetland B. The dominant vegetation was Kentucky bluegrass, which met the criteria for hydrophytic vegetation. However, hydric soil indicators and wetland hydrology were lacking.

Just west of Data point 17, the (#21) dominant vegetation was sandbar willow and reed canary grass. Soils met hydric indicators for A11. Depleted Below Dark Surface and F3. Depleted Matrix. Hydrology indicators included Saturation, Water Marks, Water-Stained Leaves, Drainage Patterns, FAC-Neutral Test, and Geomorphic Position. The adjacent upland point (#20) was approximately two feet above the wetland in a mowed lawn dominated by Kentucky bluegrass, bur oak, and black cherry, which met the criteria for hydrophytic vegetation. Hydric soil indicators and wetland hydrology were lacking.

Wetland B

This wetland is a wet meadow and scrub-shrub (#15) wetland, separated from Wetland A by an artificial berm. The dominant vegetation is Eastern cottonwood, sandbar willow, black willow, Kentucky bluegrass, and reed canary grass. Soils met hydric indicators for A12. Thick Dark Surface and F6. Redox Dark Surface. Hydrology indicators included Surface Water, Drainage Patterns, Geomorphic Position, and FAC-Neutral Test. The adjacent upland point (#14) is approximately two feet above the wetland in old field dominated by Eastern cottonwood and Kentucky bluegrass, which met the criteria for hydrophytic vegetation. Soils met the criteria for F6. Redox Dark Surface. However, hydrology indicators were not present and this area was non-wetland.

Wetland C

On the east side of the site, just east of the parcel boundary, there is a roadside ditch running along Green Bay Road. This ditch was dominated by Kentucky bluegrass at Data point 1, but became wetter as the slope decreased toward Wetland A. Soils met hydric criteria for A11. Depleted Below Dark Surface F3. Depleted Matrix, and F6. Redox Dark Surface. Hydrology indicators included Drainage Patterns and Geomorphic Position. The adjacent upland point (#2) was approximately two feet in elevation higher than the wetland point and occurred in an old field dominated by Kentucky bluegrass, bur oak, autumn olive, and common buckthorn. Hydric soil indicators and wetland hydrology were lacking.

Upland Data Points

Additional upland data points were sampled to verify lack of wetland elsewhere within FSA review areas.

Data point 7 was approximately six inches above Wetland A, in FSA Area A, which showed wetness signatures in 82% of years reviewed. The area had 100% corn stubble coverage from the previous growing season and no volunteer vegetation. However, the edge of the woodland, roughly 70 feet away and at the same topographic elevation, provided a vegetation reference point and was dominated by bur oak, Bell's honeysuckle, and black raspberry, which was a non-hydrophytic vegetative community. Hydric soil indicators included A11. Depleted Below Dark Surface and F3. Depleted Matrix. Hydrology indicators included two secondary indicators—Geomorphic Position and Saturation Visible on Aerial Imagery. However, a beehive structure was found on the property

which indicated that the field likely has drain tiles present and is effectively drained. Even though hydric soils and secondary indicators for hydrology were present, the upland reference vegetation and the evidence of a healthy corn crop from the previous season indicated that this area was non-wetland.

Data point 5 was approximately six inches above Wetland A, in FSA Area B, which showed wetness signatures in 73% of years reviewed. There was 100% corn stubble coverage from the previous growing season and a small amount of common dandelion nearby. Soils met the criteria for F6. Redox Dark Surface. Hydrology indicators included Geomorphic Position and Saturation Visible on Aerial Imagery. Even though hydric soils and secondary indicators for hydrology were present, the evidence of a healthy corn crop from the previous season and a bee hive inlet structure located nearby indicated that this area was non-wetland.

Data point 6 was taken in a slight depression on a hilltop in FSA Area C, which showed wetness signatures in only 18% of years. The field was had 100% corn stubble from the previous year's growing season, with no volunteer vegetation. Hydric soil indicators and wetland hydrology were lacking so this area was determined to be non-wetland.

Table 3 – Wetland Summary

Wetland ID	Wetland Classification	Size (Acres)
Wetland A	Forested/scrub-shrub/fresh wet meadow	4.91
Wetland B	Scrub-shrub/wet meadow	0.56
Wetland C	Wet meadow ditch	0.23

CONCLUSION

LANDCO2 identified wetlands on the project site on April 8, 2026, using the standard practices described in this report and their best professional judgment. The wetland lines staked in the field and referred to in this report are the best estimate of the wetland boundaries based on the conditions present at the time of the delineation. The wetlands identified for this report may be subject to federal regulation under the jurisdiction of the U.S. Army Corps of Engineers, state regulation under the jurisdiction of Wisconsin DNR, and local jurisdiction under your local, county, town, city, or village. Because this delineation was conducted by Ms. Sherfinski, an Assured Wetland Delineator, obtaining a concurrence letter from the Wisconsin Department of Natural Resources is not necessary. It should be noted that all reports conducted by an Assured Delineator are required to be submitted to WDNR for their records, and may be subject to their review as part of an annual review process. Concurrence with these wetland lines by the U.S. Army Corps of Engineers, however, is not required. If a permit is applied for, the USACOE will review the wetland delineation report during the permit application process.

In addition, because a wetland delineation is considered to be a point in time determination, wetland delineations are considered to be valid for a period of only five years for federal wetlands and 15 years for nonfederal wetlands. Permit applications may be submitted at the federal and state levels after a delineation is completed, with the request to review the delineation report and make a determination as to which, if any, wetlands on the site are nonfederal wetlands. Weather patterns and site conditions can change over time, making a new delineation necessary.

Other environmental considerations include threatened or endangered species, environmental corridors, or local tree ordinances. It is recommended that an Endangered Resources (ER) Review request be submitted to the WDNR prior to pursuing any permits for proposed work.

Any impact, alteration, or fill to either the wetland areas or to waterways that are considered Waters of the U.S. are subject to state and federal regulations and permits may be required. The WDNR administers Chapters 30 and 281 of the Wisconsin State Statues, and the USACE administers Section 404 of the Clean Water Act. The wetlands may also require a WDNR construction site storm water permit and be subject to NR 151 Wetland Protective Area requirements if over one acre of land disturbance is proposed **(FIGURE 13)**. Additional county, city or village ordinances may also apply to wetlands or waterways. If any disturbance occurs on the property without obtaining wetland delineation concurrence or authorization from the USACE and WDNR, it should be considered at the owner's own risk and LANDCO2 shall not be considered responsible or liable for any resulting damages.

REFERENCES

Antecedent Precipitation Tool (APT) Version 3.0: Technical and User Guide. 2025. U.S. Army Engineer Research and Development Center. Online: https://doi.org/10.21079/11681/49835.

Environmental Laboratory. 1987. Corps of Engineers Wetland Delineation Manual. Technical Report Y-87-1. Vicksburg, MS: U.S. Army Engineer Waterways Experiment Station.

Environmental Laboratory. 2010. Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Midwest Region, Version 2.0. ERDC/EL TR-10-16. Vicksburg, MS: U.S. Army Corps of Engineer Research and Development Center.

Environmental Laboratory. 2012. Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Northcentral and Northeast Region, Version 2.0. ERDC/EL TR 12-1. Vicksburg, MS: U.S. Army Corps of Engineer Research and Development Center.

Guidance for Offsite Hydrology/Wetland Determinations. July 1, 2016. St. Paul District US Army Corps of Engineers.

Guidance for Submittal of Delineation Reports to the St. Paul District Army Corps of Engineers and the Wisconsin Department of Natural Resources. March 4, 2015. St. Paul District US Army Corps of Engineers.

Munsell Color X-rite. 2009. Munsell Soil-Color Charts. Grand Rapids, MI.

NOAA Regional Climate Centers. Applied Climate Information System (ACIS). Online: www.rcc-acis.org.


Southeastern Wisconsin Regional Planning Commission (SEWRPC) Regional Map Server. Online: maps.sewrpc.org/regionallandinfo/regionalmapping/RegionalMaps/viewer.htm.

United States Department of Agriculture, Natural Resources Conservation Service. 2024. Field Indicators of Hydric Soils in the United States, Version 9.0.

U.S. Army Corps of Engineers. (2023). 2022 National Wetland Plant List, version 3.6. U.S. Army Engineer Research and Development Center, Vicksburg, MS. http://wetland-plants.usace.army.mil/

USDA Natural Resources Conservation Service. Web Soil Survey. Online: www.websoilsurvey.sc.egov.usda.gov.

Wisconsin DNR Surface Water Data Viewer (SWDV). Online: www.dnr.wi.gov/topic/surfacewater/swdv/.




1 MI

FIGURE 1. LOCATION MAP

Source: Google Maps, 2026

FIGURE 2. ANTECEDENT HYDROLOGIC ANALYSIS

Source: Antecedent Precipitation Tool V3.0, 2026



Coordinates	42.517, -87.89151
Observation Date	2026-04-08
Elevation (ft)	715.462
Drought Index (PDSI)	Mild wetness (2026-03)
WebWIMP H_2O Balance	Wet Season

30 Days Ending	30th %ile (in)	70th %ile (in)	Observed (in)	Wetness Condition	Condition Value	Month Weight	Product
2026-04-08	1.629921	3.414961	6.673229	Wet	3	3	9
2026-03-09	1.583465	2.616929	1.448819	Dry	1	2	2
2026-02-07	1.204331	2.281102	0.700787	Dry	1	1	1
Result							Normal Conditions - 12

Figures and tables made by the Antecedent Precipitation Tool Version 3.0

US Army Corps of Engineers.

ERDC

Developed by:
U.S. Army Corps of Engineers and
U.S. Army Engineer Research and Development Center

Weather Station Name	Coordinates	Elevation (ft)	Distance (mi)	Elevation Δ	Weighted Δ	Days Normal	Days Antecedent
KENOSHA WWTP	42.5608, -87.8156	595.144	4.908	120.318	2.799	11246	88
KENOSHA 1.7 SSE	42.5636, -87.8372	625.984	1.116	30.84	0.537	0	1
KENOSHA 3.1 SSE	42.5405, -87.8421	633.858	1.946	38.714	0.951	0	1
KENOSHA 1.7 S	42.5597, -87.8566	651.903	2.088	56.759	1.058	1	0
PLEASANT PRAIRIE 3.4 ESE	42.5087, -87.8188	618.11	3.603	22.966	1.704	4	0
KENOSHA RGNL AP	42.5953, -87.9383	732.94	6.682	137.796	3.928	77	0
RACINE WWTP	42.7028, -87.7858	591.864	9.928	3.28	4.5	24	0
WAUKEGAN #2	42.3606, -87.8186	649.934	13.833	54.79	6.983	1	0



FIGURE 3. TOPOGRAPHIC MAP

Source: NRCS Web Soil Survey, 2026



Map Unit Symbol	Map Unit Name
7232A	Ashkum silty clay loam, 0-2%
7298B	Beecher silt loam, 1-3%
7423B	Blount silt loam, 1-3%
7530B	Ozaukee silt loam, 2-6%
7530B2	Ozaukee silt loam, 2-6%, eroded
7530C2	Ozaukee silt loam, 6-12%, eroded

200 FT

FIGURE 4. SOIL SURVEY MAP

Source: NRCS Web Soil Survey, 2026




Map Unit Symbol	Map Unit Name
AtA	Ashkum silty clay loam, 0-2%
BcA	Beecher silt loam, 1-3%
BlA	Blount silt loam, 1-3%
OzaB	Ozaukee silt loam, 2-6%
OzaB2	Ozaukee silt loam, 2-6%, eroded
OzaC2	Ozaukee silt loam, 6-12%, eroded

200 FT

FIGURE 5. NRCS WISCONSIN SOILS MAP

Source: WIDNR Surface Water Data Viewer, 2026



Legend

- Wetland Indicators
- Wetland Class Areas

200 FT

FIGURE 6. WWI MAP

Source: WIDNR Surface Water Data Viewer, 2026



1937.



1963.

FIGURE 7. HISTORIC AERIAL PHOTOS

Source: Kenosha County GIS, 2026



1970.



1980.

FIGURE 7. HISTORIC AERIAL PHOTOS

Source: Kenosha County GIS, 2026



1990.



2000.

FIGURE 7. HISTORIC AERIAL PHOTOS

Source: Kenosha County GIS, 2026



2005.



2010.

FIGURE 7. HISTORIC AERIAL PHOTOS

Source: Kenosha County GIS, 2026



2015.



2020.

FIGURE 6. HISTORIC AERIAL PHOTOS

Source: Kenosha County GIS, 2026



2022.



2024.

FIGURE 7. HISTORIC AERIAL PHOTOS

Source: Kenosha County GIS, 2026



200 FT

FIGURE 8. FSA SLIDE REVIEW

Source: SWDV Leaf-Off, 2020

LANDCO2

WETLAND HYDROLOGY FROM AERIAL IMAGERY – RECORDING FORM

Project Name: Pinnacle Nitto Zilber	Date: 03-25-2026	County: Kenosha
Investigator: E. Johnson, K. Sherfinski		Legal Description (S, T, R): S27 & S28, T1N, R22E

Summary Table

Date Image Taken	Image Source	Climate Condition (wet, dry, normal)	Image Interpretation(s)				
			Area: A	Area: B	Area: C	Area:	Area:
2024	Google Earth	Wet	SS	SS	NSS		
2022	WIDNR SWDV	Normal	SS	SS	NSS		
2021	Google Earth	Normal	SS	SS	NSS		
2020	Google Earth	Wet	SS	SS	NSS		
2019	Google Earth	Normal	CS	NV	CS		
2018	Google Earth	Wet	SS	SS	SS		
2017	Google Earth	Normal	SS	SS	NSS		
2016	Google Earth	Normal	SS	SS	NSS		
2008	Google Earth	Normal	NV	NV	NV		
2007	Google Earth	Normal	NV	NV	NV		
2005	WIDNR SWDV	Dry	CS	CS	NV		
			Area: A	Area: B	Area: C	Area:	Area:
Number			11	11	11		
Number with wet signatures			9	8	2		
Percent with wet signatures			**82**	**73**	**18**		

KEY: WS – wetland signature; SS – soil wetness signature; CS – crop stress; NC – not cropped; NV – normal vegetative cover; AP – altered pattern; SW– standing water; NSS – no soil wetness signature; DO – drowned out

Table 1.

Area	Hydric Soils Present	Identified on NWI or other wetland map	Percent with wet signatures from Exhibit 1	Other hydrology indicators present	Wetland?
A	Yes	No	82	No	**No**
B	Yes	No	73	No	**No**
C	Yes	No	18	No	**No**

06-2024.



2022.



05-2021.



06-2020.



10-2019.



07-2018.



FIGURE 8. FSA SLIDE REVIEW

Source: WIDNR Surface Water Data Viewer & Google Earth, 2026

04-2017.



06-2016.



06-2008.



10-2007.



2005.



FIGURE 8. FSA SLIDE REVIEW

Source: WIDNR Surface Water Data Viewer & Google Earth, 2026



View of agricultural field upland within FSA Area A.



View of agricultural field upland within FSA Area B. Corn stubble from last year present and drainage tile is likely as a beehive structure was found nearby.

FIGURE 9. SITE PHOTOS



View of agricultural field upland within FSA Area C.



View of Wetland A in the northwest corner of the property.

FIGURE 9. SITE PHOTOS



View of Wetland A in forested portion in southwest corner of property.



View of the creek running through the forested part of Wetland A, near Data point 10.

FIGURE 9. SITE PHOTOS



View of narrow fresh wet meadow portion of Wetland A bisecting fields.



View of Wetland B, a wetland formed by berms that entrapped water.

FIGURE 9. SITE PHOTOS



View of the roadside ditch, Wetland C, that extends outside of the property boundary.

FIGURE 9. SITE PHOTOS

FIGURE 10. FIELD DATA SHEETS

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site: Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 1

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Swale | Local relief (concave, convex, none): Concave

Slope (%): 1-3 | Lat: | Long: | Datum:

Soil Map Unit Name: Ozaukee Silt Loam (7530B2/OzaB2) | NWI Classification: None

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic?

SUMMARY OF FINDINGS

(If needed, explain any answers in remarks.)

Hydrophytic vegetation present? Y	**Is the sampled area within a wetland?** Y
Hydric soil present? Y	If yes, optional wetland site ID:
Indicators of wetland hydrology present? Y	

Remarks: (Explain alternative procedures here or in a separate report.)

Roadside ditch

VEGETATION -- Use scientific names of plants.

Tree Stratum (Plot size: 30ft radius)	Absolute % Cover	Dominant Species	Indicator Status
1			
2			
3			
4			
5			
	0	= Total Cover	

Sapling/Shrub stratum (Plot size: 30ft radius)			
1			
2			
3			
4			
5			
	0	= Total Cover	

Herb stratum (Plot size: 5ft radius)			
1 *Poa pratensis*	100	Y	FAC
2 *Dipsacus fullonum*	5	N	FACU
3			
4			
5			
6			
7			
8			
9			
10			
	105	= Total Cover	

Woody vine stratum (Plot size: 30ft radius)			
1			
2			
	0	= Total Cover	

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 1 (A)

Total Number of Dominant Species Across all Strata: 1 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 100.00% (A/B)

Prevalence Index Worksheet

Total % Cover of:

OBL species	0	x 1 =	0
FACW species	0	x 2 =	0
FAC species	100	x 3 =	300
FACU species	5	x 4 =	20
UPL species	0	x 5 =	0
Column totals	105 (A)		320 (B)

Prevalence Index = B/A = 3.05

Hydrophytic Vegetation Indicators:

- ___ Rapid test for hydrophytic vegetation
- X Dominance test is >50%
- ___ Prevalence index is ≤3.0*
- ___ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ___ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? Y

Remarks: (Include photo numbers here or on a separate sheet)

Mowed lawn, wet meadow ditch

SOIL

Sampling Point: 1

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-9	10YR 3/2	95	10YR 4/4	5	C	M	Silty Clay Loam	
9-20	10YR 5/2	90	10YR 4/3	10	C	M	Silty Clay	

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- X Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- X Depleted Matrix (F3)
- X Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: Gravel Fill

Depth (inches): 20

Hydric soil present? Y

Remarks:

Refusal at 20" due to gravel fill

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- X Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- X Geomorphic Position (D2)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes	___	No	X	Depth (inches): ___
Water table present?	Yes	___	No	X	Depth (inches): ___
Saturation present? (includes capillary fringe)	Yes	___	No	X	Depth (inches): ___

Indicators of wetland hydrology present? Y

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 2

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Hillslope | Local relief (concave, convex, none): Convex

Slope (%): 3-4 | Lat: | Long: | Datum:

Soil Map Unit Name: Ozaukee Silt Loam (7530B2/OzaB2) | NWI Classification: None

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic?

SUMMARY OF FINDINGS

(If needed, explain any answers in remarks.)

Hydrophytic vegetation present?	Y		
Hydric soil present?	N	**Is the sampled area within a wetland?**	N
Indicators of wetland hydrology present?	N	If yes, optional wetland site ID:	

Remarks: (Explain alternative procedures here or in a separate report.)

VEGETATION -- Use scientific names of plants.

Tree Stratum (Plot size: 30ft radius)	Absolute % Cover	Dominant Species	Indicator Status
1 *Quercus macrocarpa*	10	Y	FAC
2 *Tilia americana*	3	Y	FACU
3			
4			
5			
	13	= Total Cover	

Sapling/Shrub stratum (Plot size: 30ft radius)			
1 *Elaeagnus umbellata*	5	Y	FACU
2 *Rhamnus cathartica*	2	Y	FAC
3 *Fraxinus pennsylvanica*	1	N	FACW
4			
5			
	8	= Total Cover	

Herb stratum (Plot size: 5ft radius)			
1 *Poa pratensis*	100	Y	FAC
2 *Solidago altissima*	20	N	FACU
3 *Daucus carota*	5	N	UPL
4			
5			
6			
7			
8			
9			
10			
	125	= Total Cover	

Woody vine stratum (Plot size: 30ft radius)			
1			
2			
	0	= Total Cover	

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 3 (A)

Total Number of Dominant Species Across all Strata: 5 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 60.00% (A/B)

Prevalence Index Worksheet

Total % Cover of:			
OBL species	0	x 1 =	0
FACW species	1	x 2 =	2
FAC species	112	x 3 =	336
FACU species	28	x 4 =	112
UPL species	5	x 5 =	25
Column totals	146 (A)		475 (B)

Prevalence Index = B/A = 3.25

Hydrophytic Vegetation Indicators:

- ___ Rapid test for hydrophytic vegetation
- X Dominance test is >50%
- ___ Prevalence index is ≤3.0*
- ___ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ___ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? Y

Remarks: (Include photo numbers here or on a separate sheet)

Old field

SOIL

Sampling Point: 2

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-8	10YR 3/2	100					Silty Clay Loam	
8-20	10YR 4/3	80	10YR 4/4	10	C	M	Silty Clay	
			10YR 6/1	10	C	M		

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: _____

Depth (inches): _____

Hydric soil present? N

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes	___	No	X	Depth (inches): ___
Water table present?	Yes	___	No	X	Depth (inches): ___
Saturation present? (includes capillary fringe)	Yes	___	No	X	Depth (inches): ___

Indicators of wetland hydrology present? N

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

2' above wetland

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 3

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Hillslope | Local relief (concave, convex, none): Convex

Slope (%): 4-6 | Lat: | Long: | Datum:

Soil Map Unit Name: Ozaukee Silt Loam (7530B2/OzaB2) | NWI Classification: None

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic?

SUMMARY OF FINDINGS

(If needed, explain any answers in remarks.)

Hydrophytic vegetation present?	Y		
Hydric soil present?	N	**Is the sampled area within a wetland?**	N
Indicators of wetland hydrology present?	N	If yes, optional wetland site ID:	

Remarks: (Explain alternative procedures here or in a separate report.)

VEGETATION -- Use scientific names of plants.

Tree Stratum (Plot size: 30ft radius)	Absolute % Cover	Dominant Species	Indicator Status
1 *Populus deltoides*	10	Y	FAC
2 *Juniperus virginiana*	2	N	FACU
3			
4			
5			
	12	= Total Cover	

Sapling/Shrub stratum (Plot size: 30ft radius)			
1 *Rhamnus cathartica*	5	Y	FAC
2 *Rosa multiflora*	5	Y	FACU
3 *Fraxinus pennsylvanica*	2	N	FACW
4			
5			
	12	= Total Cover	

Herb stratum (Plot size: 5ft radius)			
1 *Poa pratensis*	100	Y	FAC
2 *Rhamnus cathartica*	15	N	FAC
3 *Symphyotrichum pilosum*	5	N	FACU
4 *Solidago altissima*	5	N	FACU
5 *Euthamia graminifolia*	3	N	FACW
6			
7			
8			
9			
10			
	128	= Total Cover	

Woody vine stratum (Plot size: 30ft radius)			
1			
2			
	0	= Total Cover	

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 3 (A)

Total Number of Dominant Species Across all Strata: 4 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 75.00% (A/B)

Prevalence Index Worksheet

Total % Cover of:				
OBL species	0	x 1 =	0	
FACW species	5	x 2 =	10	
FAC species	130	x 3 =	390	
FACU species	17	x 4 =	68	
UPL species	0	x 5 =	0	
Column totals	152	(A)	468	(B)

Prevalence Index = B/A = 3.08

Hydrophytic Vegetation Indicators:

- ____ Rapid test for hydrophytic vegetation
- X Dominance test is >50%
- ____ Prevalence index is ≤3.0*
- ____ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ____ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? Y

Remarks: (Include photo numbers here or on a separate sheet)

Old field

SOIL

Sampling Point: 3

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-10	10YR 2/2	100					Silty Clay Loam	
10-20	10YR 4/3	96	10YR 4/6	2	C	M	Silty Clay	
			10YR 6/1	2	D	M		

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: _____

Depth (inches): _____

Hydric soil present? N

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes	___	No	X	Depth (inches): ___
Water table present?	Yes	___	No	X	Depth (inches): ___
Saturation present? (includes capillary fringe)	Yes	___	No	X	Depth (inches): ___

Indicators of wetland hydrology present? N

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

2' above wetland

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 4

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Depression | Local relief (concave, convex, none): Concave

Slope (%): 0-4 | Lat: | Long: | Datum:

Soil Map Unit Name: Ashkum Silty Clay Loam (7232A/AtA) | NWI Classification: E2K

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic?

SUMMARY OF FINDINGS

(If needed, explain any answers in remarks.)

Hydrophytic vegetation present?	Y		
Hydric soil present?	Y	**Is the sampled area within a wetland?**	Y
Indicators of wetland hydrology present?	Y	If yes, optional wetland site ID:	

Remarks: (Explain alternative procedures here or in a separate report.)

VEGETATION -- Use scientific names of plants.

	Absolute % Cover	Dominant Species	Indicator Status
Tree Stratum (Plot size: 30ft radius)			
1 *Populus deltoides*	5	Y	FAC
2			
3			
4			
5			
	5	= Total Cover	
Sapling/Shrub stratum (Plot size: 30ft radius)			
1 *Populus deltoides*	1	N	FAC
2			
3			
4			
5			
	1	= Total Cover	
Herb stratum (Plot size: 5ft radius)			
1 *Phalaris arundinacea*	80	Y	FACW
2 *Phragmites australis*	15	N	FACW
3 *Typha x glauca*	15	N	OBL
4			
5			
6			
7			
8			
9			
10			
	110	= Total Cover	
Woody vine stratum (Plot size: 30ft radius)			
1			
2			
	0	= Total Cover	

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 2 (A)

Total Number of Dominant Species Across all Strata: 2 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 100.00% (A/B)

Prevalence Index Worksheet

Total % Cover of:			
OBL species	15	x 1 =	15
FACW species	95	x 2 =	190
FAC species	6	x 3 =	18
FACU species	0	x 4 =	0
UPL species	0	x 5 =	0
Column totals	116 (A)		223 (B)

Prevalence Index = B/A = 1.92

Hydrophytic Vegetation Indicators:

- ___ Rapid test for hydrophytic vegetation
- X Dominance test is >50%
- X Prevalence index is ≤3.0*
- ___ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ___ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? Y

Remarks: (Include photo numbers here or on a separate sheet)

Fresh wet meadow

SOIL

Sampling Point: 4

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-4	10YR 3/1	100					Silty Clay Loam	
4-20	10YR 6/1	90	10YR 5/6	10	C	M	Silty Clay	

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- X Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- X Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: _____

Depth (inches): _____

Hydric soil present? Y

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- X Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- X Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- X Geomorphic Position (D2)
- X FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes	X	No		Depth (inches):	1
Water table present?	Yes		No	X	Depth (inches):	
Saturation present? (includes capillary fringe)	Yes		No	X	Depth (inches):	

Indicators of wetland hydrology present? Y

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site: Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 5

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Hillslope | Local relief (concave, convex, none): Convex

Slope (%): 2-3 | Lat: | Long: | Datum:

Soil Map Unit Name: Ashkum Silty Clay Loam (7232A/AtA) | NWI Classification: None

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic? (If needed, explain any answers in remarks.)

SUMMARY OF FINDINGS

Hydrophytic vegetation present? N	**Is the sampled area within a wetland?** N
Hydric soil present? Y	If yes, optional wetland site ID:
Indicators of wetland hydrology present? Y	

Remarks: (Explain alternative procedures here or in a separate report.)

VEGETATION -- Use scientific names of plants.

Tree Stratum (Plot size: 30ft radius)	Absolute % Cover	Dominant Species	Indicator Status
1			
2			
3			
4			
5			
	0 = Total Cover		

Sapling/Shrub stratum (Plot size: 30ft radius)			
1			
2			
3			
4			
5			
	0 = Total Cover		

Herb stratum (Plot size: 5ft radius)			
1 *Taraxacum officinale*	1	N	FACU
2			
3			
4			
5			
6			
7			
8			
9			
10			
	1 = Total Cover		

Woody vine stratum (Plot size: 30ft radius)			
1			
2			
	0 = Total Cover		

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 0 (A)

Total Number of Dominant Species Across all Strata: 0 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 0.00% (A/B)

Prevalence Index Worksheet

Total % Cover of:

OBL species	0	x 1 =	0
FACW species	0	x 2 =	0
FAC species	0	x 3 =	0
FACU species	1	x 4 =	4
UPL species	0	x 5 =	0
Column totals	1 (A)		4 (B)

Prevalence Index = B/A = 4.00

Hydrophytic Vegetation Indicators:

- ___ Rapid test for hydrophytic vegetation
- ___ Dominance test is >50%
- ___ Prevalence index is ≤3.0*
- ___ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ___ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? N

Remarks: (Include photo numbers here or on a separate sheet)

Corn field, 100% corn stubble

SOIL

Sampling Point: 5

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-6	10YR 2/1	100					Silty Clay Loam	
6-20	10YR 2/1	70	10YR 5/6	5	C	M	Silty Clay	
	10YR 6/2	25						

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- X Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: _____

Depth (inches): _____

Hydric soil present? Y

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- X Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- X Geomorphic Position (D2)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes		No	X	Depth (inches):	
Water table present?	Yes	X	No		Depth (inches):	18
Saturation present? (includes capillary fringe)	Yes	X	No		Depth (inches):	14

Indicators of wetland hydrology present? Y

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

FSA Area B showed wetness signatures in 73% of years.

Remarks:

6" above wetland, drain tile likely, Bee hive structure nearby

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 6

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Slight depression on hilltop | Local relief (concave, convex, none): Concave

Slope (%): 1-3 | Lat: | Long: | Datum:

Soil Map Unit Name: Ashkum Silty Clay Loam (7232A/AtA) | NWI Classification: None

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic? (If needed, explain any answers in remarks.)

SUMMARY OF FINDINGS

Hydrophytic vegetation present? N	**Is the sampled area within a wetland?** N
Hydric soil present? N	If yes, optional wetland site ID:
Indicators of wetland hydrology present? N	

Remarks: (Explain alternative procedures here or in a separate report.)

VEGETATION -- Use scientific names of plants.

Tree Stratum (Plot size: 30ft radius)	Absolute % Cover	Dominant Species	Indicator Status
1			
2			
3			
4			
5			
	0 = Total Cover		

Sapling/Shrub stratum (Plot size: 30ft radius)			
1			
2			
3			
4			
5			
	0 = Total Cover		

Herb stratum (Plot size: 5ft radius)			
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			
	0 = Total Cover		

Woody vine stratum (Plot size: 30ft radius)			
1			
2			
	0 = Total Cover		

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 0 (A)

Total Number of Dominant Species Across all Strata: 0 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 0.00% (A/B)

Prevalence Index Worksheet

Total % Cover of:

OBL species	0	x 1 =	0
FACW species	0	x 2 =	0
FAC species	0	x 3 =	0
FACU species	0	x 4 =	0
UPL species	0	x 5 =	0
Column totals	0 (A)		0 (B)

Prevalence Index = B/A =

Hydrophytic Vegetation Indicators:

- ___ Rapid test for hydrophytic vegetation
- ___ Dominance test is >50%
- ___ Prevalence index is ≤3.0*
- ___ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ___ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? N

Remarks: (Include photo numbers here or on a separate sheet)

Corn field, 100% corn stubble, no weeds

SOIL

Sampling Point: 6

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-10	10YR 4/3	97	10YR 4/6	3	C	M	Silty Clay Loam	
10-20	10YR 5/3	88	10YR 5/6	2	C	M	Silty Clay	Rocky near bottom
			10YR 7/1	10	D	M		

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: _____

Depth (inches): _____

Hydric soil present? N

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- X Geomorphic Position (D2)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes ___	No	X	Depth (inches):	___
Water table present?	Yes ___	No	X	Depth (inches):	___
Saturation present? (includes capillary fringe)	Yes ___	No	X	Depth (inches):	___

Indicators of wetland hydrology present? N

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

FSA Area C showed wetness signatures in 18% of years.

Remarks:

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 7

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Hillslope | Local relief (concave, convex, none): concave

Slope (%): 2 | Lat: | Long: | Datum:

Soil Map Unit Name: Ozaukee Silt Loam (7530B/OzaB) | NWI Classification: none

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic?

SUMMARY OF FINDINGS

(If needed, explain any answers in remarks.)

Hydrophytic vegetation present?	N		
Hydric soil present?	Y	**Is the sampled area within a wetland?**	N
Indicators of wetland hydrology present?	Y	If yes, optional wetland site ID:	

Remarks: (Explain alternative procedures here or in a separate report.)

VEGETATION -- Use scientific names of plants.

Tree Stratum (Plot size: 30ft radius)	Absolute % Cover	Dominant Species	Indicator Status
1			
2			
3			
4			
5			
	0 = Total Cover		

Sapling/Shrub stratum (Plot size: 30ft radius)			
1			
2			
3			
4			
5			
	0 = Total Cover		

Herb stratum (Plot size: 5ft radius)			
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			
	0 = Total Cover		

Woody vine stratum (Plot size: 30ft radius)			
1			
2			
	0 = Total Cover		

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 0 (A)

Total Number of Dominant Species Across all Strata: 0 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 0.00% (A/B)

Prevalence Index Worksheet

Total % Cover of:

OBL species	0	x 1 =	0	
FACW species	0	x 2 =	0	
FAC species	0	x 3 =	0	
FACU species	0	x 4 =	0	
UPL species	0	x 5 =	0	
Column totals	0	(A)	0	(B)

Prevalence Index = B/A =

Hydrophytic Vegetation Indicators:

- ____ Rapid test for hydrophytic vegetation
- ____ Dominance test is >50%
- ____ Prevalence index is ≤3.0*
- ____ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ____ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? N

Remarks: (Include photo numbers here or on a separate sheet)

Corn field, 100% corn stubble, no weeds. Edge of woods reference: *Quercus macrocarpa*, *Rubus occidentalis*, *Lonicera x bella*

SOIL

Sampling Point: 7

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-10	10YR 2/1	100					Silty Clay Loam	
10-18	10YR 2/1	40	10YR 4/6	5	C	M	Silty Clay Loam	
	2.5YR 5/2	55						
18-20	2.5Y 5/2	85	10YR 5/6	5	C	M	Silty Clay	
	10YR 2/1	10						Inclusion

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- X Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- X Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: _____

Depth (inches): _____

Hydric soil present? Y

Remarks:

Dry in pit

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- X Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- X Geomorphic Position (D2)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes	___	No	X	Depth (inches): ___
Water table present?	Yes	___	No	X	Depth (inches): ___
Saturation present? (includes capillary fringe)	Yes	___	No	X	Depth (inches): ___

Indicators of wetland hydrology present? Y

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

FSA Area A showed wetness signatures in 82% of years reviewed.

Remarks:

6" above wetland, drainage tile possible- beehive structure observed nearby.

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 8

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Ditched area | Local relief (concave, convex, none): Concave

Slope (%): 0-2 | Lat: | Long: | Datum:

Soil Map Unit Name: Ashkum Silty Clay Loam (7232A /AtA) | NWI Classification: E2K

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic?

SUMMARY OF FINDINGS

(If needed, explain any answers in remarks.)

Hydrophytic vegetation present?	Y		
Hydric soil present?	Y	**Is the sampled area within a wetland?**	Y
Indicators of wetland hydrology present?	Y	If yes, optional wetland site ID:	

Remarks: (Explain alternative procedures here or in a separate report.)

VEGETATION -- Use scientific names of plants.

Tree Stratum (Plot size: 30ft radius)	Absolute % Cover	Dominant Species	Indicator Status
1			
2			
3			
4			
5			
	0	= Total Cover	

Sapling/Shrub stratum (Plot size: 30ft radius)			
1			
2			
3			
4			
5			
	0	= Total Cover	

Herb stratum (Plot size: 5ft radius)			
1 *Phalaris arundinacea*	100	Y	FACW
2 *Solidago altissima*	3	N	FACU
3			
4			
5			
6			
7			
8			
9			
10			
	103	= Total Cover	

Woody vine stratum (Plot size: 30ft radius)			
1			
2			
	0	= Total Cover	

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 1 (A)

Total Number of Dominant Species Across all Strata: 1 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 100.00% (A/B)

Prevalence Index Worksheet

Total % Cover of:

OBL species	0	x 1 =	0
FACW species	100	x 2 =	200
FAC species	0	x 3 =	0
FACU species	3	x 4 =	12
UPL species	0	x 5 =	0
Column totals	103 (A)		212 (B)

Prevalence Index = B/A = 2.06

Hydrophytic Vegetation Indicators:

- ___ Rapid test for hydrophytic vegetation
- X Dominance test is >50%
- X Prevalence index is ≤3.0*
- ___ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ___ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? Y

Remarks: (Include photo numbers here or on a separate sheet)

Fresh wet meadow

SOIL

Sampling Point: 8

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-5	10YR 2/1	100					Silty Clay Loam	
5-20	10YR 6/1	90	10YR 4/6	10	C	M	Silty Clay	

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- X Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- X Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: _____

Depth (inches): _____

Hydric soil present? Y

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- X High Water Table (A2)
- X Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- X Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- X Geomorphic Position (D2)
- X FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes		No	X	Depth (inches):	
Water table present?	Yes	X	No		Depth (inches):	6
Saturation present? (includes capillary fringe)	Yes	X	No		Depth (inches):	At surface

Indicators of wetland hydrology present? Y

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site: Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 9

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Hillslope | Local relief (concave, convex, none): Convex

Slope (%): 3 | Lat: | Long: | Datum:

Soil Map Unit Name: Ashkum Silty Clay Loam (7232A /AtA) | NWI Classification: none

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic? (If needed, explain any answers in remarks.)

SUMMARY OF FINDINGS

Hydrophytic vegetation present?	N		
Hydric soil present?	N	**Is the sampled area within a wetland?**	N
Indicators of wetland hydrology present?	N	If yes, optional wetland site ID:	

Remarks: (Explain alternative procedures here or in a separate report.)

VEGETATION -- Use scientific names of plants.

Tree Stratum (Plot size: 30ft radius)	Absolute % Cover	Dominant Species	Indicator Status
1 *Quercus macrocarpa*	3	N	FAC
2			
3			
4			
5			
	3	= Total Cover	

Sapling/Shrub stratum (Plot size: 30ft radius)			
1 *Juniperus virginiana*	2	Y	FACU
2 *Malus pumila*	2	Y	UPL
3 *Quercus macrocarpa*	2	Y	FAC
4			
5			
	6	= Total Cover	

Herb stratum (Plot size: 5ft radius)			
1 *Poa pratensis*	90	Y	FAC
2 *Solidago altissima*	15	N	FACU
3			
4			
5			
6			
7			
8			
9			
10			
	105	= Total Cover	

Woody vine stratum (Plot size: 30ft radius)			
1			
2			
	0	= Total Cover	

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 2 (A)

Total Number of Dominant Species Across all Strata: 4 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 50.00% (A/B)

Prevalence Index Worksheet

Total % Cover of:

OBL species	0	x 1 =	0
FACW species	0	x 2 =	0
FAC species	95	x 3 =	285
FACU species	17	x 4 =	68
UPL species	2	x 5 =	10
Column totals	114 (A)		363 (B)

Prevalence Index = B/A = 3.18

Hydrophytic Vegetation Indicators:

- ____ Rapid test for hydrophytic vegetation
- ____ Dominance test is >50%
- ____ Prevalence index is ≤3.0*
- ____ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ____ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? N

Remarks: (Include photo numbers here or on a separate sheet)

Old field

SOIL

Sampling Point: 9

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-8	10YR 2/1	100					Silty Clay Loam	
8-20	10YR 4/3	90	10YR 5/6	10	C	M	Silty Clay	

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: _____

Depth (inches): _____

Hydric soil present? N

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes		No	X	Depth (inches):	
Water table present?	Yes	X	No		Depth (inches):	20
Saturation present? (includes capillary fringe)	Yes	X	No		Depth (inches):	18

Indicators of wetland hydrology present? N

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

12" above wetland

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 10

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Creek | Local relief (concave, convex, none): Concave

Slope (%): 0-2 | Lat: | Long: | Datum:

Soil Map Unit Name: Ashkum Silty Clay Loam (7232A /AtA) | NWI Classification: E2K

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic?

SUMMARY OF FINDINGS

(If needed, explain any answers in remarks.)

Hydrophytic vegetation present?	Y		
Hydric soil present?	Y	**Is the sampled area within a wetland?**	Y
Indicators of wetland hydrology present?	Y	If yes, optional wetland site ID:	

Remarks: (Explain alternative procedures here or in a separate report.)

VEGETATION -- Use scientific names of plants.

	Tree Stratum (Plot size: 30ft radius)	Absolute % Cover	Dominant Species	Indicator Status
1	*Populus deltoides*	30	Y	FAC
2	*Acer negundo*	5	N	FAC
3	*Morus alba*	3	N	FAC
4				
5				
		38	= Total Cover	

	Sapling/Shrub stratum (Plot size: 30ft radius)			
1	*Rhamnus cathartica*	15	Y	FAC
2	*Fraxinus pennsylvanica*	5	Y	FACW
3	*Rosa multiflora*	2	N	FACU
4				
5				
		22	= Total Cover	

	Herb stratum (Plot size: 5ft radius)			
1	*Phalaris arundinacea*	10	Y	FACW
2	*Rhamnus cathartica*	5	Y	FAC
3	*Acer negundo*	3	N	FAC
4				
5				
6				
7				
8				
9				
10				
		18	= Total Cover	

	Woody vine stratum (Plot size: 30ft radius)			
1				
2				
		0	= Total Cover	

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 5 (A)

Total Number of Dominant Species Across all Strata: 5 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 100.00% (A/B)

Prevalence Index Worksheet

Total % Cover of:

OBL species	0	x 1 =	0
FACW species	15	x 2 =	30
FAC species	61	x 3 =	183
FACU species	2	x 4 =	8
UPL species	0	x 5 =	0
Column totals	78 (A)		221 (B)

Prevalence Index = B/A = 2.83

Hydrophytic Vegetation Indicators:

- ___ Rapid test for hydrophytic vegetation
- X Dominance test is >50%
- X Prevalence index is ≤3.0*
- ___ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ___ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? Y

Remarks: (Include photo numbers here or on a separate sheet)

Forested wetland near intermittent creek

SOIL

Sampling Point: 10

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-12	10YR 2/1	100					Silty Clay Loam	
12-20	10YR 5/2	90	10YR 4/4	10	C	M	Silty Clay Loam	

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- X Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: _____

Depth (inches): _____

Hydric soil present? Y

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- X High Water Table (A2)
- X Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- X Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- X Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- X Geomorphic Position (D2)
- X FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes		No	X	Depth (inches):	
Water table present?	Yes	X	No		Depth (inches):	5
Saturation present? (includes capillary fringe)	Yes	X	No		Depth (inches):	At surface

Indicators of wetland hydrology present? Y

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site: Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 11

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Hillslope | Local relief (concave, convex, none): Convex

Slope (%): 2-3 | Lat: | Long: | Datum:

Soil Map Unit Name: Beecher Silt Loam (7298B/BcA) | NWI Classification: None

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic? (If needed, explain any answers in remarks.)

SUMMARY OF FINDINGS

Hydrophytic vegetation present? Y	**Is the sampled area within a wetland?** N
Hydric soil present? N	If yes, optional wetland site ID:
Indicators of wetland hydrology present? N	

Remarks: (Explain alternative procedures here or in a separate report.)

VEGETATION -- Use scientific names of plants.

Tree Stratum (Plot size: 30ft radius)	Absolute % Cover	Dominant Species	Indicator Status
1 *Quercus macrocarpa*	10	Y	FAC
2 *Juniperus virginiana*	3	Y	FACU
3			
4			
5			
	13	= Total Cover	

Sapling/Shrub stratum (Plot size: 30ft radius)			
1 *Rhamnus cathartica*	5	Y	FAC
2 *Elaeagnus umbellata*	5	Y	
3 *Lonicera x bella*	2	N	FACU
4			
5			
	12	= Total Cover	

Herb stratum (Plot size: 5ft radius)			
1 *Poa pratensis*	95	Y	FAC
2 *Solidago altissima*	15	N	FACU
3 *Asclepias syriaca*	1	N	FACU
4			
5			
6			
7			
8			
9			
10			
	111	= Total Cover	

Woody vine stratum (Plot size: 30ft radius)			
1			
2			
	0	= Total Cover	

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 3 (A)

Total Number of Dominant Species Across all Strata: 5 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 60.00% (A/B)

Prevalence Index Worksheet

Total % Cover of:			
OBL species	0	x 1 =	0
FACW species	0	x 2 =	0
FAC species	110	x 3 =	330
FACU species	21	x 4 =	84
UPL species	0	x 5 =	0
Column totals	131 (A)		414 (B)

Prevalence Index = B/A = 3.16

Hydrophytic Vegetation Indicators:

- ____ Rapid test for hydrophytic vegetation
- X Dominance test is >50%
- ____ Prevalence index is ≤3.0*
- ____ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ____ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? Y

Remarks: (Include photo numbers here or on a separate sheet)

Old field

SOIL

Sampling Point: 11

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-8	10YR 3/3	90	10YR 4/6	10	C	M	Silty Clay Loam	
8-20	7.5YR 4/4	95	7.5YR 5/6	5	C	M	Silty Clay	

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: Rocky fill

Depth (inches): 20

Hydric soil present? N

Remarks:

Refusal at 20" due to rocky fill

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes		No	X	Depth (inches):	
Water table present?	Yes	X	No		Depth (inches):	20
Saturation present? (includes capillary fringe)	Yes	X	No		Depth (inches):	19

Indicators of wetland hydrology present? N

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

18" above wetland

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 12

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Depression | Local relief (concave, convex, none): Concave

Slope (%): 0-2 | Lat: | Long: | Datum:

Soil Map Unit Name: Ashkum Silty Clay Loam (7232A/AtA) | NWI Classification: E2K

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic? (If needed, explain any answers in remarks.)

SUMMARY OF FINDINGS

Hydrophytic vegetation present?	Y		
Hydric soil present?	Y	**Is the sampled area within a wetland?**	Y
Indicators of wetland hydrology present?	Y	If yes, optional wetland site ID:	

Remarks: (Explain alternative procedures here or in a separate report.)

VEGETATION -- Use scientific names of plants.

	Tree Stratum (Plot size: 30ft radius)	Absolute % Cover	Dominant Species	Indicator Status
1	*Salix nigra*	10	Y	OBL
2				
3				
4				
5				
		10	= Total Cover	
	Sapling/Shrub stratum (Plot size: 30ft radius)			
1	*Salix interior*	50	Y	FACW
2	*Cornus alba*	15	Y	FACW
3	*Rhamnus cathartica*	5	N	FAC
4	*Salix discolor*	3	N	FACW
5				
		73	= Total Cover	
	Herb stratum (Plot size: 5ft radius)			
1	*Phalaris arundinacea*	80	Y	FACW
2	*Typha x glauca*	10	N	OBL
3				
4				
5				
6				
7				
8				
9				
10				
		90	= Total Cover	
	Woody vine stratum (Plot size: 30ft radius)			
1				
2				
		0	= Total Cover	

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 4 (A)

Total Number of Dominant Species Across all Strata: 4 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 100.00% (A/B)

Prevalence Index Worksheet

Total % Cover of:			
OBL species	20	x 1 =	20
FACW species	148	x 2 =	296
FAC species	5	x 3 =	15
FACU species	0	x 4 =	0
UPL species	0	x 5 =	0
Column totals	173 (A)		331 (B)

Prevalence Index = B/A = 1.91

Hydrophytic Vegetation Indicators:

- ___ Rapid test for hydrophytic vegetation
- X Dominance test is >50%
- X Prevalence index is ≤3.0*
- ___ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ___ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? Y

Remarks: (Include photo numbers here or on a separate sheet)

Scrub-shrub/fresh wet meadow wetland

SOIL

Sampling Point: 12

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-7	10YR 2/1	100					Silty Clay Loam	
7-20	10YR 2/1	75	10YR 5/2	20	D	M	Silty Clay	
			10YR 4/6	5	C	M		

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- X Redox Dark Surface (F6)
- X Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: _____

Depth (inches): _____

Hydric soil present? Y

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- X High Water Table (A2)
- X Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- X Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- X Geomorphic Position (D2)
- X FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes		No	X	Depth (inches):	
Water table present?	Yes	X	No		Depth (inches):	9
Saturation present? (includes capillary fringe)	Yes	X	No		Depth (inches):	At surface

Indicators of wetland hydrology present? Y

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site: Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 13

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Hillslope | Local relief (concave, convex, none): Convex

Slope (%): 3-4 | Lat: | Long: | Datum:

Soil Map Unit Name: Beecher Silt Loam (7298B/BcA) | NWI Classification: None

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic? (If needed, explain any answers in remarks.)

SUMMARY OF FINDINGS

Hydrophytic vegetation present?	Y		
Hydric soil present?	N	**Is the sampled area within a wetland?**	N
Indicators of wetland hydrology present?	N	If yes, optional wetland site ID:	

Remarks: (Explain alternative procedures here or in a separate report.)

VEGETATION -- Use scientific names of plants.

Tree Stratum (Plot size: 30ft radius)	Absolute % Cover	Dominant Species	Indicator Status
1 *Quercus macrocarpa*	15	Y	FAC
2			
3			
4			
5			
	15	= Total Cover	

Sapling/Shrub stratum (Plot size: 30ft radius)			
1 *Rhamnus cathartica*	3	N	FAC
2			
3			
4			
5			
	3	= Total Cover	

Herb stratum (Plot size: 5ft radius)			
1 *Poa pratensis*	95	Y	FAC
2 *Solidago altissima*	15	N	FACU
3 *Vitis riparia*	5	N	FACW
4			
5			
6			
7			
8			
9			
10			
	115	= Total Cover	

Woody vine stratum (Plot size: 30ft radius)			
1			
2			
	0	= Total Cover	

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 2 (A)

Total Number of Dominant Species Across all Strata: 2 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 100.00% (A/B)

Prevalence Index Worksheet

Total % Cover of:

OBL species	0	x 1 =	0
FACW species	5	x 2 =	10
FAC species	113	x 3 =	339
FACU species	15	x 4 =	60
UPL species	0	x 5 =	0
Column totals	133 (A)		409 (B)

Prevalence Index = B/A = 3.08

Hydrophytic Vegetation Indicators:

- ___ Rapid test for hydrophytic vegetation
- X Dominance test is >50%
- ___ Prevalence index is ≤3.0*
- ___ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ___ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? Y

Remarks: (Include photo numbers here or on a separate sheet)

Old field

SOIL

Sampling Point: 13

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-7	10YR 2/2	100					Silty Clay Loam	
7-20	10YR 3/4	95	10YR 4/6	5	C	M	Silty Clay	Iron concretion present

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: _____

Depth (inches): _____

Hydric soil present? N

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes ___	No	X	Depth (inches):	___
Water table present?	Yes ___	No	X	Depth (inches):	___
Saturation present? (includes capillary fringe)	Yes ___	No	X	Depth (inches):	___

Indicators of wetland hydrology present? N

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

18" above wetland

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site: Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 14

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Hillslope | Local relief (concave, convex, none): Convex

Slope (%): 2 | Lat: | Long: | Datum:

Soil Map Unit Name: Beecher Silt Loam (7298B/BcA) | NWI Classification: None

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic? (If needed, explain any answers in remarks.)

SUMMARY OF FINDINGS

Hydrophytic vegetation present? Y	**Is the sampled area within a wetland?** N
Hydric soil present? Y	If yes, optional wetland site ID:
Indicators of wetland hydrology present? N	

Remarks: (Explain alternative procedures here or in a separate report.)

VEGETATION -- Use scientific names of plants.

Tree Stratum (Plot size: 30ft radius)	Absolute % Cover	Dominant Species	Indicator Status
1 *Populus deltoides*	3	Y	FAC
2			
3			
4			
5			
	3	= Total Cover	

Sapling/Shrub stratum (Plot size: 30ft radius)			
1			
2			
3			
4			
5			
	0	= Total Cover	

Herb stratum (Plot size: 5ft radius)			
1 *Poa pratensis*	85	Y	FAC
2 *Solidago altissima*	15	N	FACU
3			
4			
5			
6			
7			
8			
9			
10			
	100	= Total Cover	

Woody vine stratum (Plot size: 30ft radius)			
1			
2			
	0	= Total Cover	

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 2 (A)

Total Number of Dominant Species Across all Strata: 2 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 100.00% (A/B)

Prevalence Index Worksheet

Total % Cover of:

OBL species	0	x 1 =	0
FACW species	0	x 2 =	0
FAC species	88	x 3 =	264
FACU species	15	x 4 =	60
UPL species	0	x 5 =	0
Column totals	103 (A)		324 (B)

Prevalence Index = B/A = 3.15

Hydrophytic Vegetation Indicators:

- ___ Rapid test for hydrophytic vegetation
- X Dominance test is >50%
- ___ Prevalence index is ≤3.0*
- ___ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ___ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? Y

Remarks: (Include photo numbers here or on a separate sheet)

Old field

SOIL

Sampling Point: 14

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-11	10YR 2/1	95	10YR 4/4	5	C	M	Silty Clay Loam	
11-20	10YR 2/1	95	10YR 3/4	5	C	PL/M	Silty Clay	

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- X Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: _____

Depth (inches): _____

Hydric soil present? Y

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes ___	No	X	Depth (inches):	___
Water table present?	Yes ___	No	X	Depth (inches):	___
Saturation present? (includes capillary fringe)	Yes ___	No	X	Depth (inches):	___

Indicators of wetland hydrology present? N

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

Dry in pit

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 15

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Depression | Local relief (concave, convex, none): Concave

Slope (%): 0-2 | Lat: | Long: | Datum:

Soil Map Unit Name: Beecher Silt Loam (7298B/BcA) | NWI Classification: None

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic?

SUMMARY OF FINDINGS

(If needed, explain any answers in remarks.)

Hydrophytic vegetation present?	Y		
Hydric soil present?	Y	**Is the sampled area within a wetland?**	Y
Indicators of wetland hydrology present?	Y	If yes, optional wetland site ID:	

Remarks: (Explain alternative procedures here or in a separate report.)

VEGETATION -- Use scientific names of plants.

Tree Stratum (Plot size: 30ft radius)	Absolute % Cover	Dominant Species	Indicator Status
1 *Populus deltoides*	10	Y	FAC
2			
3			
4			
5			
	10	= Total Cover	

Sapling/Shrub stratum (Plot size: 30ft radius)			
1 *Salix interior*	20	Y	FACW
2 *Salix nigra*	5	Y	OBL
3			
4			
5			
	25	= Total Cover	

Herb stratum (Plot size: 5ft radius)			
1 *Poa pratensis*	50	Y	FAC
2 *Phalaris arundinacea*	40	Y	FACW
3 *Euthamia graminifolia*	10	N	FACW
4 *Salix interior*	10	N	FACW
5 *Scirpus atrovirens*	10	N	OBL
6			
7			
8			
9			
10			
	120	= Total Cover	

Woody vine stratum (Plot size: 30ft radius)			
1			
2			
	0	= Total Cover	

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 5 (A)

Total Number of Dominant Species Across all Strata: 5 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 100.00% (A/B)

Prevalence Index Worksheet

Total % Cover of:

OBL species	15	x 1 =	15
FACW species	80	x 2 =	160
FAC species	60	x 3 =	180
FACU species	0	x 4 =	0
UPL species	0	x 5 =	0
Column totals	155 (A)		355 (B)

Prevalence Index = B/A = 2.29

Hydrophytic Vegetation Indicators:

- ___ Rapid test for hydrophytic vegetation
- X Dominance test is >50%
- X Prevalence index is ≤3.0*
- ___ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ___ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? Y

Remarks: (Include photo numbers here or on a separate sheet)

Scrub-shrub/fresh wet meadow wetland.

SOIL

Sampling Point: 15

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-19	10YR 2/1	95	10YR 3/4	5	C	M	Silty Clay	
19-26	10YR 5/2	85	10YR 4/4	5	C	M	Silty Clay	
			10YR 2/1	10				Inclusion

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- ___ Depleted Below Dark Surface (A11)
- X Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- X Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: _____

Depth (inches): _____

Hydric soil present? Y

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- X Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- X Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- X Geomorphic Position (D2)
- X FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes	X	No		Depth (inches):	2
Water table present?	Yes		No	X	Depth (inches):	
Saturation present? (includes capillary fringe)	Yes		No	X	Depth (inches):	

Indicators of wetland hydrology present? Y

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site: Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 16

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Top of berm | Local relief (concave, convex, none): Convex

Slope (%): 2-3 | Lat: | Long: | Datum:

Soil Map Unit Name: Ashkum Silty Clay Loam (7232A/AtA) | NWI Classification: None

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic? (If needed, explain any answers in remarks.)

SUMMARY OF FINDINGS

Hydrophytic vegetation present? Y	**Is the sampled area within a wetland?** N
Hydric soil present? N	If yes, optional wetland site ID:
Indicators of wetland hydrology present? N	

Remarks: (Explain alternative procedures here or in a separate report.)

VEGETATION -- Use scientific names of plants.

Tree Stratum (Plot size: 30ft radius)	Absolute % Cover	Dominant Species	Indicator Status
1			
2			
3			
4			
5			
	0	= Total Cover	

Sapling/Shrub stratum (Plot size: 30ft radius)			
1			
2			
3			
4			
5			
	0	= Total Cover	

Herb stratum (Plot size: 5ft radius)			
1 *Poa pratensis*	90	Y	FAC
2 *Solidago altissima*	20	N	FACU
3			
4			
5			
6			
7			
8			
9			
10			
	110	= Total Cover	

Woody vine stratum (Plot size: 30ft radius)			
1			
2			
	0	= Total Cover	

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 1 (A)

Total Number of Dominant Species Across all Strata: 1 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 100.00% (A/B)

Prevalence Index Worksheet

Total % Cover of:

OBL species	0	x 1 =	0
FACW species	0	x 2 =	0
FAC species	90	x 3 =	270
FACU species	20	x 4 =	80
UPL species	0	x 5 =	0
Column totals	110 (A)		350 (B)

Prevalence Index = B/A = 3.18

Hydrophytic Vegetation Indicators:

- ___ Rapid test for hydrophytic vegetation
- X Dominance test is >50%
- ___ Prevalence index is ≤3.0*
- ___ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ___ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? Y

Remarks: (Include photo numbers here or on a separate sheet)

Old field

SOIL

Sampling Point: 16

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-5	10YR 2/2	100					Silty Clay Loam	
5-20	10YR 2/2	50					Silty Clay	
	10YR 4/3	45	10YR 4/6	5	C	M	Silty Clay	

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: _____

Depth (inches): _____

Hydric soil present? N

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes ___	No	X	Depth (inches):	___
Water table present?	Yes ___	No	X	Depth (inches):	___
Saturation present? (includes capillary fringe)	Yes ___	No	X	Depth (inches):	___

Indicators of wetland hydrology present? N

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

6' above wetland

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 17

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Toe Slope | Local relief (concave, convex, none): Concave

Slope (%): 0-2 | Lat: | Long: | Datum:

Soil Map Unit Name: Ashkum Silty Clay Loam (7232A/AtA) | NWI Classification: E2K

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic? (If needed, explain any answers in remarks.)

SUMMARY OF FINDINGS

Hydrophytic vegetation present?	Y		
Hydric soil present?	Y	**Is the sampled area within a wetland?**	Y
Indicators of wetland hydrology present?	Y	If yes, optional wetland site ID:	

Remarks: (Explain alternative procedures here or in a separate report.)

VEGETATION -- Use scientific names of plants.

Tree Stratum (Plot size: 30ft radius)	Absolute % Cover	Dominant Species	Indicator Status
1			
2			
3			
4			
5			
	0	= Total Cover	

Sapling/Shrub stratum (Plot size: 30ft radius)			
1 *Salix bebbiana*	5	Y	FACW
2 *Lonicera x bella*	2	Y	FACU
3			
4			
5			
	7	= Total Cover	

Herb stratum (Plot size: 5ft radius)			
1 *Phalaris arundinacea*	100	Y	FACW
2 *Solidago altissima*	3	N	FACU
3			
4			
5			
6			
7			
8			
9			
10			
	103	= Total Cover	

Woody vine stratum (Plot size: 30ft radius)			
1			
2			
	0	= Total Cover	

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 2 (A)

Total Number of Dominant Species Across all Strata: 3 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 66.67% (A/B)

Prevalence Index Worksheet

Total % Cover of:			
OBL species	0	x 1 =	0
FACW species	105	x 2 =	210
FAC species	0	x 3 =	0
FACU species	5	x 4 =	20
UPL species	0	x 5 =	0
Column totals	110 (A)		230 (B)

Prevalence Index = B/A = 2.09

Hydrophytic Vegetation Indicators:

- ___ Rapid test for hydrophytic vegetation
- X Dominance test is >50%
- X Prevalence index is ≤3.0*
- ___ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ___ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? Y

Remarks: (Include photo numbers here or on a separate sheet)

Scrub-shrub/fresh wet meadow wetland

SOIL

Sampling Point: 17

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-11	10YR 2/1	95	10YR 4/4	5	C	M	Silty Clay Loam	
11-20	10YR 2/1	75	10YR 5/2	20	D	M	Silty Clay	
			10YR 4/4	5	C	PL/M		

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- X Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: _____

Depth (inches): _____

Hydric soil present? Y

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- X Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- X Geomorphic Position (D2)
- X FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes ___	No	X	Depth (inches):	___
Water table present?	Yes ___	No	X	Depth (inches):	___
Saturation present? (includes capillary fringe)	Yes ___	No	X	Depth (inches):	___

Indicators of wetland hydrology present? Y

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site: Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 18

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Depression | Local relief (concave, convex, none): Concave

Slope (%): 0-2 | Lat: | Long: | Datum:

Soil Map Unit Name: Ozaukee Silt Loam (7530C2/OzaB) | NWI Classification: T3K

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic? (If needed, explain any answers in remarks.)

SUMMARY OF FINDINGS

Hydrophytic vegetation present?	Y		
Hydric soil present?	Y	**Is the sampled area within a wetland?**	Y
Indicators of wetland hydrology present?	Y	If yes, optional wetland site ID:	

Remarks: (Explain alternative procedures here or in a separate report.)

VEGETATION -- Use scientific names of plants.

	Tree Stratum (Plot size: 30ft radius)	Absolute % Cover	Dominant Species	Indicator Status
1	*Populus deltoides*	50	Y	FAC
2				
3				
4				
5				
		50	= Total Cover	
	Sapling/Shrub stratum (Plot size: 30ft radius)			
1	*Rhamnus cathartica*	15	Y	FAC
2	*Lonicera x bella*	5	Y	FACU
3	*Rosa multiflora*	3	N	FACU
4	*Fraxinus pennsylvanica*	2	N	FACW
5				
		25	= Total Cover	
	Herb stratum (Plot size: 5ft radius)			
1	*Phalaris arundinacea*	100	Y	FACW
2				
3				
4				
5				
6				
7				
8				
9				
10				
		100	= Total Cover	
	Woody vine stratum (Plot size: 30ft radius)			
1				
2				
		0	= Total Cover	

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 3 (A)

Total Number of Dominant Species Across all Strata: 4 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 75.00% (A/B)

Prevalence Index Worksheet

Total % Cover of:			
OBL species	0	x 1 =	0
FACW species	102	x 2 =	204
FAC species	65	x 3 =	195
FACU species	8	x 4 =	32
UPL species	0	x 5 =	0
Column totals	175 (A)		431 (B)

Prevalence Index = B/A = 2.46

Hydrophytic Vegetation Indicators:

- ___ Rapid test for hydrophytic vegetation
- X Dominance test is >50%
- X Prevalence index is ≤3.0*
- ___ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ___ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? Y

Remarks: (Include photo numbers here or on a separate sheet)

Forested/fresh wet meadow wetland

SOIL

Sampling Point: 18

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-20	10YR 2/1	98	10YR 4/4	2	C	M	Silty Clay	

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- X Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: _____

Depth (inches): _____

Hydric soil present? Y

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- X Saturation (A3)
- X Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- X Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- X Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- X Geomorphic Position (D2)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes		No	X	Depth (inches):	
Water table present?	Yes	X	No		Depth (inches):	15
Saturation present? (includes capillary fringe)	Yes	X	No		Depth (inches):	12

Indicators of wetland hydrology present? Y

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 19

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Hillslope | Local relief (concave, convex, none): Convex

Slope (%): 8 | Lat: | Long: | Datum:

Soil Map Unit Name: Ozaukee Silt Loam (7530B/OzaB) | NWI Classification: None

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic? (If needed, explain any answers in remarks.)

SUMMARY OF FINDINGS

Hydrophytic vegetation present?	Y		
Hydric soil present?	N	**Is the sampled area within a wetland?**	N
Indicators of wetland hydrology present?	N	If yes, optional wetland site ID:	

Remarks: (Explain alternative procedures here or in a separate report.)

VEGETATION -- Use scientific names of plants.

Tree Stratum (Plot size: 30ft radius)	Absolute % Cover	Dominant Species	Indicator Status
1 *Quercus macrocarpa*	30	Y	FAC
2 *Juglans nigra*	30	Y	FACU
3			
4			
5			
	60	= Total Cover	

Sapling/Shrub stratum (Plot size: 30ft radius)			
1 *Lonicera x bella*	20	Y	FACU
2 *Rhamnus cathartica*	15	Y	FAC
3			
4			
5			
	35	= Total Cover	

Herb stratum (Plot size: 5ft radius)			
1 *Alliaria petiolata*	10	Y	FAC
2 *Geum canadense*	2	N	FAC
3			
4			
5			
6			
7			
8			
9			
10			
	12	= Total Cover	

Woody vine stratum (Plot size: 30ft radius)			
1			
2			
	0	= Total Cover	

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 3 (A)

Total Number of Dominant Species Across all Strata: 5 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 60.00% (A/B)

Prevalence Index Worksheet

Total % Cover of:			
OBL species	0	x 1 =	0
FACW species	0	x 2 =	0
FAC species	57	x 3 =	171
FACU species	50	x 4 =	200
UPL species	0	x 5 =	0
Column totals	107 (A)		371 (B)

Prevalence Index = B/A = 3.47

Hydrophytic Vegetation Indicators:

- ___ Rapid test for hydrophytic vegetation
- X Dominance test is >50%
- ___ Prevalence index is ≤3.0*
- ___ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ___ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? Y

Remarks: (Include photo numbers here or on a separate sheet)

Disturbed forest

SOIL

Sampling Point: 19

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-7	10YR 3/2	97	10YR 3/4	3	C	PL	Silty Clay loam	
7-15	10YR 4/3	95	10YR 4/4	5	C	M	Silty Clay	

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: Rocky fill

Depth (inches): 15

Hydric soil present? N

Remarks:

Refusal at 15" due to rocky fill

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes ___	No	X	Depth (inches):	___
Water table present?	Yes ___	No	X	Depth (inches):	___
Saturation present? (includes capillary fringe)	Yes ___	No	X	Depth (inches):	___

Indicators of wetland hydrology present? N

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

8' above wetland

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 20

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Hillslope | Local relief (concave, convex, none): Convex

Slope (%): 3 | Lat: | Long: | Datum:

Soil Map Unit Name: Ozaukee Silt Loam (7530B2/OzaB) | NWI Classification: none

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic?

SUMMARY OF FINDINGS

(If needed, explain any answers in remarks.)

Hydrophytic vegetation present?	Y		
Hydric soil present?	N	**Is the sampled area within a wetland?**	N
Indicators of wetland hydrology present?	N	If yes, optional wetland site ID:	

Remarks: (Explain alternative procedures here or in a separate report.)

VEGETATION -- Use scientific names of plants.

Tree Stratum (Plot size: 30ft radius)	Absolute % Cover	Dominant Species	Indicator Status
1 *Quercus macrocarpa*	5	Y	FAC
2 *Prunus serotina*	3	Y	FACU
3			
4			
5			
	8	= Total Cover	

Sapling/Shrub stratum (Plot size: 30ft radius)			
1			
2			
3			
4			
5			
	0	= Total Cover	

Herb stratum (Plot size: 5ft radius)			
1 *Poa pratensis*	100	Y	FAC
2			
3			
4			
5			
6			
7			
8			
9			
10			
	100	= Total Cover	

Woody vine stratum (Plot size: 30ft radius)			
1			
2			
	0	= Total Cover	

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 2 (A)

Total Number of Dominant Species Across all Strata: 3 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 66.67% (A/B)

Prevalence Index Worksheet

Total % Cover of:

OBL species	0	x 1 =	0
FACW species	0	x 2 =	0
FAC species	105	x 3 =	315
FACU species	3	x 4 =	12
UPL species	0	x 5 =	0
Column totals	108 (A)		327 (B)

Prevalence Index = B/A = 3.03

Hydrophytic Vegetation Indicators:

- ___ Rapid test for hydrophytic vegetation
- X Dominance test is >50%
- ___ Prevalence index is ≤3.0*
- ___ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ___ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? Y

Remarks: (Include photo numbers here or on a separate sheet)

Mowed lawn with landscaping

SOIL

Sampling Point: 20

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-7	10YR 3/2	100					Silty Clay Loam	
7-20	10YR 3/3	100					Silty Clay	

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- ___ Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- ___ Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: _____

Depth (inches): _____

Hydric soil present? N

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- ___ Saturation (A3)
- ___ Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- ___ Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- ___ Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- ___ Geomorphic Position (D2)
- ___ FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes ___	No	X	Depth (inches):	___
Water table present?	Yes ___	No	X	Depth (inches):	___
Saturation present? (includes capillary fringe)	Yes ___	No	X	Depth (inches):	___

Indicators of wetland hydrology present? N

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

2' above wetland

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site: Nitto | City/County: Pleasant Prairie | Sampling Date: 04/08/2026

Applicant/Owner: Nitto Americas Inc. | State: WI | Sampling Point: 21

Investigator(s): K. Sherfinski, E. Johnson, M. Provost | Section, Township, Range: S27 & 28, T01, R22E

Landform (hillslope, terrace, etc.): Toe slope | Local relief (concave, convex, none): Concave

Slope (%): 0-2 | Lat: | Long: | Datum:

Soil Map Unit Name: Beecher Silt Loam (7298B/BcA) | NWI Classification: E2K

Are climatic/hydrologic conditions of the site typical for this time of the year? Y (If no, explain in remarks)

Are vegetation ____, soil ____, or hydrology ____ significantly disturbed? Are "normal circumstances" present? Yes

Are vegetation ____, soil ____, or hydrology ____ naturally problematic?

SUMMARY OF FINDINGS

(If needed, explain any answers in remarks.)

Hydrophytic vegetation present?	Y		
Hydric soil present?	Y	**Is the sampled area within a wetland?**	Y
Indicators of wetland hydrology present?	Y	If yes, optional wetland site ID:	

Remarks: (Explain alternative procedures here or in a separate report.)

VEGETATION -- Use scientific names of plants.

Tree Stratum (Plot size: 30ft radius)	Absolute % Cover	Dominant Species	Indicator Status
1			
2			
3			
4			
5			
	0	= Total Cover	

Sapling/Shrub stratum (Plot size: 30ft radius)			
1 *Salix interior*	80	Y	FACW
2 *Cornus alba*	5	N	FACW
3			
4			
5			
	85	= Total Cover	

Herb stratum (Plot size: 5ft radius)			
1 *Rhamnus cathartica*	5	Y	FAC
2 *Geum canadense*	1	N	FAC
3 *Taraxacum officinale*	1	N	FACU
4 *Rumex crispus*	1	N	FAC
5			
6			
7			
8			
9			
10			
	8	= Total Cover	

Woody vine stratum (Plot size: 30ft radius)			
1			
2			
	0	= Total Cover	

Dominance Test Worksheet

Number of Dominant Species that are OBL, FACW, or FAC: 2 (A)

Total Number of Dominant Species Across all Strata: 2 (B)

Percent of Dominant Species that are OBL, FACW, or FAC: 100.00% (A/B)

Prevalence Index Worksheet

Total % Cover of:

OBL species	0	x 1 =	0
FACW species	85	x 2 =	170
FAC species	7	x 3 =	21
FACU species	1	x 4 =	4
UPL species	0	x 5 =	0
Column totals	93 (A)		195 (B)

Prevalence Index = B/A = 2.10

Hydrophytic Vegetation Indicators:

- ___ Rapid test for hydrophytic vegetation
- X Dominance test is >50%
- X Prevalence index is ≤3.0*
- ___ Morphological adaptations* (provide supporting data in Remarks or on a separate sheet)
- ___ Problematic hydrophytic vegetation* (explain)

*Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic

Hydrophytic vegetation present? Y

Remarks: (Include photo numbers here or on a separate sheet)

Scrub shrub wetland

SOIL

Sampling Point: 21

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (Inches)	Matrix Color (moist)	%	Redox Features Color (moist)	%	Type*	Loc**	Texture	Remarks
0-9	10YR 2/1						Silty Clay Loam	
9-20	2.5Y 4/2	90	10YR 4/4	10	C	M	Silty Clay	

*Type: C = Concentration, D = Depletion, RM = Reduced Matrix, MS = Masked Sand Grains. **Location: PL = Pore Lining, M = Matrix

Hydric Soil Indicators:

- ___ Histosol (A1)
- ___ Histic Epipedon (A2)
- ___ Black Histic (A3)
- ___ Hydrogen Sulfide (A4)
- ___ Stratified Layers (A5)
- ___ 2 cm Muck (A10)
- X Depleted Below Dark Surface (A11)
- ___ Thick Dark Surface (A12)
- ___ Sandy Mucky Mineral (S1)
- ___ 5 cm Mucky Peat or Peat (S3)
- ___ Sandy Gleyed Matrix (S4)
- ___ Sandy Redox (S5)
- ___ Stripped Matrix (S6)
- ___ Loamy Mucky Mineral (F1)
- ___ Loamy Gleyed Matrix (F2)
- X Depleted Matrix (F3)
- ___ Redox Dark Surface (F6)
- ___ Depleted Dark Surface (F7)
- ___ Redox Depressions (F8)

Indicators for Problematic Hydric Soils:

- ___ Coast Prairie Redox (A16) (**LRR K, L, R**)
- ___ Dark Surface (S7) (**LRR K, L)**
- ___ Iron-Manganese Masses (F12) (**LRR K, L, R**)
- ___ Very Shallow Dark Surface (TF12)
- ___ Other (explain in remarks)

*Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic

Restrictive Layer (if observed):

Type: _____

Depth (inches): _____

Hydric soil present? Y

Remarks:

HYDROLOGY

Wetland Hydrology Indicators:

Primary Indicators (minimum of one is required; check all that apply)

- ___ Surface Water (A1)
- ___ High Water Table (A2)
- X Saturation (A3)
- X Water Marks (B1)
- ___ Sediment Deposits (B2)
- ___ Drift Deposits (B3)
- ___ Algal Mat or Crust (B4)
- ___ Iron Deposits (B5)
- ___ Inundation Visible on Aerial Imagery (B7)
- ___ Sparsely Vegetated Concave Surface (B8)
- X Water-Stained Leaves (B9)
- ___ Aquatic Fauna (B13)
- ___ True Aquatic Plants (B14)
- ___ Hydrogen Sulfide Odor (C1)
- ___ Oxidized Rhizospheres on Living Roots (C3)
- ___ Presence of Reduced Iron (C4)
- ___ Recent Iron Reduction in Tilled Soils (C6)
- ___ Thin Muck Surface (C7)
- ___ Gauge or Well Data (D9)
- ___ Other (Explain in Remarks)

Secondary Indicators (minimum of two required)

- ___ Surface Soil Cracks (B6)
- X Drainage Patterns (B10)
- ___ Dry-Season Water Table (C2)
- ___ Crayfish Burrows (C8)
- ___ Saturation Visible on Aerial Imagery (C9)
- ___ Stunted or Stressed Plants (D1)
- X Geomorphic Position (D2)
- X FAC-Neutral Test (D5)

Field Observations:

Surface water present?	Yes		No	X	Depth (inches):	
Water table present?	Yes		No	X	Depth (inches):	
Saturation present? (includes capillary fringe)	Yes	X	No		Depth (inches):	6

Indicators of wetland hydrology present? Y

Describe recorded data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:


FIGURE 11. WETLAND BOUNDARY MAP

LOCATION: 108th STREET, PLEASANT PRAIRIE

LEGAL DESCRIPTION:

Parcel Nine (9) of CERTIFIED SURVEY MAP NO. 2273, being a redivision of Lot One (1) of Certified Survey Map No. 1971, located in part of the Southwest One-quarter (1/4) of the Northwest One-quarter (1/4) of Section Twenty-seven (27) and in the Southeast One-quarter (1/4) of the Northeast One-quarter (1/4) of Section Twenty-eight (28), in Township One (1) North, Range Twenty-two (22) East, in the Village of Pleasant Prairie, Kenosha County, Wisconsin, recorded in the Office of the Register of Deeds for Kenosha County on October 18, 2001 as Document No. 1239083. Tax Key No. 92-4-122-272-0502





VICINITY MAP
SCALE 1":1000'

LEGEND

1 = DATA POINT

NORTH

GRAPHICAL SCALE (FEET)

0 — 1" = 150' — 300'

WETLAND EXHIBIT

04/15/2026

PINNACLE ENGINEERING GROUP

5850 W. BLUEMOUND ROAD | SUITE 210 | BROOKFIELD, WI 53005 | WWW.PINNACLE-ENGR.COM

PLAN | DESIGN | DELIVER

PEG JOB# 644.00


FIGURE 12. PREVIOUS WETLAND DELINEATION MAP

LOCATION: 108th STREET, PLEASANT PRAIRIE

LEGAL DESCRIPTION:

Parcel Nine (9) of CERTIFIED SURVEY MAP NO. 2273, being a redivision of Lot One (1) of Certified Survey Map No. 1971, located in part of the Southwest One-quarter (1/4) of the Northwest One-quarter (1/4) of Section Twenty-seven (27) and in the Southeast One-quarter (1/4) of the Northeast One-quarter (1/4) of Section Twenty-eight (28), in Township One (1) North, Range Twenty-two (22) East, in the Village of Pleasant Prairie, Kenosha County, Wisconsin, recorded in the Office of the Register of Deeds for Kenosha County on October 18, 2001 as Document No. 1239083.
Tax Key No. 92-4-122-272-0602





VICINITY MAP
SCALE 1":1000'

NORTH

GRAPHICAL SCALE (FEET)
0 1" = 150' 300'

WETLAND EXHIBIT

08/01/16

PINNACLE ENGINEERING GROUP
5850 W. BLUEMOUND ROAD | SUITE 210 | BROOKFIELD, WI 53005 | WWW.PINNACLE-ENGR.COM

PLAN | DESIGN | DELIVER

PEG JOB# 644.00

NR 151 Protective Areas*

Wetland Area	Wetland Class	Protective Area
Wetland A	Moderately Susceptible	50 feet
Wetland B	Moderately Susceptible	50 feet
Wetland C	Less Susceptible	10-30 feet (10% of the average width of the wetland, but no less than 10 feet and no more than 30 feet)
Lakes		50 feet
Outstanding Resource Waters		50 feet
Perennial & Intermittent Streams On 7.5' USGS Survey		50 feet

* When applicable- generally for soil disturbances greater than one acre for non-agricultural purposes, but final authority for protective areas designation and application is with WDNR. NR 151 limits the area of impervious surfaces that can be built within the protective area.

FIGURE 13. NR151 PROTECTIVE AREAS